#### GUARANTEED MAXIMUM PRICE AMENDMENT

EXHIBIT "R" TO CONSTRUCTION MANAO	GEMENT AGREEMENT DATED SEPTEMBER 5, 2024
BETWEEN VILLAGE OF WELLINGTON A	ND <u>WHARTON-SMITH, INC.</u> ("CONSTRUCTION
MANAGER") FOR THE HIGH PRESSURE P	PUMP 9 IMPROVEMENT ("PROJECT") MADE THIS
DAY OF	_ 2026.

#### ARTICLE 1 - GUARANTEED MAXIMIM PRICE

#### 1.1 Guaranteed Maximum Price ("GMP")

Pursuant to Section 3.2 of the Agreement, the Owner and Construction Manager hereby amend the Agreement to establish a Guaranteed Maximum Price. As agreed by the Owner and Construction Manager, the Guaranteed Maximum Price is an amount that the Contract Sum shall not exceed. The Contract Sum consists of the Construction Manager's Fee plus the Cost of the Work, as that term is defined in Article 8 of this Agreement, and the Owner's Contingency. There shall be no Fee on Owner's Contingency unless and until such time as use of the Owner's Contingency is authorized by Owner. Notwithstanding, Manager's insurance and bond costs shall not be subject to Construction Manager's Fee.

- **1.1.1** The Contract Sum is guaranteed by the Construction Manager not to exceed **Two Million One Hundred Thousand Nine Hundred Seventy-One Dollars (\$2,100,971.00)** subject to additions and deductions by Change Order as provided in the Contract Documents. The GMP is subject to Construction Manager's Assumptions and Clarifications to the GMP attached as **Exhibit "R5"**.
- 1.1.2 Allowances included in the Guaranteed Maximum Price are attached as Exhibit "R4".
- 1.1.3 The Guaranteed Maximum Price includes a fixed amount for General Conditions and General Requirements of Six Hundred Eighty-One Thousand One Hundred Five Dollars and No cents (\$681,105.00) as detailed in Exhibit "R7". Construction Manager's General Conditions and General Requirements are fixed and shall not be subject to increase or decrease unless authorized by written Change Order as set forth in the Agreement.
- **1.1.4** The GMP includes an Owner's Contingency in the amount of <u>Ninety-Eight Thousand Eight Hundred Twenty-Nine Dollars (\$98,829.00)</u> to be utilized as set forth in 7.2.3 of the Agreement.
- 1.1.5 It is the intent and understanding of Construction Manager in providing a GMP for this Work, that the Drawings, Plans and Specifications listed in the attached Exhibit "R1" provide for the construction of completed Work by the Construction Manager, including all devices, fasteners, materials or other work not shown in the Drawings and Specifications but which are reasonably inferable therefrom and any and all incidental accessories necessary to make the Work complete and operable in all respects (even if not specified in the description of the Work, but necessary for proper installation and operation of the Work under the Drawings and Specifications), all of which shall be included as part of the Cost of the Work. The expression "reasonably inferable" and similar terms in the Contract Documents shall be interpreted to mean reasonably inferable by a construction manager and general contractor familiar with the Project, having performed extensive Preconstruction Services, and exercising the care, skill and diligence of the Construction Manager by the Contract Documents. Notwithstanding, the foregoing shall not be construed to impose any design responsibility or liability on Construction Manager except where such design responsibility is an existing requirement of Florida law or the Contract Documents.
- **1.2 Schedule of Values.** The Schedule of Values allocating the Contract Sum to the various portions of the Work is attached as **Exhibit "R2"**. The Construction Manager shall not imbalance its Schedule of Values nor artificially inflate any element thereof. Any violation of this provision by the Construction Manager shall constitute a material breach of this Construction Management Agreement. The Schedule of Values shall allocate the entire Guaranteed Maximum Price among the various portions of the Work, except that the Construction Manager's Fee shall be shown as a single separate item.

#### **ARTICLE 2 – CONTRACT TIME**

- 2.1 <u>Date of Commencement</u>. The Work to be performed under this Construction Management Agreement shall be commenced upon the issuance of a Notice to Proceed from Owner ("Date of Commencement").
- 2.2 <u>Contract Time</u>. Construction Manager shall meet all Milestones outlined in **Exhibit "R3"** and the entire Project shall reach Substantial Completion no later than <u>464</u> calendar days from the Date of Commencement. Construction Manager shall reach Final Completion no later than <u>45</u> days from the delivery of the Punch List as outlined in Paragraph 14.04(G) of the General Conditions, subject to any authorized extensions of time as set forth in the Contract Documents. All Work shall be performed in an expeditious manner.
- 2.2.1 Liquidated Damages. The parties to this Agreement agree that time is of the essence in the performance of this Agreement, Substantial Completion of the Work under this Agreement, as defined in Article 1 of the General Conditions shall be no later than the Substantial Completion date set forth in Section 2.2 of this GMP Amendment, subject to authorized extensions of time as set forth in the Article 12 of the General Conditions. In the event the Work is not substantially completed by the completion date stated above, and has not been extended by Change Order, the Owner shall be entitled to collect liquidated damages. Construction Manager and Owner agree that, because of the nature of the Work, the inability of the parties to precisely calculate actual damages for delay and the difficulty of determining these damages, the Construction Manager shall pay the Owner the sum of five hundred dollars (\$500.00) for each calendar day of unexcused delay for failure to achieve Substantial Completion of the Work. Further, Construction Manager and Owner agree that, because of the nature of the Work, the inability of the parties to precisely calculate actual damages for delay and the difficulty of determining these damages, the Construction Manager shall pay the Owner the sum of **two-hundred fifty dollars** (\$250.00) as liquidated damages for each and every calendar day of unexcused delay for failure to achieve Final Completion. It is hereby agreed that the amount of the per diem assessment for liquidated damages for the Construction Manager's failure to achieve Substantial Completion of the Work or Final Completion of the Work within the time specified in this Agreement is not a penalty and not excessive in light of the circumstances known to the parties at the time this Agreement is executed. The Owner's exercise of its right to terminate this Agreement shall not release the Construction Manager from its obligation to pay liquidated damages in the amount set forth herein. Such assessments shall be immediately due and payable to the Owner or, at the Owner's option, may be deducted from future payments that may be due and owing to Construction Manager. Any sums due and payable hereunder by the Construction Manager shall be payable, not as a penalty, but as liquidated damages representing an estimate of delay damages likely to be sustained by the Owner, estimated at or before the time of executing this Agreement. Construction Manager's liability for liquidated damages shall survive completion and termination of the Agreement and are in addition to Owner's other remedies available under the Contract Documents and by law.

#### **ARTICLE 3 - MISCELLANEOUS**

- 3.1 In addition to Construction Manager's and Subcontractor's warranty set forth in 6.19 of the General Conditions, Construction Manager shall be responsible for providing the Extended Warranties as set forth in **Exhibit "R6"**.
- 3.2 The GMP Amendment incorporates the following exhibits:
  - 1. Drawings, plans and specifications listed in the attached List of Drawings attached hereto as Exhibit "R1";
  - 2. Construction Manager's Schedule of Values to be attached as Exhibit "R2";
  - 3. Construction Schedule to be attached as Exhibit "R3";
  - 4. Construction Manager's Allowances to be attached as Exhibit "R4";
  - 5. Construction Manager's Assumptions and Clarifications to the GMP, if any, to be attached as **Exhibit** "R5";

- **6.** List of extended warranties to be attached as **Exhibit "R6"**;
- 7. Construction Manager's Stipulated General Conditions and General Requirements to be attached as Exhibit "R7".
- 8. Submittal Schedule to be attached as Exhibit "R8".

This GMP Amendment and all Exhibits are hereby incorporated as part of the Contract Documents as defined in the Agreement.

- 3.3 Construction Manager shall deliver Payment and Performance Bonds in accordance with Fla. Stat. §255.05 and the forms set forth as **Exhibit "E"** from a surety registered in Florida and acceptable to Owner for the full value of the Guaranteed Maximum Price, plus all change orders.
- 3.4 Other than as modified herein, the terms and conditions set forth in the Agreement, General Conditions and other Contract Documents remain in full force and effect.

[Signatures on following page]

IN WITNESS WHEREOF, Owner and Construction Manager have signed this GMP Amendment. One counterpart each has been delivered to Owner, Construction Manager, and the Engineer. All portions of the Contract Documents have been signed or identified by Owner and Construction Manager or by the Engineer on their behalf.

OWNER:	CONSTRUCTION MANAGER:
VILLAGE OF WELLINGTON	WHARTON-SMITH, INC.
Ву	By
Michael Napoleone, Mayor	Printed Name/Title
Attest:	Attest:
Chevelle Hall, Wellington's Clerk	Printed Name
(SEAL)	(CORPORATE SEAL)
Address for giving notices	Address for giving notices
12300 Forest Hill Boulevard	5210 Hood Road
Wellington, Florida 33414	Palm Beach Gardens, Florida 33418
APPROVED AS TO FORM AND LEGAL SUFFICIENCY	License No. <u>CGC1511243</u> Agent for service of process:
Laurie Cohen, Attorney for Wellington	(If Construction Manager is a corporation, attach evidence of authority to sign.)

### Wharton-Smith, Inc.

#### **CORPORATE RESOLUTION**

I, the undersigned Secretary of Wharton Smith, Inc., a corporation organized and existing under the laws of the State of Florida, do hereby certify that a meeting of the Board of Directors of said corporation, duly held on February 13, 2023, a quorum being present, the following resolution was adopted and entered upon the regular minute book of said corporation, is in accordance with the by-laws and is now in full force and effect to-wit:

The current list of qualifiers to act for the business organization in all matters connected with its contracting business has now been amended to read:

Ronald F. Davoli George E. Smith Timothy S. Smith Stephanie L. Pompeo Patrick J. Hewitt Kenneth E. Marcell III Darin A. Crafton Todd H. O'Donnell Gregory L. Williams Thomas D. Iarossi Andre P. Boagni

I HEREBY certify that the foregoing is a true and exact copy of the resolution adopted by the Board of Directors of this Corporation and that such resolution has not been amended, modified, or revoked and is still in force and effect.

Signed and sealed this 13th day of February 2023. (Seal of Corporation)

Ronald F. Davoli, Director

Stephanie L. Pompeo, Secretary

Page 5



Department of State / Division of Corporations / Search Records / Search by Entity Name /

#### **Detail by Entity Name**

Florida Profit Corporation WHARTON-SMITH, INC.

**Filing Information** 

**Document Number** G94383 FEI/EIN Number 59-2392802 **Date Filed** 04/03/1984 **Effective Date** 04/02/1984 FL

State

**ACTIVE** Status

**Last Event AMENDMENT Event Date Filed** 03/21/2024 **Event Effective Date** NONE

**Principal Address** 750 MONROE RD SANFORD, FL 32771

Changed: 04/25/2006

**Mailing Address** 750 Monroe Road Sanford, FL 32771

Changed: 01/02/2020

**Registered Agent Name & Address** 

CORPORATION SERVICE COMPANY

1201 HAYS STREET

**TALLAHASSEE, FL 32301-2525** 

Name Changed: 10/07/2019

Address Changed: 10/07/2019

Officer/Director Detail

Name & Address

Title President, CEO, Treasurer

SMITH, TIMOTHY S 750 MONROE RD SANFORD, FL 32771

Title Chairman, Asst. Secretary

DAVOLI, RONALD F 750 MONROE RD SANFORD, FL 32771

Title Director

Marcell , Kenneth E, III 750 MONROE RD SANFORD, FL 32771

Title COO

HEWITT, PATRICK J 750 MONROE RD SANFORD, FL 32771

Title COO

CRAFTON, DARIN A 750 MONROE ROAD Sanford, FL 32771

Title Director

O'Donnell, Todd H 750 MONROE RD SANFORD, FL 32771

Title Director

Williams, Gregory L 750 MONROE RD SANFORD, FL 32771

Title CFO, Secretary

POMPEO, STEPHANIE 750 MONROE RD SANFORD, FL 32771

Title Director

BOAGNI, ANDRE 750 MONROE RD SANFORD, FL 32771

#### **Annual Reports**

Report Year	Filed Date
2023	01/03/2023
2024	01/03/2024
2025	01/08/2025

#### **Document Images**

01/08/2025 ANNUAL REPORT	View image in PDF format
03/21/2024 Amendment	View image in PDF format
01/03/2024 ANNUAL REPORT	View image in PDF format
04/21/2023 Amendment	View image in PDF format
02/17/2023 Amendment	View image in PDF format
01/03/2023 ANNUAL REPORT	View image in PDF format
04/12/2022 Amendment	View image in PDF format
01/04/2022 ANNUAL REPORT	View image in PDF format
07/06/2021 AMENDED ANNUAL REPORT	View image in PDF format
01/06/2021 ANNUAL REPORT	View image in PDF format
07/06/2020 Amendment	View image in PDF format
01/31/2020 Amendment	View image in PDF format
01/21/2020 AMENDED ANNUAL REPORT	View image in PDF format
01/02/2020 ANNUAL REPORT	View image in PDF format
10/07/2019 Reg. Agent Change	View image in PDF format
01/02/2019 ANNUAL REPORT	View image in PDF format
01/02/2018 ANNUAL REPORT	View image in PDF format
03/30/2017 AMENDED ANNUAL REPORT	View image in PDF format
01/03/2017 ANNUAL REPORT	View image in PDF format
09/12/2016 AMENDED ANNUAL REPORT	View image in PDF format
01/06/2016 ANNUAL REPORT	View image in PDF format
06/18/2015 AMENDED ANNUAL REPORT	View image in PDF format
05/18/2015 Amendment	View image in PDF format
04/07/2015 AMENDED ANNUAL REPORT	View image in PDF format
02/04/2015 AMENDED ANNUAL REPORT	View image in PDF format
01/05/2015 ANNUAL REPORT	View image in PDF format
12/01/2014 AMENDED ANNUAL REPORT	View image in PDF format
06/23/2014 AMENDED ANNUAL REPORT	View image in PDF format
01/10/2014 ANNUAL REPORT	View image in PDF format
04/12/2013 AMENDED ANNUAL REPORT	View image in PDF format
01/16/2013 ANNUAL REPORT	View image in PDF format
01/10/2012 ANNUAL REPORT	View image in PDF format
04/18/2011 ANNUAL REPORT	View image in PDF format
01/05/2011 ANNUAL REPORT	View image in PDF format
<u>07/08/2010 Amendment</u>	View image in PDF format
01/20/2010 ANNUAL REPORT	View image in PDF format
01/30/2009 ANNUAL REPORT	View image in PDF format
01/23/2008 ANNUAL REPORT	View image in PDF format
03/01/2007 ANNUAL REPORT	View image in PDF format

04/25/2006 ANNUAL REPORT	View image in PDF format
02/17/2006 Amendment	View image in PDF format
01/04/2005 ANNUAL REPORT	View image in PDF format
04/02/2004 ANNUAL REPORT	View image in PDF format
02/17/2003 ANNUAL REPORT	View image in PDF format
02/18/2002 ANNUAL REPORT	View image in PDF format
10/03/2001 Amendment	View image in PDF format
04/19/2001 ANNUAL REPORT	View image in PDF format
04/21/2000 ANNUAL REPORT	View image in PDF format
04/22/1999 ANNUAL REPORT	View image in PDF format
<u>05/13/1998 ANNUAL REPORT</u>	View image in PDF format
<u>05/16/1997 ANNUAL REPORT</u>	View image in PDF format
05/01/1996 ANNUAL REPORT	View image in PDF format
04/07/1995 ANNUAL REPORT	View image in PDF format

Florida Department of State, Division of Corporations

# WTP Membrane Plant #2 (M2) High Pressure Pump 9 Improvements Village of Wellington



#### **GMP Proposal**

November 17, 2025

Presented by Wharton-Smith (CMAR)



Wharton-Smith Contact:

Greg Williams – Vice President gwilliams@whartonsmith.com

Engineer: Kimley-Horn



#### **TABLE OF CONTENTS**

- **SECTION 1 EXECUTIVE SUMMARY**
- SECTION 2 EXHIBIT R1 DRAWINGS, PLANS AND SPECIFICATIONS
- **SECTION 3 EXHIBIT R2 SCHEDULE OF VALUES**
- **SECTION 4 EXHIBIT R3 CONSTRUCTION SCHEDULE**
- SECTION 5 EXHIBIT R4 CONSTRUCTION MANAGER'S ALLOWANCES
- **SECTION 6 EXHIBIT R5 ASSUMPTIONS AND CLARIFICATIONS**
- **SECTION 7 EXHIBIT R6 LIST OF EXTENDED WARRANTIES**
- SECTION 8 EXHIBIT R7 GENERAL CONDITIONS AND GENERAL REQUIREMENTS
- **SECTION 9 EXHIBIT R8 SUBMITTAL SCHEDULE**



#### **SECTION 1 – EXECUTIVE SUMMARY**

November 17, 2025

Mrs. Anjuli Panse, PE Director of Utilities Village of Wellington 12300 Forest Hill Blvd. Wellington, FL 33414

Re: WTP Membrane Plant #2 (M2) High Pressure Pump 9 Improvements

**GMP Proposal** 

Dear Mrs. Panse:

Wharton-Smith is pleased to submit the Guaranteed Maximum Price (GMP) proposal for the WTP Membrane Plant 2 (M2) High Pressure Pump 9 Improvements project. A comprehensive breakdown of material, equipment, subcontractor, and labor is provided in the supporting documentation following this letter. The GMP is valued at \$2,100,971.00 and is broken out as follows:

Base Bid: \$1,704,215Alternate Bid: \$396,756

Please note the following clarifications regarding this proposal:

- 1. Per discussions with the Village of Wellington, the following items are provided in accordance with the CMAR GMP Amendment Guide:
  - a. The Daily Liquidated Damages are as follows:
    - i. \$500 per calendar day for Substantial Completion
    - ii. \$250 per calendar day for Final Completion.
  - b. The GMP includes an Owner Controlled Contingency of \$98,829.00, broken out as follows:
    - i. Base Bid Owner Contingency: \$78,482
    - ii. Alternate Bid Owner Contingency: \$20,347
  - c. Project shall reach Substantial Completion no later than 464 calendar days from the Date of Commencement.
  - d. The following is a list of the competitively bid work packages and the recommended low responsive bidder for each. Please refer to Section 3 for the detailed bid evaluations.
    - i. Master Plant Contractor Wharton-Smith
    - ii. Electrical Loveland Electric
    - iii. Instrumentation & Controls CC Control
  - e. There are no proposed Owner Direct Purchases for this project.
  - f. The proposed GMP is valued at \$2,100,971.00. Refer to Exhibit R2 for the Cost of Work organized by the scope of work bid packages, allowances, Owner's Contingency, and the Construction Manager's Fee.
- 2. The work is in accordance with Kimley-Horn's "Membrane Plant #2 (M2) High Pressure Pump 9 Improvements" conformed documents dated May 2025. Please refer to Section 2 for the Drawings and Specifications.



- 3. The GMP includes work for High Pressure Pump 9 along with the associated piping and Trains 6, 7, and 8 concentrate piping modifications. Pricing for the bid proposals received will remain valid for a period of one hundred and eighty (180) days after the bid date.
- 4. We have included an Owner Controlled Contingency of \$98,829.00. Please note that this contingency is currently shown below the line without fee, fee to be included on contingency usage once brought into the project as approved by the Village of Wellington.
- 5. We have included the following allowances for work items with undefined scopes at this time. Please note that the allowances are currently shown below the line without fee, fee to be included on allowance usage once brought into the project as approved by the Village of Wellington.
  - a. Coatings \$35,000
  - b. Independent Testing \$10,000
  - c. Flow Meter Installation \$130,000
- 6. We have included a performance and payment bond and insurance.
- 7. ERP, FDEP, FDOT, & ROW permit fees are by others.
- 8. Village of Wellington Building Department fees are by others.
- 9. Costs associated with Davis-Bacon Wages & AIS requirements have not been included.
- 10. It is assumed that the Village of Wellington will provide power and water for use during construction and startup at no cost.
- 11. We have not included any costs for Lead/Asbestos Survey nor abatement of any kind.
- 12. Pricing includes no knowledge of buried or concealed conditions beyond what is indicated or shown on documents received to date. Unforeseen conflicts and utilities will be submitted as additional costs.
- 13. All Pricing (Labor, Material, Equipment, Subcontract) is based on current market value with no escalation or inflation adjustment. Duration of Material lead times are based on current market conditions.
- 14. The following is Owner furnished equipment:
  - a. High Pressure Pump 9, Motor and Can
  - b. Cartridge Filter Housing
  - c. Micron Filters
  - d. VFD
- 15. Owner furnished Equipment is subject to Engineer's shop drawing submittal review and approval. The Equipment services and features specified within Bid Documents are to be verified by Direct Purchaser prior to their system integration by Contractor.
- 16. We have included administrative costs to coordinate field services with Owner furnished equipment vendors. This is limited to communication and scheduling. Wharton Smith and subcontractors are not responsible for delays associated with these vendors.
- 17. Procurement, review, submission, and copies of Operation and Maintenance Manuals for Owner Furnished Equipment is excluded. It is the Owner's responsibility to coordinate this effort and share all pertinent information with Wharton Smith in a timely manner.
- 18. All work required per Specification Section 02670 *Flushing, Testing and Disinfection* is excluded as no discharge and bacteriological sampling locations have been identified in the bid drawings. Wharton Smith responsibility will be limited to swabbing all new piping to be installed on the Raw Water Feed System. If required, additional form of disinfection, temporary piping, flushing, and bacteriological sampling will be coordinated with the Owner and submitted as additional cost.
- 19. Spare Parts for all Owner Furnished Equipment are excluded.
- 20. Factory testing for all Owner Furnished Equipment is excluded. This includes coordinating, reviewing test reports, and submission.



- 21. Vibration testing costs per Specification Section 11936 *Vertical Turbine High Pressure Pump* and Specification Section 13080 *Vibration and Alignment*, are excluded as these costs were carried by Afton for Owner Furnished HPP 9. Wharton Smith responsibility will be limited to coordinating with Afton.
- 22. Part 1 of Specification Sections 16480 and 16485/16495 is excluded since the manufacturer's services were included in the direct Purchase Order from the Village of Wellington to Schneider.
- 23. Offloading and storage of Owner Furnished Equipment is excluded.
- 24. Part 3.1 of Specification Section 16485/16495 states that a 10% payment retainage will be released to Contractor upon final acceptance of the work. Per Executed CMAR Agreement, a 5% retainage will be held.
- 25. Additional material cost or delays to the Project Schedule due to Owner or Owner's contracted Supplier will be assessed and Contractor reserves the right to submit any applicable claims within the Terms and Conditions of the Contract.
- 26. It is assumed that the 10" 90° bends can be modified and reinstalled, therefore, we have included cost for these modifications per General Note No. 9 on Sheet M-2. If for reasons outside of our control, new 90° bends are required, a Contingency Authorization Request will be submitted for the additional cost.
- 27. Cost to modify existing grating is included as shown in the bid documents. Additional modifications will be submitted as additional cost.
- 28. As requested by the Village of Wellington, cost to furnish the micron filters is not included.
- 29. Coiling, hanging, or arranging of existing wiring and other items present within existing PLC-RO2 or PCPMOVRO2 is excluded.
- 30. Contractor has excluded cost to perform post-construction inspection referenced in Spec Section 01700-1.9. It is the Owner's responsibility to send notification of any deficiencies concerning material, equipment, and workmanship furnished by Wharton Smith within the warranty period established in the bid documents. Deficiencies relating to Owner Furnished Equipment will be the sole responsibility of the Owner.
- 31. It is assumed that Engineer and Owner will review and return submittals within 14 calendar days. RFIs and resubmittals shall be returned within 7 calendar days.
- 32. It is assumed that Contractor will utilize the Owner's existing gantry crane and that the crane's capacity is sufficient for the cartridge filter and HPP. Should the gantry crane capacity not be sufficient, Contractor will seek alternate method of hoisting for additional cost.
- 33. Pricing only includes materials and equipment specified in the bid documents. As there are no references to the Village's Approved Product List (APL), those approved products have been excluded.
- 34. Please refer to Section 4 for the proposed GMP schedule. Please note that the P6 schedule is referenced in "work days" as the program automatically accounts for weekends and holidays. The contract time is expressed in "calendar days". 508 calendar days from Notice of Commencement to Final Completion indicated equates to the 522 work days shown in the P6 schedule. Our current estimated duration of onsite construction is 8 months.

As always, I am available to discuss at your earliest convenience.

Respectfully,

Eliana Corie

Project Manager

Wharton-Smith, Inc.



#### **SECTION 2 – EXHIBIT R1 DRAWINGS, PLANS AND SPECIFICATIONS**

#### Technical Specifications

# Water Treatment Plant (WTP) Membrane Plant #2 (M2) High Pressure Pump No. 9 Improvements

Prepared For: Village of Wellington

Prepared By: Kimley-Horn and Associates, Inc. 1920 Wekiva Way, Suite 200 West Palm Beach FL 33411 Ca 00000696

April 2025 PROJECT NO. 144957081



#### **SECTION 01000**

#### TABLE OF CONTENTS

<u>Division</u>	<u>Section</u>	<u>Title</u>
1		GENERAL REQUIREMENTS
	01010	Summary of Work
	01300	Submittals
	01410	Testing Laboratory Services
	01600	Material and Equipment
	01700	Project Closeout
	01720	Project Record Drawings
_	01730	Operation and Maintenance Manuals
2		SITE WORK
	02065	Demolition
_	02670	Flushing, Testing and Disinfection
3		CONCRETE
	03100	Concrete Formwork
	03200	Concrete Reinforcement
	03300	Cast-in-Place Concrete
4		MASONRY – NOT USED
5		METALS
	05500	Miscellaneous Metals
	05700	Anchors, Fasteners and Injection Adhesives
6		WOOD AND PLASTICS – NOT USED
7		THERMAL AND MOISTURE PROTECTION – NOT USED
8		DOORS AND WINDOWS – NOT USED
9		FINISHES
	09900	Painting
10		SPECIALTIES
	10400	Identifying Devices
11		EQUIPMENT
	11245	Cartridge Filters - (Owner Furnished)
	11280	Control Valves
	11936	Vertical Turbine High Pressure Pump - (Owner Furnished)
12		FURNISHINGS – NOT USED
13		SPECIAL CONSTRUCTION
	13080	Vibration and Alignment
14	<del>-</del>	CONVEYING SYSTEMS – NOT USED
15		MECHANICAL
13		IVILCHANICAL

TABLE OF CONTENTS 01000

	15100	Piping, Valves, and Fittings
16		ELECTRICAL
	16010	Basic Electrical Requirements
	16050	Basic Electrical Materials
	16110	Raceways
	16120	Conductors
	16405	Electric Motors
	16450	Grounding
	16480	Low Voltage Motor Control
	16485	Variable Frequency Drives – (Owner Furnished)
	16950	Electrical Testing
	17301	Instrumentation and Controls

01000 TABLE OF CONTENTS

# MEMBRANE PLANT #2 (M2) HIGH PRESSURE PUMP 9 IMPROVEMENTS

PREPARED FOR

# VILLAGE OF WELLINGTON MAY 2025






#### **VILLAGE COUNCIL**

MAYOR
VICE MAYOR
COUNCILMAN
COUNCILWOMAN
COUNCILWOMAN

CONTRACT MODIFICATIONS

**REVISIONS** 

VILLAGE MANAGER ASSISTANT VILLAGE MANAGER DEPUTY VILLAGE MANAGER UTILITY DIRECTOR




MICHAEL J. NAPOLEONE TANYA SISKIND JOHN T. MCGOVERN MARIA S. ANTUÑA AMANDA SILVESTRI

JIM BARNES ED DE LA VEGA TANYA W. QUICKEL ANJULI PANSE, P.E.

PROJECT LOCATION

VOW WTP 1100 WELLINGTON TRACE WELLINGTON, FL 33414



**LOCATION MAP** 

PALM BEACH COUNTY

N.T.S. or AS NOTED

	SHEET LIST			
Sheet Number Sheet Title				
G-1	COVER SHEET			
G-2	SITE KEY MAP, PROCESS AREA PLAN AND GENERAL NOTES			
G-3	PROCESS FLOW DIAGRAM			
M-1	HPP ROOM DEMOLITION PLAN AND SECTIONS			
M-2	HPP ROOM PROPOSED PLAN AND SECTIONS			
M-3	MECHANICAL DETAILS			
M-4	NF ROOM DEMOLITION PLAN AND SECTIONS			
M-5	NF ROOM PROPOSED PLAN AND SECTIONS			
M-6	CONSTRUCTION DETAILS			
E-1	ELECTRICAL LEGEND AND SYMBOLS			
E-2	ELECTRICAL GENERAL NOTES AND SPECIFICATIONS			
E-3	MEMBRANE BUILDING 2 MODIFIED ELECTRICAL PLAN			
E-4	MCC-1002 MODIFIED ONE-LINE DIAGRAM			
E-5	ELECTRICAL RISER DIAGRAMS AND SCHEDULES			
E-6	ELECTRICAL SCHEMATICS			
E-7	ELECTRICAL STANDARD DETAILS			
I-1	INSTRUMENTATION LEGEND & SYMBOLS			
I-2	MODIFIED HIGH PRESSURE PUMP P&ID			
I-3	MODIFIED MEMBRANE TRAIN P&ID			
I-4	EXISTING PCPMOVRO2 MODIFICATION			
I-5	INSTRUMENTATION STANDARD DETAILS			

**CONFORMED SET** 

VICINITY MAP

N.T.S. or AS NOTED

10/16/24 NPOE

DATE BY

Kimley» Horn

© 2025 KIMLEY-HORN AND ASSOCIATES, INC. 1920 WEKIVA WAY SUITE 200, WEST PALM BEACH, FL 33411 PHONE: 561-845-0665 FAX: 561-863-8175 WWW.KIMLEY-HORN.COM REGISTRY NO. 696 KHA PROJECT
144957081

DATE
MAY 2025

SCALE AS SHOWN

DESIGNED BY NPOB

RAWN BY

HIGH PRESSURE PUMP NO. 9 IMPROVEMENTS

PREPARED FOR
VILLAGE OF WELLINGTON

No 84908

\*

STATE OF

STATE OF

ON A L

MINIMUM MINIM

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY


SHEET NUMBER

**COVER SHEET** 

G-1

ON THE DATE ADJACENT TO THE SEAL.
THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

OF 21



DRAWN BY



### PROCESS AREA PLAN

VSF VANSTONE FLANGE

IS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY

CONCENTRATE PIPING TO DIW CIP SYSTEM SUPPLY PIPING CIP SYSTEM RETURN PIPING

> → PERMEATE FROM TRAIN NO. 6 TO CLEARWELL

-PERMEATE FROM TRAIN NO. 7 TO CLEARWELL NO. 4 DEGASIFIERS

RECOVERY BASIN

-FLUSH WATER TO BACKWASH

PERMEATE FROM TRAIN

NO. 8 TO CLEARWELL NO. 4 DEGASIFIERS

NO. 4 DEGASIFIERS

#### **GENERAL NOTES:**

- 1. CONTRACTOR SHALL COORDINATE WORK WITH THE OWNER AND PROVIDE ONE WEEK NOTICE PRIOR TO DEMOLITION.
- 2. CONTRACTOR SHALL CONFIRM SIZE, MATERIAL, AND LOCATION OF ALL MECHANICAL EQUIPMENT AND FIELD VERIFY EXISTING CONDITIONS AND DIMENSIONS TO ACCOMMODATE PROPOSED EQUIPMENT AS REQUIRED.
- 3. THE TYPE, SIZE, AND MATERIAL OF M2 PROCESS PIPING AND FITTINGS IS INDICATED ON THE DRAWINGS. IF NOT INDICATED OR WHERE PIPING OR FITTINGS OF DIFFERING SIZE, MATERIAL, OR RATING ARE IDENTIFIED IN THE FIELD AND ARE TO BE CONNECTED (NEW OR EXISTING), THE CONTRACTOR SHALL SUPPLY AND INSTALL ALL NECESSARY FITTINGS, TRANSITIONS, AND OR ADAPTORS TO FACILITATE EXISTING AND OR PROPOSED
- 5. CONTRACTOR SHALL VERIFY ALL DIMENSIONS PRIOR TO ORDERING MATERIALS AND CONSTRUCTION.
- 6. CONTRACTOR SHALL FIELD LOCATE EXISTING UTILITIES AND SHALL PROTECT AND MAINTAIN THE INTEGRITY OF ANY AND ALL EXISTING UNDERGROUND UTILITIES. THE CONTRACTOR WILL BE RESPONSIBLE FOR ANY AND ALL DAMAGES DUE TO CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE EXISTING UTILITIES. CONTRACTOR WILL BE REQUIRED TO REPAIR/REPLACE ANY DAMAGED UTILITIES TO OWNERS SATISFACTION.
- 7. ALL AREAS IMPACTED BY CONSTRUCTION SHALL BE RESTORED PER SPECIFICATIONS
- 8. ELEVATION SHOWN HEREIN REFERENCE TO NGVD'29. CONVERSION FROM NGVD 1929 TO NAVD 1988 IS AS FOLLOWS: (NGVD 1929) 1.471 = (NAVD 1988)

SCALE: 1" = 50'



BUTTERFLY VALVE NANOFILTRATION CONCENTRATE CL, © CONST CENTERLINE NANOFILTRATION FEEDWATER CONTRUCT NANOFILTRATION INTERSTAGE CFV CARTRIDGE FILTER VESSEL CLEANING SYSTEM RETURN

SCALE: 1" = 10'

NANOFILTRATION PERMEATE ON CENTER CLEANING SYSTEM SUPPLY SAMPLE LINE CLEANING SYSTEM WASTE STAINLESS STEEL LUG STYLE T.O. TOP OF LONG RADIUS

BID ALTERNATE WORK




$\triangle$	CONTRACT MODIFICATIONS	10/16/24	NPOB
No.	REVISIONS	DATE	BY

© 2025 KIMLEY-HORN AND ASSOCIATES, INC. 1920 WEKIVA WAY SUITE 200, WEST PALM BEACH, FL 33411 PHONE: 561-845-0665 FAX: 561-863-8175 WWW.KIMLEY-HORN.COM REGISTRY NO. 696

#### KHA PROJECT HIGH PRESSURE PUMP NO. 9 144957081 DATE **IMPROVEMENTS** MAY 2025 CALE AS SHOWN PREPARED FOR ESIGNED BY NPC

PALM BEACH COUNTY

VILLAGE OF WELLINGTON




# SITE KEY MAP, PROCESS AREA PLAN AND GENERAL NOTES


I THE DATE ADJACENT TO THE SEAL. E SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

G-2

SHEET NUMBER


OF 21





### M2 H.P.P. ROOM DEMOLITION PLAN

24x36 SHEET SIZE:  $\frac{1}{2}$ "= 1'-0" 11x17 SHEET SIZE:  $\frac{1}{4}$ "= 1'-0"





PALM BEACH COUNTY

#### **GENERAL NOTES:**

- 1. CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS.
- 2. ALL PIPING SHALL BE SCH. 10 316 SST, U.O.N. ALL GROOVES SHALL BE SCH. 40 CUT GROOVES
- 3. CONTRACTOR SHALL COORDINATE WORK WITH THE OWNER AND PROVIDE 48-HOURS NOTICE PRIOR TO DEMOLITION.
- 4. CONTRACTOR SHALL FIELD LOCATE EXISTING PIPING, EQUIPMENT, AND STRUCTURAL/SUPPORT COMPONENTS AND SHALL PROTECT AND MAINTAIN THE INTEGRITY OF ANY AND ALL EXISTING PIPING, EQUIPMENT, AND STRUCTURAL/SUPPORT COMPONENTS. THE CONTRACTOR WILL BE RESPONSIBLE FOR ANY AND ALL DAMAGES DUE TO CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE EXISTING COMPONENTS. CONTRACTOR WILL BE REQUIRED TO REPAIR/REPLACE ANY DAMAGED COMPONENTS TO OWNERS SATISFACTION.
- 5. ALL AREAS IMPACTED BY CONSTRUCTION SHALL BE RESTORED PER SPECIFICATIONS.
- 6. COORDINATE WITH THE OWNER AND ENGINEER FOR ITEMS TO BE RETURNED AFTER DEMOLITION. THE OWNER RESERVES THE RIGHT TO DESIGNATE ANY ITEMS FOR SALVAGE PER SPECIFICATION SECTION 02065. ALL MATERIALS TO BE DEMOLISHED ARE TO BE DISPOSED OF LEGALLY OFF—SITE.
- 7. ALL STAINLESS STEEL PIPING AND FITTINGS SHALL BE FINAL PICKLED AND PASSIVATED U.O.N, WELDED 316/316L SCHEDULE 10S MINIMUM. ALL STAINLESS STEEL PIPING AND FITTINGS ABOVE THE PIPE TRENCH SHALL ALSO BE ELECTROPOLISHED.
- 8. EXIST. DISCHARGE VALVES TO BE ROTATED 90° TO ALLOW FOR INSTALLATION OF ACTUATOR AND STEM EXTENSION. GRATING PENETRATION SHALL BE CUT AND BANDED FOR ACTUATOR TO BE INSTALLED ABOVE TRENCH.

9. CONTRACTOR IS PERMITTED TO MODIFY EXIST. 10" 90° BENDS FOR RE—USE. FITTINGS SHALL BE RE—WELDED BY CERTIFIED WELDER. FITTINGS SHALL BE PICKLED <u>AND</u> PASSIVATED, <del>ELECTROPOLISHED</del> PRIOR TO RE—INSTALL. WELDED BOSSES SHALL BE PROVIDED FOR RE—INSTALLATION OF GAUGE ASSEMBLIES.

**CONFORMED SET** 

主					
MOV.					
Set:					
Sheet					
<u>•</u>					
Dan					
Sornu,					
By: C	$\triangle$	CONTRACT MODIFICATIONS	10/16/24	NPOB	
Plotted	No.	REVISIONS	DATE	BY	

# Kimley» Horn

© 2025 KIMLEY-HORN AND ASSOCIATES, INC.

1920 WEKIVA WAY SUITE 200, WEST PALM BEACH, FL 33411

PHONE: 561-845-0665 FAX: 561-863-8175

WWW.KIMLEY-HORN.COM REGISTRY NO. 696

KHA PROJECT
144957081

DATE
MAY 2025

SCALE AS SHOWN
DESIGNED BY NPOB

CHECKED BY NPOB

DRAWN BY

# HIGH PRESSURE PUMP NO. 9 IMPROVEMENTS

PREPARED FOR VILLAGE OF WELLINGTON

# HPP ROOM DEMOLITION PLAN AND SECTIONS

ON THE DATE ADJACENT TO THE SEAL.
THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.


IS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY

SHEET NUMBER

OF 21

M-1

Page 22




### M2 H.P.P. ROOM IMPROVEMENTS PLAN

24x36 SHEET SIZE:  $\frac{1}{2}$ "= 1'-0" 11x17 SHEET SIZE:  $\frac{1}{4}$ "= 1'-0"





PALM BEACH COUNTY



<u>M-2</u>

#### M2 H.P.P. 6,7, AND 8 IMPROVEMENTS SECTION

24×36 SHEET SIZE:  $\frac{1}{2}$ "= 1'-0" 11×17 SHEET SIZE:  $\frac{1}{4}$ "= 1'-0"

#### **GENERAL NOTES:**

- 1. CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS.
- 2. ALL PIPING SHALL BE SCH. 10 316 SST, U.O.N. ALL GROOVES SHALL BE SCH. 40 CUT GROOVES
- 3. CONTRACTOR SHALL COORDINATE WORK WITH THE OWNER AND PROVIDE 48-HOURS NOTICE PRIOR TO DEMOLITION
- 4. CONTRACTOR SHALL FIELD LOCATE EXISTING PIPING, EQUIPMENT, AND STRUCTURAL/SUPPORT COMPONENTS AND SHALL PROTECT AND MAINTAIN THE INTEGRITY OF ANY AND ALL EXISTING PIPING, EQUIPMENT, AND STRUCTURAL/SUPPORT COMPONENTS. THE CONTRACTOR WILL BE RESPONSIBLE FOR ANY AND ALL DAMAGES DUE TO CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE EXISTING COMPONENTS. CONTRACTOR WILL BE REQUIRED TO REPAIR/REPLACE ANY DAMAGED COMPONENTS TO OWNERS SATISFACTION.
- 5. ALL AREAS IMPACTED BY CONSTRUCTION SHALL BE RESTORED PER SPECIFICATIONS.
- 6. COORDINATE WITH THE OWNER AND ENGINEER FOR ITEMS TO BE RETURNED AFTER DEMOLITION. THE OWNER RESERVES THE RIGHT TO DESIGNATE ANY ITEMS FOR SALVAGE PER SPECIFICATION SECTION 02065. ALL MATERIALS TO BE DEMOLISHED ARE TO BE DISPOSED OF LEGALLY OFF—SITE.
- 7. ALL STAINLESS STEEL PIPING AND FITTINGS SHALL BE FINAL PICKLED AND PASSIVATED U.O.N, WELDED 316/316L SCHEDULE 10S MINIMUM. ALL STAINLESS STEEL PIPING AND FITTING ABOVE THE PIPE TRENCH SHALL ALSO BE ELECTROPOLISHED.
- 8. EXIST. DISCHARGE VALVES TO BE ROTATED 90° TO ALLOW FOR INSTALLATION OF ACTUATOR AND STEM EXTENSION. GRATING PENETRATION SHALL BE CUT AND BANDED FOR ACTUATOR TO BE INSTALLED ABOVE TRENCH.
- 9. CONTRACTOR IS PERMITTED TO MODIFY EXIST. 10" 90° BENDS FOR RE-USE. FITTINGS SHALL BE RE-WELDED BY CERTIFIED WELDER. FITTINGS SHALL BE PICKLED AND PASSIVATED, ELECTROPOLISHED PRIOR TO RE-INSTALL. WELDED BOSSES SHALL BE PROVIDED FOR RE-INSTALLATION OF GAUGE ASSEMBLIES.
- 10. CUT AND PENETRATE ALUMINUM GRATING AS REQUIRED TO ACCOMMODATE INSTALLATION. BAND NEW OPENINGS AT PENETRATIONS. COORDINATE WITH OWNER AND ENGINEER.
- 11. FLANGES SHALL BE ANSI 150#, U.O.N.

**CONFORMED SET** 

CONTRACT MODIFICATIONS	10/16/24 NPOE
REVISIONS	DATE BY

# Kimley» Horn

© 2025 KIMLEY-HORN AND ASSOCIATES, INC. 1920 WEKIVA WAY SUITE 200, WEST PALM BEACH, FL 33411 PHONE: 561-845-0665 FAX: 561-863-8175 WWW.KIMLEY-HORN.COM REGISTRY NO. 696

# KHA PROJECT 144957081 DATE MAY 2025 SCALE AS SHOWN DESIGNED BY NPOB

CHECKED BY NPOB

DRAWN BY

## HIGH PRESSURE PUMP NO. 9 IMPROVEMENTS

PREPARED FOR
VILLAGE OF WELLINGTON


THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY


SHEET NUMBER

HPP ROOM PROPOSED PLAN AND SECTIONS

M-2


ON THE DATE ADJACENT TO THE SEAL. THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.






#### **GENERAL NOTES**

- 2. ALL PIPING SHALL BE SCH. 10 316 SST, U.O.N. ALL GROOVES SHALL BE SCH. 40 CUT GROOVES
- 3. CONTRACTOR SHALL COORDINATE WORK WITH THE OWNER AND PROVIDE 48-HOURS NOTICE PRIOR TO DEMOLITION.
- EXISTING PIPING, EQUIPMENT, AND STRUCTURAL/SUPPORT COMPONENTS. THE CONTRACTOR WILL BE RESPONSIBLE FOR ANY AND ALL DAMAGES DUE TO CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE EXISTING COMPONENTS. CONTRACTOR WILL BE REQUIRED TO REPAIR/REPLACE ANY DAMAGED COMPONENTS TO OWNERS SATISFACTION.
- 5. ALL AREAS IMPACTED BY CONSTRUCTION SHALL BE RESTORED PER SPECIFICATIONS.
- 6. COORDINATE WITH THE OWNER AND ENGINEER FOR ITEMS TO BE RETURNED AFTER DEMOLITION. THE OWNER RESERVES THE RIGHT TO DESIGNATE ANY ITEMS FOR SALVAGE PER SPECIFICATION SECTION 02050. ALL MATERIALS TO BE DEMOLISHED ARE TO BE DISPOSED OF LEGALLY OFF-SITE.
- 8. ALL BUTTERFLY VALVES ARE TO BE INSTALLED WITH THE SHAFT IN THE SAME PLANE, OR PARALLEL, WITH ANY BEND IN THE PIPE ATTACHED TO EITHER SIDE OF THE VALVE. A TEE IS CONSIDERED A BEND.





© 2025 KIMLEY-HORN AND ASSOCIATES, INC. 1920 WEKIVA WAY SUITE 200, WEST PALM BEACH, FL 33411 PHONE: 561-845-0665 FAX: 561-863-8175 WWW.KIMLEY-HORN.COM REGISTRY NO. 696


KHA PROJECT 144957081 DATE MAY 2025 CALE AS SHOWN ESIGNED BY NPC

PALM BEACH COUNTY

DRAWN BY

### HIGH PRESSURE PUMP NO. 9 **IMPROVEMENTS**

PREPARED FOR VILLAGE OF WELLINGTON





# NF ROOM DEMOLITION PLAN AND SECTIONS


SHEET NUMBER OF 21

I THE DATE ADJACENT TO THE SEAL. E SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES

IS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY









#### **GENERAL NOTES**

- 1. CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS.
- 2. ALL PIPING SHALL BE SCH. 10 316 SST, U.O.N. ALL GROOVES SHALL BE SCH. 40 CUT GROOVES
- 3. CONTRACTOR SHALL COORDINATE WORK WITH THE OWNER AND PROVIDE 48-HOURS NOTICE PRIOR TO DEMOLITION.
- 4. CONTRACTOR SHALL FIELD LOCATE EXISTING PIPING, EQUIPMENT, AND STRUCTURAL/SUPPORT COMPONENTS AND SHALL PROTECT AND MAINTAIN THE INTEGRITY OF ANY AND ALL EXISTING PIPING, EQUIPMENT, AND STRUCTURAL/SUPPORT COMPONENTS. THE CONTRACTOR WILL BE RESPONSIBLE FOR ANY AND ALL DAMAGES DUE TO CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE EXISTING COMPONENTS. CONTRACTOR WILL BE REQUIRED TO REPAIR/REPLACE ANY DAMAGED COMPONENTS TO OWNERS SATISFACTION.
- 5. ALL AREAS IMPACTED BY CONSTRUCTION SHALL BE RESTORED PER SPECIFICATIONS.
- 6. COORDINATE WITH THE OWNER AND ENGINEER FOR ITEMS TO BE RETURNED AFTER DEMOLITION. THE OWNER RESERVES THE RIGHT TO DESIGNATE ANY ITEMS FOR SALVAGE PER SPECIFICATION SECTION 02050. ALL MATERIALS TO BE DEMOLISHED ARE TO BE DISPOSED OF LEGALLY OFF-SITE.
- 8. ALL BUTTERFLY VALVES ARE TO BE INSTALLED WITH THE SHAFT IN THE SAME PLANE, OR PARALLEL, WITH ANY BEND IN THE PIPE ATTACHED TO EITHER SIDE OF THE VALVE. A TEE IS CONSIDERED A BEND.





© 2025 KIMLEY-HORN AND ASSOCIATES, INC. 1920 WEKIVA WAY SUITE 200, WEST PALM BEACH, FL 33411 PHONE: 561-845-0665 FAX: 561-863-8175 WWW.KIMLEY-HORN.COM REGISTRY NO. 696

KHA PROJECT 144957081 DATE MAY 2025 CALE AS SHOWN ESIGNED BY NPO


CHECKED BY NPOB

PALM BEACH COUNTY

DRAWN BY

## HIGH PRESSURE PUMP NO. 9 **IMPROVEMENTS**


PREPARED FOR VILLAGE OF WELLINGTON




# NF ROOM PROPOSED PLAN AND SECTIONS

I THE DATE ADJACENT TO THE SEAL. E SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

IS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY






ADJUSTABLE PIPE SUPPORT APPROX. DIMENSIONS IN INCHES						
PIPE SIZE	А	В	С	D MIN.	D MAX.	
2 1/2	2 1/2	1 1/2	9	8	11 1/2	
3	2 1/2	1 1/2	9	8 1/4	11 3/4	
3 1/2	2 1/2	1 1/2	9	8 1/2	12	
4	3	2 1/2	9	10 1/4	14	
6	3	2 1/2	9	11 5/8	15 1/4	
8	3	2 1/2	9	13 5/8	16 1/2	
10	3	2 1/2	9	14 5/8	18 1/4	
12	3	2 1/2	9	15 5/8	19 3/4	
14	4	3	11	18 5/8	20 3/4	

#### NOTE


1. UNDER VALVES, METERS OR OTHER SPECIAL APPURTENANCES. A FABRICATED SUPPORT PIECE MAY BE UTILIZED AS ACCEPTABLE TO ENGINEER



STANCHION PIPE SUPPORT DETAIL
Scale: N.T.S.







PRESSURE INDICATOR DETAIL
Scale: N.T.S.

**CONFORMED SET** 

No. REVISIONS DATE BY

Kimley»Horn

© 2025 KIMLEY-HORN AND ASSOCIATES, INC. 1920 WEKIVA WAY SUITE 200, WEST PALM BEACH, FL 33411 PHONE: 561-845-0665 FAX: 561-863-8175 WWW.KIMLEY-HORN.COM REGISTRY NO. 696 KHA PROJECT 144957081 DATE MAY 2025 SCALE AS SHOWN

ESIGNED BY NPO


PALM BEACH COUNTY

DRAWN BY

HIGH PRESSURE PUMP NO. 9 IMPROVEMENTS

PREPARED FOR
VILLAGE OF WELLINGTON

FLORIDA STA



HIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY

SHEET NUMBER


CONSTRUCTION DETAILS

M-6

ON THE DATE ADJACENT TO THE SEAL.
THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

OF 21

age 27



#### **GENERAL NOTES AND SPECIFICATIONS:**

- THE SCOPE OF WORK SHALL BE AS DESCRIBED IN SPECIFICATION SECTION 16010 AND AS SHOWN ON DRAWINGS.
- 2. THE CONTRACTOR SHALL PROVIDE ALL MATERIALS AND LABOR TO INSTALL THE ELECTRICAL SYSTEMS AS INDICATED ON THE DRAWINGS. ITEMS NOT SHOWN BUT OBVIOUSLY NECESSARY FOR
- 3. PRIOR TO SUBMITTING A BID, THE CONTRACTOR SHALL CONTACT SQUARE D/SCHNEIDER ELECTRIC TO VERIFY THEIR SCOPE OF SERVICES. ANY WORK SPECIFIED IN THESE DRAWINGS AND SPECIFICATIONS AND NOT FURNISHED BY THE OWNER FURNISHED EQUIPMENT PURCHASE FROM SQUARE D SHALL BE FURNISHED BY THE CONTRACTOR. THE INTENTION IS FOR THE CONTRACTOR TO RETAIN COMPLETE RESPONSIBLITY FOR COMPLIANCE WITH THE DRAWINGS AND SPECIFICATIONS. THIS INCLUDES ALL SCHEDULING, START-UP, TESTING AND TRAINING SERVICES REQUIRED TO INSTALL OWNER PURCHASED EQUIPMENT FOR A WORKING SYSTEM COMPLETE IN PLACE AND IN COMPLIANCE WITH THESE DRAWINGS AND THE SPECIFICATIONS.
- 4. DRAWINGS THAT ILLUSTRATE EXISTING STRUCTURES. PIPING, ELECTRICAL AND EQUIPMENT ARE BASED UPON RECORD DRAWINGS AVAILABLE UPON REQUEST FOR GENERAL INFORMATIONAL PURPOSES ONLY, LOCATION, SIZE AND ALIGNMENT OF EXISTING FACILITIES HAVE BEEN DETERMINED FROM AVAILABLE RECORDS, THIS INFORMATION IS FURNISHED AS A GUIDE FOR THE CONTRACTOR. THE ENGINEER AND THE OWNER DO NO GUARANTEE THE ACCURACY OF THIS DATA. THE CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR DETERMINING THE LOCATION AND PROTECTING ALL TYPES OF UTILITIES AND STRUCTURES ENCOUNTERED DURING THE COURSE OF OPERATION ON THIS PROJECT. FIELD OBSERVATIONS INDICATE THAT FIELD CONDITIONS DO NOT FULLY MATCH THE ABOVE REFERENCED RECORD DRAWINGS.
- 5. THE INSTALLATION SHALL BE IN ACCORDANCE WITH THE 2020 NATIONAL ELECTRICAL CODE (NFPA 70), 2024 ELECTRICAL SAFETY IN THE WORKPLACE (NFPA 70E), LOCAL CODES, VILLAGE CODES, ALL PALM BEACH COUNTY CODES AND 2023 FLORIDA BUILDING CODE INCLUDING PALM BEACH COUNTY AMENDMENTS.
- 6. THE CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS, INSPECTIONS AND APPROVALS AND TO INCLUDE ALL FEES AS PART OF HIS BID IF NOT OTHERWISE NOTED.
- 7. THE CONTRACTOR SHALL COORDINATE THE WORK WITH THE ENGINEER AND OWNER.
- 8. THE CONTRACTOR SHALL, BEFORE SUBMITTING A BID, VISIT THE SITE OF THE PROJECT AND BECOME FAMILIAR WITH THE EXISTING CONDITIONS. NO ALLOWANCE WILL BE MADE FOR EXISTING CONDITIONS OR FAILURE OF THE CONTRACTOR TO OBSERVE THEM.
- 9. ALL EQUIPMENT AND MATERIAL SHALL BE UNUSED AND U.L. LISTED. ALL REFERENCES TO A PARTICULAR MANUFACTURER ARE GIVEN ON AN "APPROVED EQUAL" BASIS, UNLESS SPECIFICALLY NOTED OTHERWISE.
- 10. THE CONTRACTOR IS RESPONSIBLE TO TEST ALL SYSTEMS INSTALLED OR MODIFIED UNDER THIS PROJECT AND REPAIR OR REPLACE ALL DEFECTIVE WORK TO THE SATISFACTION OF THE ENGINEER AND OWNER.
- 11. ALL EQUIPMENT FURNISHED AND INSTALLED BY THE CONTRACTOR SHALL BE GUARANTEED AGAINST DEFECTS IN MATERIAL AND WORKMANSHIP FOR A PERIOD OF ONE YEAR FROM DATE OF FINAL ACCEPTANCE.
- 12. ALL CONDUCTORS SHALL BE COPPER. NO ALUMINUM ALLOWED UNLESS SPECIFICALLY INDICATED ON DRAWINGS.
- SHOP DRAWINGS SHALL BE SUBMITTED FOR ALL ELECTRICAL & CONTROL EQUIPMENT AND MATERIAL.
- 14. ALL CONTROL PANELS SHALL BE CONSTRUCTED BY A UL 508A APPROVED PANEL VENDOR AND SHALL BEAR A UL 508A LABEL ON THE PANEL.
- 15. THE DRAWINGS ARE NOT INTENDED TO SHOW THE EXACT LOCATION OF CONDUIT RUNS. THESE ARE TO BE COORDINATED WITH THE OTHER TRADES SO THAT CONFLICTS ARE AVOIDED PRIOR TO INSTALLATIONS.
- 16. ALL LOCATIONS OF EQUIPMENT, PANELS ETC. ARE SHOWN FOR ILLUSTRATION PURPOSES. CONTRACTOR SHALL VERIFY AND COORDINATE EXACT LOCATION AND SIZE WITH ALL SUBCONTRACTORS AND EQUIPMENT SUPPLIERS PRIOR TO ANY INSTALLATION AND THEN INSTALL AS SUCH WITH CORRESPONDING CONDUIT STUB-UPS.
- 17. LOCATIONS OF MANHOLES, HANDHOLES AND PULL BOXES ARE APPROXIMATE. CONTRACTOR SHALL COORDINATE EXACT LOCATION WITH EXISTING AND NEW PIPING OR CONDUIT AND ADJUST ACCORDINGLY.
- 18. NOT ALL CONDUITS SHOWN ON RISER AND ONE-LINE DIAGRAMS ARE SHOWN ON BUILDING LAYOUTS. CONTRACTOR SHALL SUPPLY ALL CONDUITS AND CABLES AS SHOWN ON RISER AND ONE-LINE DIAGRAMS.
- 19. ALL CIRCUITS SHALL BE IDENTIFIED IN JUNCTION BOXES, PULL BOXES, CONTROL PANELS, PANELBOARDS, LIGHTING POLES, CONTROLLERS AND SERVICE POINTS. IDENTIFICATION SHALL MATCH PANELBOARD SCHEDULES.
- 20. EXPOSED RUNS OF CONDUITS SHALL BE INSTALLED WITH RUNS PARALLEL OR PERPENDICULAR TO WALLS, STRUCTURAL MEMBERS OR INTERSECTIONS OF VERTICAL PLANES AND CEILINGS, WITH RIGHT ANGLE TURNS CONSISTING OF SYMMETRICAL BENDS OR PULL BOXES AS INDICATED ON THE DRAWINGS. BENDS AND OFFSETS SHALL BE AVOIDED WHERE POSSIBLE.
- 21. ELECTRICAL CONDUIT ROUTING IS SHOWN FOR ILLUSTRATION PURPOSES ONLY. CONTRACTOR SHALL FIELD VERIFY THE CONDUIT ROUTING WITH EXISTING CONDITIONS AND PROPOSED PIPING. DRAINAGE, ETC. TO AVOID CONFLICTS AND ADJUST ACCORDINGLY. SOME CONDUIT ROUTINGS REQUIRE FIELD DETERMINATION OF THE ROUTINGS TO AVOID CONFLICTS WITH EXISTING CONDITIONS.
- 22. CONTRACTOR SHALL SAW CUT EXISTING SIDEWALK, ROADWAY, CONCRETE SLAB, ETC. FOR CONDUIT OR COUNTERPOISE CROSSING AND REPAIR/RESTORE TO MATCH EXISTING CONDITION
- 23. NO CONDUIT SHALL PENETRATE AN OUTDOOR ELECTRICAL PANEL FROM TOP. FOR OUTDOOR ELECTRICAL PANELS, ALL CONDUIT PENETRATIONS SHALL BE FROM THE BOTTOM OR SIDE. PROVIDE
- NEMA 4X 316 STAINLESS STEEL J-BOX AS NECESSARY TO ASSIST CONDUITS ENTERING OUTDOOR ELECTRICAL PANEL.
- 24. ALL EXPOSED CONDUITS SHALL BE ROUTED TO AVOID A TRIPPING HAZARD, WHERE POSSIBLE. WHEN APPROVED BY ENGINEER AND OWNER, EXPOSED CONDUITS CAN BE MOUNTED ON FLOOR PROVIDE ALUMINUM RAMP COVER AS PER DETAIL FOR FLOOR MOUNTED CONDUITS.

25. INSTRUMENTATION IS LOW VOLTAGE SIGNALS SUCH AS 4-20MA, TELEPHONE COMMUNICATION, FIRE ALARM COMMUNICATION. POWER CONDUIT SHALL ONLY CROSS INSTRUMENTATION CONDUIT

PERPENDICULARLY AT RIGHT ANGLES WITH 6" SEPARATION.

26. CONDUCTOR PULLING TENSIONS SHALL NOT EXCEED MANUFACTURER'S RECOMMENDATION. CONTRACTOR SHALL INSTALL PULL BOXES TO MEET MANUFACTURER'S REQUIREMENTS.

- 27. MINIMUM DISTANCE ALLOWED BETWEEN POWER CONDUITS AND INSTRUMENTATION CONDUITS SHALL BE
  - 4160V 3 FT

120V

480V 2 FT

1 FT

- 28. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONDUIT AND WIRING INSTALLATION FOR ALL VENDOR PROVIDED EQUIPMENT (PACKAGE SYSTEMS) AND OWNER FURNISHED EQUIPMENT. IF THE SHOP DRAWINGS DIFFER FROM THE DESIGNED FACILITIES. THE CONTRACTOR SHALL REDESIGN THE FACILITIES AND SUBMIT THE REVISED DESIGN FOR THE ENGINEER'S APPROVAL ALONG WITH THE SHOP DRAWINGS. THERE SHALL BE NO ADDITIONAL COST TO THE OWNER FOR THE REDESIGN NOR FOR ANY ADDITIONAL CONDUITS AND WIRING. DURING SUBMITTAL THE CONTRACTOR SHALL VERIFY ALL SUPPLIED BREAKER SIZES FOR ALL PACKAGED SYSTEMS SUCH AS HVAC, EXHAUST FANS, MIXERS, CHEMICAL PUMPS ETC. AND MODIFY ALL BREAKERS IN MCC'S AND PANELBOARDS ACCORDINGLY WITHOUT ANY ADDITIONAL COST TO THE OWNER.
- 29. COLORED WARNING TAPE 6" WIDE SHALL BE INSTALLED 8" BELOW FINISHED GRADE DIRECTLY ABOVE ALL UNDERGROUND YARD CONDUITS ACCORDING TO THE FOLLOWING SCHEDULE: POWER: RED ALL OTHER CONDUITS: GREEN
- 30. CONTRACTOR SHALL RESTORE SIDEWALKS, ROADWAYS, SOD AND SPRINKLER SYSTEM PIPING TO MATCH EXISTING, AFTER THE COMPLETION OF THE CONDUIT AND PULL BOX INSTALLATION.
- 31. GROUNDING SHALL BE INSTALLED IN ACCORDANCE WITH NEC, ARTICLE 250. THE GROUNDING SYSTEM TEST SHALL NOT EXCEED A 48 HOUR SPAN DRY RESISTANCE OF 10 OHMS. ADDITIONAL GROUNDING TO MEET THIS REQUIREMENT SHALL BE INSTALLED AT NO EXTRA COST. GROUNDING AND BONDING CONNECTIONS SHALL NOT BE PAINTED. ALL GROUNDING CONNECTIONS SHALL BE EXOTHERMIC UNLESS SPECIFICALLY INDICATED OTHERWISE.
- 32. UNLESS OTHERWISE NOTED, UTILIZE HI-PRESS LUGS WITH STAINLESS STEEL MOUNTING HARDWARE FOR BONDING OF ALL METAL EQUIPMENT TO THE GROUNDING COUNTERPOISE WHEN USING 2/0 AWG OR LARGER GROUND WIRE.
- 33. AN EQUIPMENT GROUND WIRE SIZED PER NEC SHALL BE PULLED IN ALL ELECTRICAL CONDUITS, POWER AND CONTROL, WHETHER OR NOT INDICATED ON THE PLANS. RACEWAYS SHALL NOT BE
- 34. ALL ENCLOSURES, TJB, WIREWAY, PULL BOXES ETC. SHALL CONTAIN A GROUNDING BUS. CONNECT ALL RACEWAY BONDS TO THIS BUS VIA GROUNDING BUSHING AND EXTEND BONDING JUMPER FROM THIS BUS TO THE ENCLOSURE.

- 35. ALL NEMA 4X OUTDOOR PANELS SHALL BE EQUIPPED WITH A NEMA 4X BREATHER AND DRAIN TO PREVENT BUILD UP OF CONDENSATION WITHIN THE PANEL. FIELD DRILLING HOLES INTO SEALED NEMA 4X PANELS IS NOT PERMITTED.
- 36. CONTRACTOR SHALL CORE DRILL EXISTING CONCRETE WALLS, FLOORS, MANHOLES, HANDHOLES AND PULL BOXES FOR CONDUIT PENETRATIONS. X-RAY PRIOR TO CORE DRILLING. SEAL PENETRATIONS WITH NON-SHRINK GROUT OR APPROPRIATE FIRE RATED DEVICES WHERE APPLICABLE.
- 37. ALL CONDUITS PENETRATING RATED FIRE WALLS OR RATED FIRE FLOORS SHALL BE INSTALLED WITH U.L. APPROVED DEVICES TO MAINTAIN THE FIRE RATING OF THE WALL OR FLOOR PENETRATED.
- 38. PROVIDE CONDUIT DUCT SEAL AT ALL CONDUIT ENDS.
- 39. ALL SPARE CONDUITS SHALL BE SEALED WITH A CAP AT BOTH ENDS AND A PULL STRING INSTALLED WITH IDENTIFICATION ON BOTH ENDS.
- 40. FLEXIBLE CONDUITS SHALL BE USED TO TERMINATE ALL MOTORS AND OTHER VIBRATING EQUIPMENT AND SHALL BE BETWEEN 18" AND 3' IN LENGTH.
- 41. TYPEWRITTEN AND LAMINATED PANEL SCHEDULES SHALL BE INSTALLED IN EACH PANELBOARD, AND TYPEWRITTEN TERMINAL BLOCK SCHEDULES IN EACH CONTROL CABINET.
- 42. ALL MATERIAL IN DESIGNATED CORROSIVE AREAS SHALL BE NEMA 4X 316 STAINLESS STEEL.
- 43. ALL OUTDOOR LIGHTING FIXTURES SHALL BE OF COPPER FREE CONSTRUCTION.
- 44. ALL REFERENCES TO SS OR STAINLESS STEEL SHALL BE CONSTRUED AS MEANING OF 316 STAINLESS STEEL, UNLESS OTHERWISE NOTED.
- 45. CONTRACTOR SHALL BALANCE PANELBOARD LOADS AT THE END OF THE PROJECT.
- 46. FEEDER AND BRANCH CIRCUIT CONDUCTORS ARE SIZED FOR MAXIMUM VOLTAGE DROP OF 5 PERCENT COMBINED AT DESIGN LOAD PER THE FLORIDA BUILDING CODE ENERGY CONSERVATION CHAPTER.
- 47. CONTRACTOR SHALL PROVIDE TO THE OWNER RECORD DRAWINGS DEPICTING THE COMPLETED INSTALLATION AS INSTALLED INCLUDING A SINGLE LINE DIAGRAM OF THE BUILDING ELECTRICAL DISTRIBUTION AND FLOOR PLANS INDICATING THE LOCATION AND AREA SERVED BY ALL INSTALLED DISTRIBUTIONS PER THE FLORIDA BUILDING CODE ENERGY CONSERVATION CHAPTER.
- 48. CONTRACTOR SHALL PROVIDE TO THE OWNER OPERATING AND MAINTENANCE MANUALS (O&M MANUALS) FOR ALL EQUIPMENT PER THE FLORIDA BUILDING CODE ENERGY CONSERVATION CHAPTER. THE MANUALS SHALL INCLUDE:
- 48.1. SUBMITTAL DATA STATING EQUIPMENT RATING AND SELECTED OPTIONS FOR EACH PIECE OF EQUIPMENT REQUIRING MAINTENANCE.
- 48.2. O&M MANUALS FOR EACH PIECE OF EQUIPMENT REQUIRING MAINTENANCE. REQUIRED ROUTINE MAINTENANCE ACTIONS SHALL BE CLEARLY IDENTIFIED.
- 48.3. NAMES AND ADDRESSES OF AT LEAST ONE QUALIFIED SERVICE AGENCY.

**CONFORMED SET** 

**NOT FOR CONSTRUCTION** 

NOTES AND

HILLERS ELECTRICAL ENGINEERING, INC. 23257 STATE ROAD 7, SUITE 100 BOCA RATON, FLORIDA 33428 (561) 451-9165 (561) 451-4886 FAX

BAR IS ONE INCH ON ORIGINAL DRAWING IF NOT ONE INCH ON

THIS SHEET, ADJUST SCALES ACCORDINGLY

SHEET NUMBER

ELECTRICAL GENERAL

**SPECIFICATIONS** on the date adjacent

NOQN

No 85334

10/16/24 BK DATE REVISIONS

© 2023 KIMLEY-HORN AND ASSOCIATES, INC.

1920 WEKIVA WAY SUITE 200, WEST PALM BEACH, FL 33411

PHONE: 561-845-0665 FAX: 561-863-8175

WWW.KIMLEY-HORN.COM REGISTRY NO. 696


KHA PROJECT HIGH PRESSURE PUMP NO. 9 144957081 DATE **IMPROVEMENTS** MAY 2025 CALE AS SHOWN


RAWN BY

HECKED BY

PREPARED FOR ESIGNED BY BK VILLAGE OF WELLINGTON PALM BEACH COUNTY

OF 21





#### MODIFIED MCC-1002 ONE-LINE DIAGRAM NOT TO SCALE

	MLO	HIGH PRESSURE PUMP NO. 8 VFD	DEGASIFIER BLOWER NO. 4 M146  SCRUBBER PUMP NO. 8 M149  SCRUBBER PUMP NO. 6 M150  SPACE  SPACE	TRANSFER PUMP NO. 9 M7339 VFD  SPACE	HIGH PRESSURE PUMP NO. 9	HIGH SERVICE PUMP NO. 13 M7513 VFD
--	-----	---------------------------------------	--	--------------------------------------	--------------------------	---

MODIFIED MCC-1002 ELEVATION

NOT TO SCALE

MCC-1002 LOAD SUMMARY (480VAC)

DESCRIPTION	CL	RL
HIGH SERVICE PUMP NO. 13	124.0 A	124.0 A
TRANSFER PUMP NO. 9	52.0 A	52.0 A
DEGASIFIER BLOWER NO. 4	40.0 A	40.0 A
SCRUBBER PUMP NO. 6	11.0 A	11.0 A
SCRUBBER PUMP NO. 8	11.0 A	11.0 A
HIGH PRESSURE PUMP NO. 8	302.0 A	179.0 A
HIGH PRESSURE PUMP NO. 9 (STANDBY)*	302.0 A	0.0 A
TOTAL	842.0 A	417.0 A
25% LARGEST MOTOR	75.2 A	
SERVICE TOTAL	917.2 A	
KVA @480V, 3PH	762.5 KVA	346.7 KVA

CL = CONNECTED LODRL = RUNNING LOAD

\*NO NEW DEMAND LOAD ADDED AS A RESULT OF THIS PROJECT. HPP-9 IS AN INSTALLED STANDBY, IT DOES NOT OPERATE UNLESS ANOTHER HIGH PRESSURE PUMP OF EQUIVALENT HORSEPOWER IS OUT OF SERVICE.

#### **KEYED NOTES:**

- CONTRACTOR SHALL UTILIZE EXISTING SECTION IN MCC-1002 FOR NEW HPP-9 VFD. FURNISH ALL LABOR AND MATERIALS REQUIRED FOR A FULLY FUNCTIONAL VFD SECTION COMPLETE IN PLACE.
- (2) EXISTING MCC-1002 IS SQUARE D MODEL 6, FRONT ACCESS ONLY. ALL MODIFICATIONS SHALL MAINTAIN UL LISTING OF THE MCC ASSEMBLY.
- (3) EXISTING CONDUIT STUB LOCATED AT EQUIPMENT. CONTRACTOR SHALL EXTEND EXISTING CONDUIT AND TERMINATE ONTO NEW EQUIPMENT AS INDICATED IN DRAWINGS AND SPECIFICATIONS. FURNISH ALL LABOR AND MATERIALS FOR A WORKING HIGH PRESSURE PUMP SYSTEM COMPLETE IN PLACE.

(4) VFD ASSEMBLY IS OWNER FURNISHED EQUIPMENT. THE VILLAGE SHALL NOT BE RESPONSIBLE FOR COORDINATION OF SCHEDULING OF EQUIPMENT MANUFACTURER TO COMPLETE THE WORK SCOPE DEFINED HEREIN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL REVIEWING SHOP DRAWING SUBMITTALS, ADJUSTMENTS, COORDINATION AND INTEGRATION OF OWNER FURNISHED EQUIPMENT, INCLUDING SCHEDULING OF EQUIPMENT MANUFACTURER FOR INSTALLATION, TESTING, AND START-UP FOR A WORKING SYSTEM COMPLETE IN PLACE. REFER TO SPECIFICATIONS 16480 AND 16485 FOR ADDITIONAL REQUIREMENTS.

**CONFORMED SET** 

**NOT FOR CONSTRUCTION** 

HILLERS ELECTRICAL ENGINEERING, INC. 23257 STATE ROAD 7, SUITE 100 BOCA RATON, FLORIDA 33428 (561) 451-9165 (561) 451-4886 FAX

BAR IS ONE INCH ON ORIGINAL DRAWING IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.

MCC-1002 MODIFIED

SHEET NUMBER

E-4

13

	CONTRACT MODIFICATIONS	10/16/24	ВКН
No.	REVISIONS	DATE	BY

Kimley» Horn

© 2023 KIMLEY-HORN AND ASSOCIATES, INC. 1920 WEKIVA WAY SUITE 200, WEST PALM BEACH, FL 33411 PHONE: 561-845-0665 FAX: 561-863-8175 WWW.KIMLEY-HORN.COM REGISTRY NO. 696

KHA PROJECT HIGH PRESSURE PUMP NO. 9 144957081 DATE MAY 2025 CALE AS SHOWN ESIGNED BY

RAWN BY

**IMPROVEMENTS** PREPARED FOR

VILLAGE OF WELLINGTON

FLORIDA DATE:

LICENSED PROFESSIONAL

BRANDON K. HAAS

FLORIDA LICENSE NUMBER

85334

ONE-LINE DIAGRAM






PHOTO 1 - EXISTING HPP-9 CONDUIT STUBS NOT TO SCALE

#### PCPMOVRO2 CONNECTED LOAD SUMMARY®

EXISTING CONNECTED LOAD	18.9 A
NEW CONNECTED LOAD	6.3 A
CONNECTED LOAD TOTAL	25.2 A
25% LARGEST MOTOR	<u>0.6 A</u>
MINIMUM REQ. AMPACITY	25.8 A
KVA, 480V, 3-PH	21.4 KVA
EXISTING FEEDER AMPACITY-10 AWG	35.0 A

ELECTRIC ROOM

#### **GENERAL NOTES:**

- 1. REFER TO PLAN DRAWINGS FOR EQUIPMENT LOCATIONS.
- 2. PROVIDE PERMANENT LABELS FOR AND COIL SPARE WIRES IN JUNCTION BOXES THAT ARE ACCESSIBLE AT FINISHED FLOOR ELEVATION.
- 3. NOT ALL CONDUITS AND CABLES SHOWN. SEE OTHER PLAN DRAWINGS FOR ADDITIONAL CONDUITS AND CABLES.
- 4. BEFORE INSTALLATION, THE CONTRACTOR SHALL COORDINATE ALL CONDUIT REQUIREMENTS WITH INSTRUMENTATION CONTRACTOR AND MECHANICAL EQUIPMENT SUPPLIER DIVISION 11. IF REQUIRED FOR SPECIFIED FUNCTIONALITY, FURNISH AND INSTALL ADDITIONAL CONTROL WIRES AND ADJUST CONDUIT SIZE AT NO ADDITIONAL COST TO THE VILLAGE.
- 5. UTILIZE EXISTING CONDUITS STUBS AS IDENTIFIED IN THE CONDUIT STUB LEGEND TO COMPLETE CONDUIT RUNS BETWEEN EQUIPMENT SHOWN ON THE RISER
- 6. TO THE EXTENT POSSIBLE, INSTALLATION OF NEW EQUIPMENT SHALL MATCH EXISTING INSTALLATIONS FOR FEED PUMPS 6, 7 AND 8.
- 7. CONDUITS WITHIN TRENCHES SHALL BE ROUTED AS TO NOT CREATE OBSTACLES OR OBSTRUCT EXISTING ACCESS TO EQUIPMENT. PROVIDE ADDITIONAL PULL POINTS AS REQUIRED BY FIELD ROUTING OF CONDUITS WITHIN TRENCHES. WHERE CONDUITS MUST TRAVERSE THE SPAN OF THE TRENCH, THEY SHALL BE SUPPORTED BY UNISTRUT MOUNTED TO TRENCH FLOOR.
- 8. CONDUIT ENTRIES FROM TOP OF ENCLOSURES NOT PERMITTED IN PIPING TRENCH.

#### KEYED NOTES:

- 1 DISCONNECTING MEANS FOR VALVE ELECTRIC ACTUATOR LOCATED INSIDE PANEL
- FIELD VERIFY AND USE 2 EXISTING #16TSP WIRES TO INTERFACE NEW CONCENTRATE VALVE POSITION COMMAND AND FEEDBACK SIGNALS INTO EXISTING
- (3) SPARE SIGNAL AND CONTROL WIRES ARE BUNDLED AND COILED IN BOTTOM OF PANEL. FIELD VERIFY SPARES AND CONNECT NEW SIGNALS TO EXISTING TERMINAL BLOCKS. FURNISH AND INSTALL NEW TERMINAL BLOCKS IF NO SPARES ARE AVAIALBLE.
- (4) INTERCEPT EXISTING CV1X46 POWER CONDUIT ON TRENCH WALL AND INSTALL SPLICE JUNCTION BOX, EXTEND CONDUCTORS TO NEW VALVE. TYPICAL OF 3 (X=6,7,8)
- (5) INTERCEPT EXISTING CONDUIT STUB AND EXTEND TO NEW EQUIPMENT.
- (6) INTERFACE NEW CONCENTRATE VALVE CV-1X20 IN AUTO AND FAILED SIGNALS WITH EXISTING PCPMOVRO2. FIELD VERIFY AND SPLICE CONDUCTORS IN EXISTING 2-7/C#16 CABLES ASSOCIATED WITH CV-1X46. SPLICES SHALL BE MADE INSIDE CJB-1X43. LABEL WIRES WITH NEW SHRINK-WRAP MARKERS INDICATING TAG.
- 7 FIELD VERIFY AND USE EXISTING CV-1X46 OPEN AND CLOSE FEEDBACK SIGNAL WIRES BETWEEN PCPMOVRO2 AND PLC-RO2 FOR NEW CV-1X20 IN AUTO AND FAILED SIGNALS. LABEL WIRES WITH NEW SHRINK-WRAP MARKERS INDICATING TAG.
- (8) NEW VALVE ACTUATORS ARE RATED 1/8 HP AND INTERMITTENT DUTY.
- (9) FIELD MODIFY GRATING FOR CONDUIT ENTRIES, DEBURR ALL CUT EDGES. AT COMPLETION, GRATING SHALL BE REMOVABLE WITHOUT ALTERING CONDUITS.

#### **CONDUIT STUB LEGEND:**

- 1 3/4"C TO CONDUIT STUB 8 FOR PIT-1940
- 2 3/4"C TO VFD SECTION IN MCC-1002
- 2"C TO VFD SECTION IN MCC-1002 FOR PUMP POWER
- 2"C TO VFD SECTION IN MCC-1002 FOR PUMP POWER
- 5 3/4"C TO VFD SECTION INC MCC-1002
- 6 EXISTING GROUNDING PIGTAIL FOR HPP-9
- 7 1-1/2"C TO PLC-RO2
- 8 3/4"C TO CONDUIT STUB 1 FOR PIT-1940
- 9 3/4"C SPARE
- 10 SPARE
- 11 3/4"C TO CONDUIT STUB 14
- 12 3/4"C TO PCPMOVRO2
- 13 1"C TO PLC-RO2
- 14 3/4"C TO CONDUIT STUB 11
- 15 1-1/2"C TO PLC-RO2

BID ALTERNATE ITEM #1

LEGEND:

**CONFORMED SET** 

**NOT FOR CONSTRUCTION** 

HILLERS ELECTRICAL ENGINEERING, INC. BOCA RATON, FLORIDA 33428 (561) 451-9165 (561) 451-4886 FAX

BAR IS ONE INCH ON ORIGINAL DRAWING IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY


SHEET NUMBER


E-5

No 85334

ELECTRICAL RISER DIAGRAMS AND SCHEDULES

to the seal.					
The signature	must be	verified o	n any	electronic	copies.





NOT TO SCALE

LCONTRACT MODIFICATIONS

REVISIONS



TYPICAL OF 3

X = 6,7,8

© 2023 KIMLEY-HORN AND ASSOCIATES, INC.

1920 WEKIVA WAY SUITE 200, WEST PALM BEACH, FL 33411

PHONE: 561-845-0665 FAX: 561-863-8175

WWW.KIMLEY-HORN.COM REGISTRY NO. 696

EXISTING PCPMOVRO2 PLC-RO2 HPP ROOM -1-1/2"C, PULL STRING PULL STRING 4XSS 10"X10"X6' -3/4"C, 3#12, 1#12G \1643/ FIELD ROUTE ON TRENCH WALLS

NO INCREASE TO DEMAND (8)

LOAD AS RESULT OF THIS PROJECT

SWING VALVE ACTUATOR INSTRUMENTATION AND CONTROL DIAGRAM REFER TO NOTE 7

NOT TO SCALE

KHA PROJECT Kimley» Horn 144957081 DATE MAY 2025 CALE AS SHOW


ESIGNED BY

HIGH PRESSURE PUMP NO. 9 **IMPROVEMENTS** 

PREPARED FOR VILLAGE OF WELLINGTON

**EXISTING** 

OF 21



KEYED NOTES:

1 VFD ASSEMBLY IS OWNER FURNISHED EQUIPMENT. THE VILLAGE SHALL NOT BE RESPONSIBLE FOR COORDINATION OF SCHEDULING OF EQUIPMENT MANUFACTURER TO COMPLETE THE WORK SCOPE DEFINED HEREIN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL REVIEWING SHOP DRAWING SUBMITTALS, ADJUSTMENTS, COORDINATION AND INTEGRATION OF OWNER FURNISHED EQUIPMENT, INCLUDING SCHEDULING OF EQUIPMENT MANUFACTURER FOR INSTALLATION, TESTING, AND START-UP FOR A WORKING SYSTEM COMPLETE IN PLACE. REFER TO SPECIFICATIONS 16480 AND 16485 FOR ADDITIONAL REQUIREMENTS.

**CONFORMED SET** 

**NOT FOR CONSTRUCTION** 

HILLERS ELECTRICAL ENGINEERING, INC. 23257 STATE ROAD 7, SUITE 100 BOCA RATON, FLORIDA 33428 (561) 451-9165 (561) 451-4886 FAX

ORIGINAL DRAWING

IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.

SHEET NUMBER

This item has been digitally signed and sealed by

ELECTRICAL SCHEMATICS

E-6

OF 21 15

on the date adjacent to the seal.

**IMPROVEMENTS** PREPARED FOR

HIGH PRESSURE PUMP NO. 9

VILLAGE OF WELLINGTON

KHA PROJECT

144957081 DATE

MAY 2025

CALE AS SHOWN

ESIGNED BY BK

DRAWN BY

Kimley» Horn

© 2023 KIMLEY-HORN AND ASSOCIATES, INC.

1920 WEKIVA WAY SUITE 200, WEST PALM BEACH, FL 33411

PHONE: 561-845-0665 FAX: 561-863-8175


WWW.KIMLEY-HORN.COM REGISTRY NO. 696

10/16/24 BK

DATE

A CONTRACT MODIFICATIONS

REVISIONS




#### INSTRUMENT SOCIETY OF AMERICA TABLE

	FIRST LETTER		SUCCEEDING LETTERS		
LETTER	PROCESS OR INITIATING VARIABLE	MODIFIER	READOUT OR PASSIVE FUNCTION	OUTPUT FUNCTION	MODIFIER
А	ANALYSIS (*)		ALARM		USERS CHOICE (*)
В	BURNER FLAME		USERS CHOICE (*)	USERS CHOICE (*)	
С	CONDUCTIVITY			CONTROL	CLOSE
D	DENSITY (S.G.)	DIFFERENTIAL			
Е	VOLTAGE		PRIMARY ELEMENT		
F	FLOW RATE	RATIO			
G	GAUGE		GLASS	GATE	
Н	HAND (MANUAL)				HIGH
I	CURRENT		INDICATE		
J	POWER	SCAN			
K	TIME OR SCHEDULE			CONTROL STATION	
L	LEVEL		LIGHT (PILOT)		LOW
М	MOTION				MIDDLE
N	STROKE		USERS CHOICE (*)	USERS CHOICE (*)	NORMAL
0	LOOP VEH. DETECTOR		OFFICE		OPEN
Р	PRESSURE OR VACUUM		POINT (TEST CONNECTION)		
Q	QUANTITY OR EVENT		INTEGRATE		
R	RATIO		RECORD OR PRINT		
S	SPEED OR FREQUENCY	SAFETY		SWITCH	
Т	TEMPERATURE			TRANSMIT	
U	MULTIVARIABLE (*)		MULTIFUNCTION (*)		
V	VIBRATION			VALVE	
W	WEIGHT OR FORCE		WELL		
Х	UNCLASSIFIED (*)		UNCLASSIFIED (*)	UNCLASSIFIED (*)	UNCLASSIFIED (*)
Υ	PHOTO CELL		LIGHT SOURCE	RELAY OR COMPUTE (*)	
Z	POSITION			DRIVE, ACTUATE OR UNCLASSIFIED FINAL CONTROL ELEMENT	

(\*) WHEN USED, EXPLANATION IS SHOWN ADJACENT TO INSTRUMENT SYMBOL

#### INSTRUMENT IDENTIFICATION



STATUS/CONTROL WITH INTERLOCKS (OFTEN LOCATED IN MCC)

PLC (PROGRAMMABLE LOGIC CONTROLLER)

DATE B'



ALARM ANNUNCIATOR OR STATUS INDICATING LIGHT

#### **NOTES:**

- 1. COMPONENTS AND PANELS SHOWN WITH A DIAMOND (lacktriangle) ARE TO BE PROVIDED UNDER SECTION "INSTRUMENTATION & CONTROLS".
- 2. COMPONENTS AND PANELS SHOWN WITH A DOUBLE ASTERISK (\*\*) ARE TO BE PROVIDED AS PART OF A PACKAGED OR MECHANICAL SYSTEM.
- 3. COMPONENTS AND PANELS SHOWN WITH A TRIANGLE (A) ARE EXISTING. COMPONENTS AND PANELS WHICH HAVE NO SYMBOL ATTACHED TO IT ARE
- 4. COMPONENTS AND PANELS SHOWN WITH A HEXAGON ( ) ARE EXISTING TO BE MODIFIED AND/OR RELOCATED.
- 5. COMPONENTS AND PANELS SHOWN WITH A SQUARE (■) ARE PROVIDED BY THE 6. THE SINGLE INSTRUMENT & CONTROL SUPPLIER SHALL HAVE A U.L. APPROVED
- 7. ALL PROCESS TUBING AND ISOLATION VALVES SHALL BE 1/4"- 316 S.S., UNLESS OTHERWISE NOTED.
- ALL CONTROL PANELS SHALL BE FURNISHED AND INSTALLED WITH A 1P-15A CIRCUIT BREAKER, UNLESS OTHERWISE NOTED. SEE MECHANICAL PLANS AND SPECIFICATIONS FOR EQUIPMENT NUMBERS.
- 10. SUNSHIELD SHALL BE PROVIDED FOR ALL OUTDOOR INSTRUMENTS.

#### **INSTRUMENT LINE SYMBOLS**

	PRIMARY PROCESS FLOW
	FUTURE PRIMARY PROCESS FLOW
	SECONDARY PROCESS FLOW, CONNECTION TO PROCESS FLOW, MECHANICAL LINK OR INSTRUMENT SUPPLY
	ELECTRICAL SIGNAL (DISCRETE)
———A———	ELECTRICAL SIGNAL (ANALOG)
	PNEUMATIC SIGNAL
	FIBER OPTIC
x	PROCESS OR SIGNAL CONTINUED SOMEWHERE ELSE (X=1,2,3,)
	ETHERNET

#### **INSTRUMENT ABBREVIATION**

ACCELATOR

CHLORINE


BELT FILTER PRESS

BFP


CL2


CL2	CHLORINE
CLW	CLEARWELL
COM	COMMON
COND	CONDUCTIVITY
CP	CONTROL PANEL
DI, AI	DISCRETE INPUT, ANALOG INPUT
DO, AO	DISCRETE OUTPUT, ANALOG OUTPUT
D.O.	DISSOLVED OXYGEN
DR	DISTANCE RELAY
EFFL	EFFLUENT
EP	ELECTRICAL PANEL
ES	EMERGENCY STOP
ETM	ELAPSED TIME METER
FD	CHEMICAL FEEDER
FIL	FILTER
GEN	GENERATOR
HLO	HIGH-LOW-OFF
HLOR	HIGH-LOW-OFF-REMOTE
HOA	HAND-OFF-AUTO
HOR	HAND-OFF-REMOTE
HOTC	HAND-OFF-TIMER-COMPUTER
H/L	HIGH/LOW
HSP	HIGH SERVICE PUMP
INFL	INFLUENT
JP	JOCKEY PUMP
LOS	LOCK-OUT-STOP
LPU	LINE PROTECTION UNIT
MCC MCP	MOTOR CONTROL CENTER
ME	MAIN CONTROL PANEL MISCELLANEOUS EQUIPMENT
M.G.	MILLION GALLON
MOD.	MODULATING VALVE
MOV	MOTOR OPERATED VALVE
OCA	OPEN-CLOSE-AUTO
OC, O/C	OPEN-CLOSE
00	ON-OFF
ORP	OXIDATION REDUCTION POTENTIAL
OSC	OPEN-STOP-CLOSE
OSCR	OPEN-STOP-CLOSE-REMOTE
PH	HYDROGEN ION CONCENTRATION
PRES	PRESSURE
RES	RESTORE
RF	RF (ADMITTANCE) LEVEL MONITOR
RIP, RIO	REMOTE I/O PANEL
R/L	REMOTE/LOCAL
RSP	REMOTE SETPOINT
SA	SURGE ARRESTER
SEC	SECONDARY
SL	SLAKER
SF	SONIC FLOWMETER
SP	SETPOINT
SS	START/STOP
ST	STEP
STOR	STORAGE
SUS	SUSPENDED SOLIDS
SSRVS	SOLID STATE REDUCED
TD	VOLTAGE STARTER
TD	THERMAL DISPERSION
TP	TRANSFER PUMP
TURB	TURBIDITY
VFD	VARIABLE FREQUENCY DRIVE

#### INSTRUMENTATION LEGEND










No 85334



AIR RELEASE VALVE

PRESSURE SUSTAINING VALVE



**CONFORMED SET** 

HILLERS ELECTRICAL ENGINEERING, INC. BOCA RATON, FLORIDA 33428 (561) 451-9165 (561) 451-4886 FAX

VERIFY SCALES BAR IS ONE INCH ON ORIGINAL DRAWING IF NOT ONE INCH ON

# **NOT FOR CONSTRUCTION**

This item has been digitally signed and sealed by

23257 STATE ROAD 7, SUITE 100

THIS SHEET, ADJUST SCALES ACCORDINGLY. SHEET NUMBER

**|-**1

### INSTRUMENTATION LEGEND & SYMBOLS

on the date adjacent

# 1\ | CONTRACT MODIFICATIONS | 10/16/24 | BKH

REVISIONS

Kimley» Horn

© 2023 KIMLEY-HORN AND ASSOCIATES, INC. 1920 WEKIVA WAY SUITE 200, WEST PALM BEACH, FL 33411 PHONE: 561-845-0665 FAX: 561-863-8175 WWW.KIMLEY-HORN.COM REGISTRY NO. 696


KHA PROJECT 144957081 DATE MAY 2025 CALE AS SHOWN ESIGNED BY BK


DRAWN BY


HECKED BY


HIGH PRESSURE PUMP NO. 9 **IMPROVEMENTS** 


PREPARED FOR VILLAGE OF WELLINGTON PALM BEACH COUNTY













PRESSURE GAUGE, INSTRUMENT OR SWITCH NOT TO SCALE



PIPE STAND TRANSMITTER MOUNT NOT TO SCALE



- 1. ALL PRESSURE TRANSMITTERS (PIT) SHALL BE INSTALLED AS IDENTIFIED
- 2. INSTRUMENT SHALL BE INSTALLED SO THAT AIR IS NOT ENTRAPPED WITHIN
- THE INSTRUMENT.
- 3. ALL BALL VALVES SHALL BE 316SS ALL MOUNTING HARDWARE SHALL BE 316SS.
- CONTRACTOR SHALL PROVIDE TAPPING SADDLES FOR PVC PIPE TAPS, WELDED THREAD-O-LETS FOR STAINLESS STEEL PIPE TAPS, AND THREADED BOSSES FOR DUCTILE IRON PIPE TAPS.

TYPICAL PRESSURE TRANSMITTER INSTALLATION NOT TO SCALE



**NOT FOR CONSTRUCTION** 

HILLERS ELECTRICAL ENGINEERING, INC. 23257 STATE ROAD 7, SUITE 100 BOCA RATON, FLORIDA 33428 (561) 451-9165 (561) 451-4886 FAX

VERIFY SCALES BAR IS ONE INCH ON ORIGINAL DRAWING IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.

SHEET NUMBER

1\ | CONTRACT MODIFICATIONS | 10/16/24 | BKH REVISIONS DATE

Kimley» Horn

© 2023 KIMLEY-HORN AND ASSOCIATES, INC. 1920 WEKIVA WAY SUITE 200, WEST PALM BEACH, FL 33411 PHONE: 561-845-0665 FAX: 561-863-8175 WWW.KIMLEY-HORN.COM REGISTRY NO. 696


KHA PROJECT 144957081 DATE MAY 2025 SCALE AS SHOWN ESIGNED BY BKH

DRAWN BY

HECKED BY

HIGH PRESSURE PUMP NO. 9 **IMPROVEMENTS** 

PREPARED FOR VILLAGE OF WELLINGTON PALM BEACH COUNTY



INSTRUMENTATION STANDARD DETAILS

21

The signature must be verified on any electronic copies.



## **SECTION 3 – EXHIBIT R2 SCHEDULE OF VALUES**



## **BASE BID**



# VOW WTP Membrane Plant #2 (M2) High Pressure Pump 9 Improvements - BASED BID GMP PROPOSAL 11/17/2025

## **COST SUMMARY**

Direct Costs	LABOR	EC	QUIPMENT	N	MATERIALS	SUBS		TOTALS
Total Direct Costs	\$ -	\$	-	\$	-	\$ 754,649	\$	754,649
Total GC's	\$ 463,887	\$	-	\$	74,151	\$ 15,345	\$	553,383
Fee						\$ 117,723	\$	117,723
Total for Direct Costs	\$ 463,887	\$	-	\$	74,151	\$ 887,717	\$	1,425,755
Contingencies and Allowances	LABOR	EC	QUIPMENT	I	MATERIALS	SUBS		TOTALS
Owner Controlled Contingency (6.0% of Direct Costs)						\$ 78,482	\$	78,482
Dedicated Allowances (see next sheet)						\$ 175,000	\$	175,000
Total for Contingencies and Allowances	\$ -	\$	-	\$	-	\$ 253,482	\$	253,482
David and Incomes	LABOR	-	OLUDBAENT.		AATEDIALC	CHIDC		TOTALS
Bond and Insurance	LABOR	E	QUIPMENT	N	MATERIALS	SUBS	<u>.</u>	TOTALS
Bond						\$ 15,982	\$	15,982
Insurance						\$ 8,996	\$	8,996
Total for Bond and Insurance	\$ -	\$	-	\$	-	\$ 24,978	\$	24,978
GMP TOTALS	\$ 463,887	\$	-	\$	74,151	\$ 1,166,177	\$	1,704,215



VOW WTP Membrane Plant #2 (M2) High Pressure Pump 9 Improvements - BASED BID GMP PROPOSAL 11/17/25

				COST OF WORK							
DESCRIPTION	QTY	иом	LABOR \$ AMOUNT	EQUIPMENT \$ AMOUNT	MATERIALS \$ AMOUNT		SUBS \$ AMOUNT	,	\$ TOTALS	COMMENTS	
DIRECT COSTS				,				\$	754,649		
MECHANICAL INSTALL SUBCONTRACTOR	1	LS	\$ -	\$ -	\$ -	\$	512,860	\$	512,860	Wharton Smith	
INSTRUMENTATION SUBCONTRACTOR	1	LS	\$ -	\$ -	\$ -	\$	77,889	\$	77,889	CC Control Corp	
ELECTRICAL SUBCONTRACTOR	1	LS	\$ -	\$ -	\$ -	\$	163,900	\$	163,900	Loveland Electric	
DEDICATED ALLOWANCES								\$	175,000		
ALLOWANCE FOR COATINGS	1	LS	\$ -	\$ -	\$ -	\$	35,000	\$	35,000		
ALLOWANCE FOR INDEPENDENT TESTING	1	LS	\$ -	\$ -	\$ -	\$	10,000	\$	10,000		
ALLOWANCE FOR FLOW METER INSTALLATION	1	LS	\$ -	\$ -	\$ -	\$	130,000	\$	130,000		
TOTAL DIRECT COST			\$ -	\$ -	\$ -	\$	799,649	\$	929,649		



# Wharton-Smith, Inc. CONSTRUCTION GROUP

	JOB NAME:	VOW WTP Mem	nbrane Plant #2	(M2) HPP 9 Im	provements – BASI	
	ESTIMATE #:	1				

	DUBATION	T		DIRECT MANH				MANWEEKS								
GENERAL CONDITIONS	DURATION =		5	MONTHS, PLA	NNED		2	MEN								
			MH/	BASE		LABOR			EQUIP			MATERIAL		SUBCONT		
DESCRIPTION	QTY	UNIT	UNIT	RATE	U/P	TOTAL MH	\$ AMOUNT	HR/UNIT R	ATE	\$ AMOUNT	U/P	\$ AMOUNT	\$ AMOUNT	U/P	\$ AMOUNT	\$ TOTALS
PROJECT MANAGEMENT TEAM				,			,	,		,		,	W/ 7% TAX		,	
FIELD STAFF																
SUPERINTENDENT	22	WK	40	\$157.00	\$6,280	\$866	\$135,962			\$0		\$0	\$0		\$0	\$135,962
OFFICE STAFF																
PROJECT MANAGER		WK	40	\$157.00	\$6,280	\$866	\$135,962			\$0		\$0			\$0	\$135,962
PROJECT ENGINEER		WK	40	\$96.00	\$3,840	\$866	\$83,136			\$0		\$0			\$0	\$83,136
PROJECT ASSISTANT	22	WK	24	\$80.00	\$1,920	\$520	\$41,568			\$0		\$0	\$0		\$0	\$41,568
OTHER STAFF																
COST ACCOUNTANT		WK	16	\$124.00	\$1,984	\$346	\$42,954			\$0		\$0			\$0	\$42,954
SAFETY COORDINATOR	22	WK	4	\$140.00	\$560	\$87	\$12,124			\$0		\$0	\$0		\$0	\$12,124
RELATED MANAGEMENT COSTS		,														
SOFTWARE COSTS	1	LS		\$50.00	\$0	\$0	\$0			\$0		\$0	\$0	\$3,932	\$3,932	\$3,932
TEMP.FACILITIES & UTILITIES																
WATER, MONTHLY	5	МО		\$50.00	\$0	\$0	\$0			\$0	\$250	\$1,250	\$1,338		\$0	\$1,338
INTERNET/TELEPHONE, MONTHLY CHARGES - W-S	5	МО		\$50.00	\$0		\$0			\$0	\$200				\$0	\$1,070
CELLULAR TELEPHONE, MONTHLY CHARGES	5	МО		\$50.00	\$0	\$0	\$0			\$0	\$300	\$1,500	\$1,605		\$0	\$1,605
FIELD OFFICE, WHARTON SMITH INC	5	МО	5	\$50.00	\$250	\$25	\$1,250			\$0	\$8,000	\$40,000	\$42,800		\$0	\$44,050
JOB OFFICE SUPPLIES	5	МО		\$50.00	\$0	\$0	\$0			\$0	\$750	\$3,750	\$4,013		\$0	\$4,013
COMPUTER EQUIPMENT FOR FIELD OFFICE - W-S	1	LS		\$50.00	\$0	\$0	\$0			\$0	\$2,000	\$2,000	\$2,140		\$0	\$2,140
Tool trailers - <u>1</u> required	5	МО		\$50.00	\$0	\$0	\$0			\$0	\$250	\$1,250	\$1,338		\$0	\$1,338
TEMPORARY TOILETS - 1 REQUIRED	5	МО		\$50.00	\$0	\$0	\$0			\$0	\$150	\$750	\$803		\$0	\$803
TEMPORARY SEWAGE HOLDING TANKS - ENGINEER & W-S	5	МО		\$50.00	\$0	\$0	\$0			\$0	\$300	\$1,500	\$1,605		\$0	\$1,605
CONSTRUCTION EQUIPMENT & TOOLS			· ·	Ö												
SMALL TOOLS AND SUPPLIES	1	LS		\$50.00	\$0	\$0	\$0			\$0	\$4,800	\$4,800	\$5,136		\$0	\$5,136
SAFETY & HEALTH & HOUSEKEEPING				·			·									
SAFETY DEVICES	1	LS		\$50.00	\$0	\$0	\$0			\$0	\$3,000	\$3,000	\$3,210		\$0	\$3,210
CLEAN-UP AT END OF PROJECT	1	LS	80	\$50.00	\$4,000	\$80	\$4,000			\$0		\$0	\$0		\$0	\$4,000
CLEAN-UP THROUGHOUT DURATION OF PROJECT	22	WK	4	\$50.00	\$200	\$87	\$4,330			\$0		\$0	\$0		\$0	\$4,330
DUMPSTERS	5	МО		\$50.00	\$0	\$0	\$0			\$0	\$1,250	\$6,250	\$6,688		\$0	\$6,688
JANITORIAL	22	WK		\$50.00	\$0	\$0	\$0			\$0		\$0	\$0	\$280	\$6,062	\$6,062
TOTAL GENERAL CONDITIONS			·			\$3,742	\$461,287			\$0			\$71,744		\$9,994	\$543,023
																40.0,020
CENEDAL DECLIDEMENTS																
GENERAL REQUIREMENTS																
PERMITS, FEES, INSURANCE, LEGAL, ETC. BUILDER'S RISK INSURANCE-COASTAL COUNTY	_	MO		¢ = 0, 00	<b>#</b> ^	#0	<b>#</b> 0			40		**	# 0	£250	¢2.050	¢2.050
	5	МО		\$50.00	\$0	\$0	\$0			\$0		\$0	\$0	\$250	\$2,850	\$2,850
PROJECT DOCUMENTATION AND SERVICES	_	MO		¢ = 0, 0,0	¢^	¢0	¢Λ			to!	¢1.50	¢750	¢003		t 0	¢003
PHOTOGRAPHS  PRE CONSTRUCTION AUDIO MEDIO DOCUMENTATION		MO		\$50.00	\$0		\$0			\$0	\$150				\$0	\$803
PRE-CONSTRUCTION AUDIO-VIDEO DOCUMENTATION	I	LS		\$50.00	\$0	\$0	\$0			\$0		\$0	\$0	\$2,500	\$2,500	\$2,500

							JOB NAME: VO	W WTP Membra	ane Plant #2	(M2) HPP 9 Im	provements - BAS	E	
							ESTIMATE #: 1						
					Smith	, Inc.							
DESIGN SERVICES (CADD) – AS-BUILTS	1 LS	40	\$65.00	\$2,600	\$40	\$2,600	\$0		\$0	\$0		\$0	\$2,600
PLANS & SPECIFICATIONS REPRODUCTION COSTS	1 LS		\$50.00	\$0	\$0	\$0	\$0	\$1,500	\$1,500	\$1,605		\$0	\$1,605
TOTAL GENERAL REQUIREMENTS					\$40	\$2,600	\$0			\$2,408		\$5,351	\$10,358

Subcontrator Bid Trad	e Description:	Master Plant Contractor
Evaluation and Proj	ect Name:	VOW WTP M2 High Pressure Pump 9 Improvements
Comparison Own	er:	Village of Wellington
Sheet Bid I	Date:	Tuesday, October 28, 2025

		/harton-Smith		Lawrence Lee Geoff Schmidt		Florida Design Drilling		N/A
	-	561-748-5956		561-578-7715		561-818-3228		
Scope Item Description	-	361-746-3336		361-376-7713	1	301-010-3220		
Base Bid Before Alternates		\$ 512,860.00		NO BID		NO BID		
Base Bid - HPP 9 Install, HPP 6, 7, 8 Mods.		\$ 512,860.00						
Alternates								
Bid Alternate - Concentrate Pipe Mods.		\$ 149,703.00						
Bid Document Requirements								
Bid Form		N/A						
Clarifications / Exceptions		N/A						
Acknowledged Addenda		N/A						
Additional Notes								
Payment & Performance Bond Rate		N/A						
Submittal Package Lead Time		See Schedule						
Material Delivery		See Schedule						
SUBTOTAL:		\$ 512,860.00		\$ -		\$ -		\$ -
Bond:	0.00%		0.00%		0.00%	Excluded	0.00%	
Adjustment	•	None	•			None		_
Total Adjusted Scope:		\$ 512,860.00		\$ -		\$ -		\$ -
		\$ 512,860.00		\$ -		\$ -		

Recommend award to Wharton-Smith as the lowest responsive bidder.

 Subcontrator Bid Evaluation and Comparison Sheet
 Trade Description:
 Electrical

 VOW WTP M2 High Pressure Pump 9 Improvements

 VOW WTP M2 High Pressure Pump 9 Improvements

 Village of Wellington

 Friday, August 29, 2025

Γ		Love	eland Electric II		N/A		N/A		N/A
		Rob	ert J. Loveland						
Scope Item Description		5	61-882-0401						
Base Bid Before Alternates		\$	163,900.00						
Base Bid		\$	161,000.00						
Payment & Performance Bond		\$	2,800.00						
Indemnification		\$	100.00						
Alternates									
Bid Alternate		\$	16,000.00						
Payment & Performance Bond		\$	-						
Indemnification		\$	-						
Bid Document Requirements									
Bid Form			Complete						
Clarifications / Exceptions		Not	ed in Proposal						
Acknowledged Addenda			Yes						
Additional Notes									
Payment & Performance Bond Rate			N/A						
Submittal Package Lead Time			8 weeks						
Material Delivery			30 weeks						
SUBTOTAL:		\$	163,900.00		\$ -		\$ -		\$ -
Bond:	0.00%		Included	0.00%		0.00%	\$ -	0.00%	
Adjustment			None						
Total Adjusted Scope:		\$	163,900.00		\$ -		\$ -		\$ -
		\$	163,900.00		\$ -		\$ -		

Recommend award to Loveland Electric as the lowest responsive bidder.



To:	Wharton-Smith, Inc.	_ Project:	VOW WTF	P HSP #9	
		Location:	1100 Welli	ngton Trace	
Attn:	Eliana Corie	Bid Date:	08/08/24	04/17/25	08/18/25

We are pleased to submit our scope and proposal for the above referenced project. Our electrical proposal includes all labor, material, and taxes, and is based and bid upon the electrical drawings as noted below.

Electrical wiring in accordance with the following:

I. Attachment A – Scope of WorkAttachment B – Scope Clarifications

II. Plans: E-1 thru E-7 Kimley Horn Dated March 2024

III. Specifications: Division 16000

IV. Addenda: 1

V. Duration: Proposal is based on 270 calendar day final completion.

- VI. We propose to complete all work to furnish the required material, labor and supervision in accordance with National Electric Code for work indicated on the bid documents only. No provisions have been included in this proposal for design errors or omissions.
- VII. Subcontract Agreement: AIA Document A101 or other mutually agreed upon document. Other documents may require further negotiations of terms and conditions.
- VIII. Insurance: Based on Loveland Electric, Inc. standard certificate of insurance and coverage. Copy of certificate is available upon request.
- IX. Market Conditions: This proposal is valid for one hundred eighty (180) days from this date. After this time we reserve the right to review our proposal and modify, if necessary, based on changing market conditions.

Proposal VOW WTP HSP #9 Pg 2

The price for the work described above including attachments will be as follows:

Base Bid: \$161,000.00

Alt-1 Base Bid (Not included in base bid): \$ 16,000.00

Bond premium not included in base bid: \$ 2,800.00

Thank you for the opportunity to submit this proposal. Should you require any additional information or clarifications, please do not hesitate to contact our office.

## LOVELAND ELECTRIC II, LLC

**Tim McMullen**Chief Estimator



1344 S. Killian Dr. Lake Park, FL 33403 561-882-0401 Fax 561-882-0555

## Scope of Work - Attachment A

**Project Name:** VOW WTP HSP #9

**Bid Date:** 8/8/2024

Not withstanding other provisions of the Bid Documents, this proposal is based upon:

No.	Description	Incl	Excl	NA	Comments
1	Davis Bacon Wage Rates		X		
2	Blueprinting & reproduction costs	X			
3	Temporary power for construction		X		
4	Utility installation fees, costs or deposits		X		
5	Electrical permit fees		X		
6	Inspections, approval and tests	X			
7	Submittals and shop drawings	X			
8	Record As-Built drawings	X			
9	Tools, equipment and transportation	X			
10	Material and personnel hoisting	X			
11	Garbage and debris removal	X			To on-site dumpster FBO
12	Hazardous waste disposal		X		
13	Electrical demolition	X			
14	Cutting and patching		X		
15	Excavation and backfill			X	Excludes soil testing
16	Import or export of fill dirt			X	Excludes soil testing
17	De-watering			X	
18	Cutting and patching of roads, drives, etc.			X	
19	Traffic control			X	
20	Concrete encasement			X	Excludes concrete lab testing
21	Housekeeping and equipment pads		X		
22	Concrete pole bases			X	
23	Plywood backboards			X	
24	Painting		X		Equipment touch up only
25	Roof penetrations and pitch pans			X	
26	Access panels			X	

0.7					
27	Special appliances			X	
28	Motor starters		X		
29	Motor disconnects		X		
30	HVAC control raceways		X		
31	Energy Management System		X		
32	Flow & tamper switches (by FP Contractor)		X		
33	Power connections to FBO equipment	X			
34	Field layout and trade coordination	X			
35	Electrical sleeves & fireproofing	X			
36	Electric Door Strikes and Installation		X		
37	FPL primary service		X		
38	Secondary service entrance		X		
39	Telephone service entrance raceway			X	
40	CATV service entrance raceway			X	
41	Site lighting and fixtures			X	
42	Lighting system and fixtures			X	
43	Power distribution system	X			
44	Emergency Generator Set			X	
45	Generator primary fuel tank			X	
46	Generator fuel			X	
47	Generator fuel piping			X	
48	Gen exhaust piping, intake/discharge duct, insulation			X	
49	Generator muffler and wall thimble				
50	Uninterrupted Power Supply system			Х	
51	Transient Voltage Surge Suppression		X		
52	Generator control wiring			X	
53	Generator Charger Connection			X	
54	Generator Block Heater			Х	
55	Generator ATS			Х	
56	Contingency Fees or allowances		Х		
57	Signage and neon lighting			Х	
58	Irrigation system controls and controls wiring			X	
59	Valance trim and lenses at restrooms			X	
60	Bond premium		X		
61	Survey of all light poles, manholes, pullboxes, etc.		X		
UI	Dai vey of all light poics, mailloies, pulloaxes, etc.		Λ	<u> </u>	

62 Special Systems:

Division	System	Incl	Excl	NA	Notes	Comments
	Lightning Protection			X		
	Fire Alarm			X		
	Telephone			X		
	Data / Premise Wiring			X		
	CATV/MATV			X		
	CCTV			X		
	Security / Intrusion			X		
	Building Automation System			X		
	PA / Sound / Background Music			X		

## \*Special Systems Notes:

- A This system is complete and operational.
- **B** This system includes conduit and boxes only. Wiring and devices are by others.
- 63 Loveland Electric II, LLC guarantees its work to be free from defects for one year from beneficial occupancy by the owner, or final completion, whichever comes first. Repairs to defective workmanship and/or materials within this period will be made at no cost to the owner. This warranty excludes lamps, items furnished by others, unauthorized service or negligent care.
- 64 Loveland Electric II, LLC will require the following to be provided to us at no cost:
  - A. Adequate on-site employee parking and an area for our storage and office trailer(s).
  - B. On-site dumpster and dumping services.
  - C. Sanitary toilet facilities.
  - D. Potable water.
  - E. Complete CADD files.
- 65 Loveland Electric II, LLC agrees to furnish a sufficient number of qualified workers to perform the work in sequen with a mutually agreed upon construction schedule. We rely on the work of other trades to be completed in a timely manner, prior to our work.
- All work will be performed during normal working hours. We have no provision included for overtime, multiple shifts, weekend or holiday work in order to make up time in the construction schedule lost by other trades, permitin inclement weather or other lost time not attributable to the work of Loveland Electric II, LLC
- 67 Transportation and storage of owner furnished equipment is excluded.



## Scope Clarifications – Attachment B

Project Name: VOW WTP HSP #9

Bid Date: 08/08/24

## **Specifications**

- 1. Specification Section 16010 Basic Electrical Requirements: Included
- 2. Specification Section 16050 Basic Electrical Materials: Included
- 3. Specification Section 16110 Raceways: Included
- 4. Specification Section 16120 Conductors: Included
- 5. Specification Section 16450 Grounding: Included
- 6. Specification Section 16480 Low Voltage Motor Control: Excluded
- 7. Specification Section 16485 Variable Frequency Drives: **Excluded**
- 8. Specification Section 16950 Electrical Testing: Included
- 9. Specification Section 17301 Instrumentation and Control: Includes conduit, wire and wire terminations to all instrumentation and control devices shown on drawings and specified.

  All instrumentation and control devices, junction boxes, surge suppressors and control panels will be furnished by I & C Subcontractor.

All process pipe mounted devices to be installed by others.

All other instrumentation and control devices, junction boxes, surge suppressors and control panels with be installed under this scope.

## **Inclusions**

- 1. Performance and Payment Bond premium.
- 2. Trash and debris removal to Contractor provided dumpsters.
- 3. Applicable taxes.

## **Exclusions**

- 1. Permit fees
- 2. Exhaust fans and associated control panels.
- 3. FPL primary conduit.
- 4. Utility installation fees, deposits or temporary power consumption costs.
- 5. Dewatering
- 6. Repairing and/or replacing asphalt and sub-base.
- 7. Repairing and/or replacing concrete floors and sidewalks.
- 8. Replacing sod or other landscape material.
- 9. Traffic and safety bollards.
- 10. Concrete and housekeeping pads.
- 11. Concrete lab testing.

Scope Clarifications – Attachment B VOW WTP HSP #9 Pg 2

- 12. Soil testing.
- 13. Transportation, off-loading, storage and setting in place equipment not furnished under this scope.
- 14. Prevailing Wage Rates/Responsible Wages and Benefits.
- 15. Furnishing, terminating, and testing fiber optic cable.

## **Clarifications**

- 1. Demolition will consist of making all circuits safe.
- 2. Demolition of electrical equipment and wire will consist of complete removal from site.
- 3. The failure of other trades to maintain the project schedule will not adversely affect the durations allowed in the original schedule for the electrical portion of the work.
- 4. All work will be performed during normal working hours. We have no provision included for overtime, multiple shifts, weekend or holiday work in order to make up time in the construction schedule lost by other trades, permitting, inclement weather or other lost time not attributable to the work of Loveland Electric II, LLC.
- 5. Proposal assumes the electrical drawings to be complete and no further redesign and installation of additional systems, equipment, conduit or wire, not specifically shown on drawings or otherwise noted in proposal, will be necessary to make a complete and working electrical system.

## **General Conditions**

- 1. Loveland Electric II, LLC guarantees its work to be free from defects for one year from beneficial occupancy by the owner, or final completion, whichever comes first. Repairs to defective workmanship and/or materials within this period will be made at no cost to the owner. This warranty excludes lamps, items furnished by other, unauthorized service or negligent care.
- 2. Loveland Electric II, LLC agrees to furnish a sufficient number of qualified workers to perform the work in sequence with a mutually agreed upon construction schedule. We rely on the work of other trades to be completed in a timely manner, prior to our work.
- 3. Loveland Electric II, LLC will require the following to be provided at no cost:
  - adequate on-site employee parking and an area for our storage and office trailers;
  - on-site dumpster and dumping services;
  - sanitary toilet facilities;
  - potable water;
  - complete CADD files.
- 4. Loveland Electric II, LLC shall not be held liable for errors or omissions in the designs of others, nor inadequacies of materials and equipment specified or supplied by others.

Scope of Work – Attachment B VOW WTP HSP #9 Pg 3

- 5. Equipment and materials supplied by Loveland Electric II, LLC are warranted only to the extent that the same are warranted by the manufacturer.
- 6. Loveland Electric II, LLC shall not be liable for indirect loss or damage.
- 7. Unless included in this proposal, all bonding and/or special insurance requirements are supplied at additional cost.
- 8. If a formal contract is required, its' conditions must not deviate from this proposal without our prior approval.
- 9. Anything (verbal or written) expressed or implied elsewhere, which is contrary to these conditions shall be null and void.

 Subcontrator Bid Evaluation and Comparison Sheet
 Trade Description:
 Instrumentation & Controls

 VOW WTP M2 High Pressure Pump 9 Improvements

 VOW WTP M2 High Pressure Pump 9 Improvements

 Village of Wellington

 Friday, August 29, 2025

		CC Control Corporation Juan Reyes	N/A	N/A	N/A
		561-293-3975			
Scope Item Description		301-233-3373			
Base Bid Before Alternates		\$ 77,889.00	\$	-	
Base Bid		\$ 77,789.00			
Payment & Performance Bond		\$ -			
Indemnification		\$ 100.00			
Alternates					
Bid Alternate		\$ 45,689.00			
Payment & Performance Bond		\$ -			
Indemnification		\$ -			
Bid Document Requirements					
Bid Form		Complete			
Clarifications / Exceptions		Noted in Proposal			
Acknowledged Addenda		No			
Additional Notes					
Payment & Performance Bond Rate		N/A			
Submittal Package Lead Time		6 weeks			
Material Delivery		12 weeks			
SUBTOTAL:		\$ 77,889		- \$ -	\$ -
Bond:	0.00%	Not Included	0.00%	0.00% \$ -	0.00%
Adjustment		None			
Total Adjusted Scope:	•	\$ 77,889.00	\$	- \$ -	\$ -
		\$ 77,889.00	\$	- \$ -	

Recommend award to CC Control Corp. as the lowest responsive bidder.



## C. C. CONTROL CORP.

5760 CORPORATE WAY, SUITE 100 WEST PALM BEACH, FLORIDA 33407

PHONE: 561 293-3975 FAX: 561 293-3976

**CUSTOMER:** WHARTON-SMITH INC.

ATTN: ELIANA CORIE

ecorie@whartonsmith.com

**PROJECT:** WTP M2 HIGH PRESSURE PUMP #9 IMPROVEMENTS

VILLAGE OF WELLINGTON

**DATE:** 8/20/2025

**VALID FROM:** 8/20/2025 **VALID TO:** 10/19/2025

<u>DESCRIPTION</u> <u>QTY</u> <u>AMOUNT</u>

## C. C. CONTROL CORP. PROPOSES TO FURNISH THE FOLLOWING COMPLETE WITH EXCEPTIONS AS LISTED:

#### **EXCEPTIONS:**

- A) QUOTE DOES NOT INCLUDE ANY DEMOLITION OR INSTALLATION.
- B) QUOTE DOES NOT INCLUDE ANY CONDUITS OR CONDUIT SEAL-OFF'S.
- C) QUOTE DOES NOT INCLUDE ANY WIRE/CABLE, EXCEPT AS NOTED BELOW.
- D) QUOTE DOES NOT INCLUDE ANY FIELD TERMINATIONS.
- E) QUOTE DOES NOT INCLUDE ANY PANEL MOUNTING HARDWARE
- F) QUOTE DOES NOT INCLUDE ANY DISCONNECTS OR PULL BOXES.
- G) QUOTE DOES NOT INCLUDE ANY IMPULSE PIPING OR PROCESS TAPS.
- H) QUOTE DOES NOT INCLUDE ANY VALVES OR VALVE ACTUATOR ACTUATOR.
- I) QUOTE DOES NOT INCLUDE HPP-9 VARIABLE FREQUNCY DRIVE.

#### ITEM NO.1

VALVE CONTROL PANEL PCPMOVRO2 MODIFICATIONS (CV-1*34 SWING PUMP VALVES)	
EATON / CUTLER HAMMER AN56BNOAC NEMA SIZE 0 3-PHASE REVERSING STARTER	3
EATON / CUTLER HAMMER H2005B-3 CLASS 20 HEATER PACKS, 1.2-1.96A, 3/CARTON	3
EATON / CUTLER HAMMER GMCP003AOC 3A 3-POLE G-FRAME BREAKER	3
EATON / CUTLER HAMMER 1294C01H01 BREAKER LOCK DOG	3
ALLEN-BRADLEY 1492-GH005 1P 120V 0.5A CIRCUIT BREAKER	3
ALLEN-BRADLEY 1492-GH050 1P 120V 5A CIRCUIT BREAKER	3
WIRES, TERMINALS, NAMEPLATES	LOT
ITEM NO.2	
HS2-1634, HS2-1734, HS2-1834 SWING PUMP VALVES OPERATOR STATION (3-REQ'D)	
SQUARE-D 9001SKY3 3-HOLE POLYMERIC CONTROL STATION	3

3

SQD 9001SKS43B 3 POSITION SELECTOR SWITCH

SQD 9001SKR1U 30MM MOMENTARY PUSH BUTTON OPERATOR SQD 9001KA1 30MM CONTACT BLOCK, 10A, (1)NO / (1)NC, SCREW CLAMP TERMINAL LABELS	6 12 LOT
ITEM NO.3	
HIGH PRESSURE PUMP NO.9 OPERATOR PUSH BUTTON STATION	
SQUARE-D 9001SKY111 1-HOLE POLYMERIC CONTROL STATION WITH HOA SELECTOR	1
ITEM NO.4	
HPP-9 PUMP INLET PRESSURE GAUGE ASSEMBLY	
ASHCROFT 45-1279AS-04L-XNHPD-100# DURAGAUGE PLUS 4.5" DIAL PROCESS GAUGE	1
A) RANGE: 0 TO 100 PSI	
B) 316L STAINLESS STEEL BOURDON TUEB AND SOCKET	
C) 1/2 IN MNPT LOWER STEM CONNECTION	
D) SEAL: BUNA-N	
E) ACRYLIC WINDOW, SILICONE FILL	
F) TAGS: <b>PI-1940</b> ASHCROFT 02-1112SD-25 PRESSURE SNUBBER, 303 SST. BODY	INCL
ASHCROFT 50-201SS-02T-XCKPUSE SERIES THREADED DIAPHRAGM SEAL	INCL
A) 1/2" NPT FEMALE PROCESS CONNECTION	
B) 1/2" NPT FEMALE INSTRUMENT CONNECTION	
C) 316L STAINLESS STEEL HOUSING	
D) 316L STAINLESS STEEL DIAPHRAGM MATERIAL	
E) 1/4" FLUSHING PORT IN LOWER HOUSING	
JAMESBURY 1/4-33-3600TL 1/4" 316 S.S. BALL VALVE	1
JAMESBURY 1/2-33-3600TL 1/2" 316 S.S. BALL VALVE 1/4" x 2" 316 STAINLESS STEEL NIPPLE	1 2
1/4" STAINLESS STEEL ELBOW	1
1/2" x 2" 316 STAINLESS STEEL NIPPLE	2
1/2" x 4" 316 STAINLESS STEEL NIPPLE	1
ITEM NO.5	
HPP-9 PUMP INLET PRESSURE TRANSMITTER ASSEMBLY	
ROSEMOUNT 3051S PRESSURE TRANSMITTER	1
A) RANGE: -14 TO 2000 PSI	
B) OUTPUT: 4-20MADC WITH HART	
C) PROCESS CONN.: 316L TRADITIONAL FLANGE 1/4-18 NPT	
D) HOUSING: ALUMINUM WITH 1/2-14 NPT	
F) DISPLAY: PLANTWEB LCD H) ASSEMBLE TO ROSEMOUNT CONVENSIONAL 304 INTEGRAL MANIFOLD	
I) TAGS: PIT-1940	
ROSEMOUNT 0304 IN-LINE MANIFOLD WITH THE FOLLOWING:	1
A) MANIFOLD STYLE: THREADED	
B) MANIFOLD TYPE: 2-VALVE	
C) BODY   BONNET   STEM   TIP: SST   SST   SST   316 SST	
D) PROCESS CONN. 1/2-14 FNPT	
E) PACKING MATERIAL: PTFE F) VALVE SEAT: INTEGRAL	
SQD SSP030SSE10HC 4/20MA PIPE STYLE SURGE ARRESTER	1
JAMESBURY 1/2-33-3600TL 1/2" 316 S.S. BALL VALVE	2
1/2" STAINLESS STEEL TEE	1
1/2" x 2" 316 STAINLESS STEEL NIPPLE	3
1/2" x 4" 316 STAINLESS STEEL NIPPLE	1
2" X 60" ALUMINUM PIPE STANCHION W/ 10" X 10" X 1/2" ALUMINUM BASE	1
MISC. BRACKET HARWARE	LOT

## ITEM NO.6

HEM NO.6	
HPP-9 PUMP OUTLET PRESSURE GAUGE ASSEMBLY	
ASHCROFT 1279 DURAGAUGE PLUS 4.5" DIAL PROCESS GAUGE	1
A) RANGE: 0 TO 200 PSI	
B) 316L STAINLESS STEEL BOURDON TUEB AND SOCKET	
C) 1/2 IN MNPT LOWER STEM CONNECTION	
D) SEAL: BUNA-N	
E) ACRYLIC WINDOW, SILICONE FILL	
F) TAGS: <b>PI-1942</b>	
ASHCROFT 02-1112SD-25 PRESSURE SNUBBER, 303 SST. BODY	INCL
ASHCROFT 50-201SS-02T-XCKPUSE SERIES THREADED DIAPHRAGM SEAL	INCL
A) 1/2" NPT FEMALE PROCESS CONNECTION	
B) 1/2" NPT FEMALE INSTRUMENT CONNECTION	
C) 316L STAINLESS STEEL HOUSING	
D) 316L STAINLESS STEEL DIAPHRAGM MATERIAL	
E) 1/4" FLUSHING PORT IN LOWER HOUSING	
JAMESBURY 1/4-33-3600TL 1/4" 316 S.S. BALL VALVE	1
JAMESBURY 1/2-33-3600TL 1/2" 316 S.S. BALL VALVE	1
1/4" x 2" 316 STAINLESS STEEL NIPPLE	2
1/4" STAINLESS STEEL ELBOW	1
1/2" x 2" 316 STAINLESS STEEL NIPPLE	2
1/2" x 4" 316 STAINLESS STEEL NIPPLE	1
1/2 X4 S10 STAINLESS STELL INFFEL	1
ITEM NO.7	
HPP-9 PUMP OUTLET PRESSURE TRANSMITTER ASSEMBLY ROSEMOUNT 3051S PRESSURE TRANSMITTER	1
	7
A) RANGE: -14 TO 2000 PSI	
B) OUTPUT: 4-20MADC WITH HART	
C) PROCESS CONN.: 316L TRADITIONAL FLANGE 1/4-18 NPT	
D) HOUSING: ALUMINUM WITH 1/2-14 NPT	
F) DISPLAY: PLANTWEB LCD	
H) ASSEMBLE TO ROSEMOUNT CONVENSIONAL 304 INTEGRAL MANIFOLD	
I) TAGS: <b>PIT-1942</b>	
ROSEMOUNT 0304 IN-LINE MANIFOLD WITH THE FOLLOWING:	1
A) MANIFOLD STYLE: THREADED	
B) MANIFOLD TYPE: 2-VALVE	
C) BODY   BONNET   STEM   TIP: SST   SST   SST   316 SST	
D) PROCESS CONN. 1/2-14 FNPT	
E) PACKING MATERIAL: PTFE	
F) VALVE SEAT: INTEGRAL	
SQD SSP030SSE10HC 4/20MA PIPE STYLE SURGE ARRESTER	1
JAMESBURY 1/2-33-3600TL 1/2" 316 S.S. BALL VALVE	2
1/2" STAINLESS STEEL TEE	1
1/2" x 2" 316 STAINLESS STEEL NIPPLE	3
1/2" x 4" 316 STAINLESS STEEL NIPPLE	1
2" X 60" ALUMINUM PIPE STANCHION W/ 10" X 10" X 1/2" ALUMINUM BASE	1
MISC. BRACKET HARWARE	LOT
ITEM NO.8	
PROJECT SERVICES	
ENGINEERING	LOT
SUBMITTALS	LOT
PLC PROGRAMMING	LOT
SCADA PROGRAMMING	LOT
	201

TESTING START-UP	LOT LOT
TRAINING	LOT
O & M MANUALS	LOT
WARRANTY, 1-YEAR	LOT
**************************************	
ITEM NO.9	
VALVE CONTROL PANEL PCPMOVRO2 MODIFICATIONS (CV-1*20 CONCENTRATE VALVES)	
EATON / CUTLER HAMMER ANS6BNOAC NEMA SIZE 0 3-PHASE REVERSING STARTER	3 3
EATON / CUTLER HAMMER H2005B-3 CLASS 20 HEATER PACKS, 1.2-1.96A, 3/CARTON EATON / CUTLER HAMMER GMCP003AOC 3A 3-POLE G-FRAME BREAKER	3
EATON / CUTLER HAMMER 1294C01H01 BREAKER LOCK DOG	3
ALLEN-BRADLEY 1492-GH005 1P 120V 0.5A CIRCUIT BREAKER	3
ALLEN-BRADLEY 1492-GH050 1P 120V 0.5A CIRCUIT BREAKER	3
WIRES, TERMINALS, NAMEPLATES	LOT
WINES, TERMINALS, NAMERIATES	LOT
ITEM NO.10	
HS1-1620, HS1-1720, HS1-1820 CONCENTRATE VALVES OPERATOR STATION (3 REQ'D)	
SQUARE-D 9001SKY3 3-HOLE POLYMERIC CONTROL STATION	3
SQD 9001SKS43B 3 POSITION SELECTOR SWITCH	3
SQD 9001SKR1U 30MM MOMENTARY PUSH BUTTON OPERATOR	6
SQD 9001KA1 30MM CONTACT BLOCK, 10A, (1)NO / (1)NC, SCREW CLAMP TERMINAL	12
LABELS	LOT
ITEM NO.11	
MAIN CONTROL PANEL PLC-RO2 MODIFICATIONS	4
ALLEN-BRADLEY 1756-A7 CONTROLLOGIX 7-SLOT MOUNTING CHASSIS RACK	1
ALLEN-BRADLEY 1756-PA72 CONTROLLOGIX POWER SUPPLY, 85-256VAC, 75W	1 1
ALLEN-BRADLEY 1756-IB16 CONTROLLOGIX DIGITAL INPUT, 16-POINT, 24VDC ALLEN-BRADLEY 1756-OB16I CONTROLLOGIX ISOLATED DIGITAL OUTPUT, 16-POINT, 12/24VDC	1
ALLEN BRADLEY 1756-08161 CONTROLLOGIX ISOLATED DIGITAL OUTPOT, 16-POINT, 12/24VDC ALLEN BRADLEY 1756-TBCH TERMINAL BLOCK, 36-PIN CAGE CLAMP BLOCK	2
PHOENIX CONTACT 2838322 PT 4X1-24DC-ST PLUGTRAB PT SURGE PROTECTION PLUG	4
PHOENIX CONTACT 2839363 PT 4X1-BE PLUGTRAB PT SURGE PROTECTION BASE	4
FINDER 60.13.9.024.0070 60 SERIES RELAYS, 3PDT, 10A, 24VDC, LED	8
FINDER 90.27SMA DIN RAIL 11-PINS RELAY SOCKET, SCREW TERMINAL	8
WIRES, TERMINALS, LABELS	LOT
ITEM NO.12	
ADDITONAL PROJECT SERVICES	
ENGINEERING	LOT
SUBMITTALS	LOT
PLC PROGRAMMING	LOT
TESTING	LOT
START-UP	LOT
O & M MANUALS	LOT
WARRANTY, 1-YEAR	LOT
SUMMARY	SELL
ITEMS NO.1 THRU NO.8 HIGH PRESSURE PUMP #9 ADDITION (BASE BID)	\$72,700.00
ITEMS NO 0 TRULL 12	¢42.700.00

CONCENTRATE PIPING IMPROVEMENTS (BID ALTERNATIVE #1)

\$42,700.00

ITEMS NO.9 TRHU 12

TOTAL: \$115,400.00 PLUS TAX

**SUBMITTAL:** 6-8 WEEKS (AFTER RECEIPT OF PURCHASE ORDER)

**DELIVERY:** 18-20 WEEKS (AFTER APPROVED DRAWINGS)

FOB: JOB SITE

TERMS: NET 30 DAYS (SUBJECT TO CREDIT APPROVAL)

WARRANTY: ALL WARRANTIES SHALL EXPIRE ONE (1) YEAR FROM DATE OF START-UP

FROM SELLER TO BUYER UNLESS SPECIALLY INDICATED OTHERWISE AND WILL BE NULL AND VOID UNLESS MATERIALS ARE STORED UNDER PROPER

CONDITIONS DETERMINED BY C.C. CONTROL CORP.

JUAN REYES

<u>ireyes@cccontrolcorp.com</u>



## **ALTERNATE BID**



## VOW WTP Membrane Plant #2 (M2) High Pressure Pump 9 Improvements - Bid Alt GMP PROPOSAL 8/29/2025

## **COST SUMMARY**

Direct Costs	LABOR	EQUIPMENT	MATERIALS	SUBS	TOTALS
Total Direct Costs	\$0	\$0	\$0	\$211,392	\$211,392
Total GC's	\$93,467	\$0	\$30,795	\$3,460	\$127,722
Fee				\$30,520	\$30,520
Total for Direct Costs	\$93,467	\$0	\$30,795	\$245,373	\$369,635
Contingencies and Allowances	LABOR	EQUIPMENT	MATERIALS	SUBS	TOTALS
Owner Controlled Contingency (6.0% of Direct Costs)				\$20,347	\$20,347
Dedicated Allowances (see next sheet)				\$0	\$0
Total for Contingencies and Allowances	\$0	\$0	\$0	\$20,347	\$20,347
Bond and Insurance	LABOR	EQUIPMENT	MATERIALS	SUBS	TOTALS
Bond				\$4,740	\$4,740
Insurance				\$2,034	\$2,034
Total for Bond and Insurance	\$0	\$0	\$0	\$6,774	\$6,774
GMP TOTALS	\$93,467	\$0	\$30,795	\$272,494	\$396,756



VOW WTP Membrane Plant #2 (M2) High Pressure Pump 9 Improvements - Bid Alt GMP PROPOSAL 8/29/25

				COST OF WORK							
DESCRIPTION	QTY	UOM	LABOR \$ AMOUNT	EQUIPM \$ AMOU		MATERIALS \$ AMOUNT		SUBS \$ AMOUNT		\$ TOTALS	COMMENTS
DIRECT COSTS									\$	211,392	
MECHANICAL INSTALL SUBCONTRACTOR	1	LS	\$ -	\$	-	\$ -	\$	149,703	\$	149,703	Wharton Smith
INSTRUMENTATION SUBCONTRACTOR	1	LS	\$ -	\$		\$ -	\$	45,689	\$	45,689	CC Control Corp
ELECTRICAL SUBCONTRACTOR	1	LS	\$ -	\$		\$ -	\$	16,000	\$	16,000	Loveland Electric
DEDICATED ALLOWANCES									\$	-	
N/A	1	LS	\$ -	\$	-	\$ -	\$	-	\$	-	
TOTAL DIRECT COST			\$ -	\$	-	\$ -	\$	211,392	\$	211,392	



# Wharton-Smith, Inc. CONSTRUCTION GROUP

	JOB NAME:	VOW WTP Mem				
	JOB NAME.	VOW WITH MICH	ibiane i lant #2	(1412) 1111 3 111		
	ESTIMATE #:	1				

			960	DIRECT MANH				MANWEEKS								
GENERAL CONDITIONS	DURATION =		2.0	MONTHS, PLAN	INED		1	MEN								
			MH/	BASE		LABOR			EQUIP	MENT	N	MATERIAL		SUBCONT	TRACTS	
DESCRIPTION	QTY	UNIT	UNIT	RATE	U/P	TOTAL MH	\$ AMOUNT	HR/UNIT	RATE	\$ AMOUNT	U/P	\$ AMOUNT	\$ AMOUNT	U/P	\$ AMOUNT	\$ TOTALS
PROJECT MANAGEMENT TEAM		,	,					,			,		W/ 7% TAX		,	
FIELD STAFF																
SUPERINTENDENT	9	WK	24	\$157.00	\$3,768	\$208	\$32,706			\$0		\$0	\$0		\$0	\$32,706
OFFICE STAFF																
PROJECT MANAGER	9	WK	16	\$157.00	\$2,512	\$139	\$21,804			\$0		\$0	\$0		\$0	\$21,804
PROJECT ENGINEER	9	WK	24	\$96.00	\$2,304	\$208	\$19,999			\$0		\$0	\$0		\$0	\$19,999
PROJECT ASSISTANT	9	WK	8	\$80.00	\$640	\$69	\$5,555			\$0		\$0	\$0		\$0	\$5,555
OTHER STAFF																
COST ACCOUNTANT	9	WK	4	\$124.00	\$496	\$35	\$4,305			\$0		\$0	\$0		\$0	\$4,305
SAFETY COORDINATOR	9	WK	4	\$140.00	\$560	\$35	\$4,861			\$0		\$0	\$0		\$0	\$4,86
RELATED MANAGEMENT COSTS		,	'	·		<u>'</u>		'			'				'	
SOFTWARE COSTS	1	LS		\$50.00	\$0	\$0	\$0			\$0		\$0	\$0	\$880	\$880	\$880
TEMP.FACILITIES & UTILITIES		,	,	,		,				'	,				'	
WATER, MONTHLY	2	МО		\$50.00	\$0	\$0	\$0			\$0	\$250	\$500	\$535		\$0	\$535
INTERNET/TELEPHONE, MONTHLY CHARGES - W-S	2	МО		\$50.00	\$0	\$0	\$0			\$0	\$200	\$400	\$428		\$0	\$428
CELLULAR TELEPHONE, MONTHLY CHARGES	2	МО		\$50.00	\$0	\$0	\$0			\$0	\$300	\$600	\$642		\$0	\$642
FIELD OFFICE, WHARTON SMITH INC	2	МО	5	\$50.00	\$250	\$10	\$500			\$0	\$8,000	\$16,000	\$17,120		\$0	\$17,620
JOB OFFICE SUPPLIES	2	МО		\$50.00	\$0	\$0	\$0			\$0	\$750	\$1,500	\$1,605		\$0	\$1,605
COMPUTER EQUIPMENT FOR FIELD OFFICE - W-S	1	LS		\$50.00	\$0	\$0	\$0			\$0	\$2,000	\$2,000	\$2,140		\$0	\$2,140
TOOL TRAILERS - 1 REQUIRED	2	МО		\$50.00	\$0	\$0	\$0			\$0	\$250	\$500	\$535		\$0	\$535
TEMPORARY TOILETS - 1 REQUIRED	2	МО		\$50.00	\$0	\$0	\$0			\$0	\$150	\$300	\$321		\$0	\$321
TEMPORARY SEWAGE HOLDING TANKS - ENGINEER & W-S	2	МО		\$50.00	\$0	\$0	\$0			\$0	\$300	\$600	\$642		\$0	\$642
CONSTRUCTION EQUIPMENT & TOOLS		,									l					
SMALL TOOLS AND SUPPLIES	1	LS		\$50.00	\$0	\$0	\$0			\$0	\$2,880	\$2,880	\$3,082		\$0	\$3,082
SAFETY & HEALTH & HOUSEKEEPING		1		·							I				1	
SAFETY DEVICES	1	LS		\$50.00	\$0	\$0	\$0			\$0	\$1,000	\$1,000	\$1,070		\$0	\$1,070
CLEAN-UP AT END OF PROJECT	1	LS	40	\$50.00	\$2,000	\$40	\$2,000			\$0		\$0			\$0	\$2,000
CLEAN-UP THROUGHOUT DURATION OF PROJECT	9	WK	4	\$50.00	\$200	\$35	\$1,736			\$0		\$0	\$0		\$0	\$1,736
DUMPSTERS	2	МО		\$50.00	\$0	\$0	\$0			\$0	\$1,250	\$2,500			\$0	\$2,675
JANITORIAL	9	WK		\$50.00	\$0		\$0			\$0	•	\$0		\$280	\$2,430	\$2,430
TOTAL GENERAL CONDITIONS					•	\$779	\$93,467			\$0		·	\$30,795	·	\$3,310	\$127,571
TOTAL GLINLIKAL CONDITIONS						· ·	•								1	\$127,371
CENTER AL DECLURENTS																
GENERAL REQUIREMENTS																
PERMITS, FEES, INSURANCE, LEGAL, ETC.		1		1												
BUILDER'S RISK INSURANCE-COASTAL COUNTY	2	МО		\$50.00	\$0.00		0.00			\$0		\$0				\$150
TOTAL GENERAL REQUIREMENTS						0.00	0.00			\$0			\$0		\$150	\$150

Subcontrator Rid	Trade Description:	Master Plant Contractor
Evaluation and	Project Name:	VOW WTP M2 High Pressure Pump 9 Improvements
Comparison	Owner:	Village of Wellington
Sheet	Bid Date:	Tuesday, October 28, 2025

	Wharton-Smith  Greg Williams			Lawrence Lee Geoff Schmidt	-	Florida Design Drilling  Jeff Holst		N/A	
Scope Item Description			561-748-5956		561-578-7715		561-818-3228		
Base Bid Before Alternates		\$	512,860.00		NO BID		NO BID		
Base Bid - HPP 9 Install, HPP 6, 7, 8 Mods.		\$	512,860.00						
Alternates									
Bid Alternate - Concentrate Pipe Mods.		\$	149,703.00						
Bid Document Requirements									
Bid Form			N/A						
Clarifications / Exceptions			N/A						
Acknowledged Addenda			N/A						
Additional Notes									
Payment & Performance Bond Rate			N/A						
Submittal Package Lead Time			See Schedule						
Material Delivery			See Schedule						
SUBTOTAL:		\$	512,860.00		\$ -	<del> </del>	\$ -		\$ .
Bond:	0.00%			0.00%		0.00%	Excluded	0.00%	
Adjustment			None				None		
Total Adjusted Scope:		\$	512,860.00		\$ -		\$ -		\$
		\$	512,860.00		\$ -		\$ -		

Recommend award to Wharton-Smith as the lowest responsive bidder.

 Subcontrator Bid Evaluation and Comparison Sheet
 Trade Description:
 Electrical

 VOW WTP M2 High Pressure Pump 9 Improvements

 VOW WTP M2 High Pressure Pump 9 Improvements

 Village of Wellington

 Sheet
 Friday, August 29, 2025

		Lovel	and Electric II		N/A		N/A		N/A
		Robe	rt J. Loveland						
Scope Item Description		56	1-882-0401					1	
· ·									
Base Bid Before Alternates		\$	163,900.00						
Base Bid		\$	161,000.00						
Payment & Performance Bond		\$	2,800.00						
Indemnification		\$	100.00						
Alternates									
Bid Alternate		\$	16,000.00						
Payment & Performance Bond		\$	-						
Indemnification		\$	-						
Bid Document Requirements									
Bid Form			Complete						
Clarifications / Exceptions		Note	d in Proposal						
Acknowledged Addenda			Yes						
Additional Notes									
Payment & Performance Bond Rate			N/A						
Submittal Package Lead Time			8 weeks						
Material Delivery			30 weeks						
SUBTOTAL:		\$	163,900.00		\$ -		\$ -		\$ -
Bond:	0.00%		Included	0.00%		0.00%	\$ -	0.00%	
Adjustment			None		•				•
Total Adjusted Scope:		\$	163,900.00		\$ -		\$ -		\$ -
		\$	163,900.00		\$ -		\$ -		

Recommend award to Loveland Electric as the lowest responsive bidder.



To:	Wharton-Smith, Inc.	Project:	VOW WTF	HSP #9	
		Location:	1100 Wellin	ngton Trace	
Attn:	Eliana Corie	Bid Date:	08/08/24	04/17/25	08/18/25

We are pleased to submit our scope and proposal for the above referenced project. Our electrical proposal includes all labor, material, and taxes, and is based and bid upon the electrical drawings as noted below.

Electrical wiring in accordance with the following:

I. Attachment A – Scope of WorkAttachment B – Scope Clarifications

II. Plans: E-1 thru E-7 Kimley Horn Dated March 2024

III. Specifications: Division 16000

IV. Addenda: 1

V. Duration: Proposal is based on 270 calendar day final completion.

- VI. We propose to complete all work to furnish the required material, labor and supervision in accordance with National Electric Code for work indicated on the bid documents only. No provisions have been included in this proposal for design errors or omissions.
- VII. Subcontract Agreement: AIA Document A101 or other mutually agreed upon document. Other documents may require further negotiations of terms and conditions.
- VIII. Insurance: Based on Loveland Electric, Inc. standard certificate of insurance and coverage. Copy of certificate is available upon request.
- IX. Market Conditions: This proposal is valid for one hundred eighty (180) days from this date. After this time we reserve the right to review our proposal and modify, if necessary, based on changing market conditions.

Proposal VOW WTP HSP #9 Pg 2

The price for the work described above including attachments will be as follows:

Base Bid: \$161,000.00

Alt-1 Base Bid (Not included in base bid): \$ 16,000.00

Bond premium not included in base bid: \$ 2,800.00

Thank you for the opportunity to submit this proposal. Should you require any additional information or clarifications, please do not hesitate to contact our office.

## LOVELAND ELECTRIC II, LLC

**Tim McMullen** Chief Estimator

 Subcontrator Bid Evaluation and Comparison Sheet
 Trade Description:
 Instrumentation & Controls

 VOW WTP M2 High Pressure Pump 9 Improvements

 VOW WTP M2 High Pressure Pump 9 Improvements

 Village of Wellington

 Sheet
 Friday, August 29, 2025

		CC Control Corporation Juan Reyes	N/A	N/A	N/A
Scope Item Description		561-293-3975			
Base Bid Before Alternates		\$ 77,889.00	\$	-	
Base Bid		\$ 77,789.00			
Payment & Performance Bond		\$ -			
Indemnification		\$ 100.00			
Alternates					
Bid Alternate		\$ 45,689.00			
Payment & Performance Bond		\$ -			
Indemnification		\$ -			
Bid Document Requirements					
Bid Form		Complete			
Clarifications / Exceptions		Noted in Proposal			
Acknowledged Addenda		No			
Additional Notes					
Payment & Performance Bond Rate		N/A			
Submittal Package Lead Time		6 weeks			
Material Delivery		12 weeks			
SUBTOTAL:		\$ 77,889	\$	- \$	- \$ -
Bond:	0.00%	Not Included	0.00%	0.00% \$	0.00%
Adjustment		None			
Total Adjusted Scope:		\$ 77,889.00	\$	- \$ -	\$ -
		\$ 77,889.00	\$	- \$ -	

Recommend award to CC Control Corp. as the lowest responsive bidder.



## C. C. CONTROL CORP.

5760 CORPORATE WAY, SUITE 100 WEST PALM BEACH, FLORIDA 33407

PHONE: 561 293-3975 FAX: 561 293-3976

**CUSTOMER:** WHARTON-SMITH INC.

ATTN: ELIANA CORIE

ecorie@whartonsmith.com

**PROJECT:** WTP M2 HIGH PRESSURE PUMP #9 IMPROVEMENTS

VILLAGE OF WELLINGTON

**DATE:** 8/20/2025

**VALID FROM:** 8/20/2025 **VALID TO:** 10/19/2025

<u>DESCRIPTION</u> <u>QTY</u> <u>AMOUNT</u>

## C. C. CONTROL CORP. PROPOSES TO FURNISH THE FOLLOWING COMPLETE WITH EXCEPTIONS AS LISTED:

#### **EXCEPTIONS:**

- A) QUOTE DOES NOT INCLUDE ANY DEMOLITION OR INSTALLATION.
- B) QUOTE DOES NOT INCLUDE ANY CONDUITS OR CONDUIT SEAL-OFF'S.
- C) QUOTE DOES NOT INCLUDE ANY WIRE/CABLE, EXCEPT AS NOTED BELOW.
- D) QUOTE DOES NOT INCLUDE ANY FIELD TERMINATIONS.
- E) QUOTE DOES NOT INCLUDE ANY PANEL MOUNTING HARDWARE
- F) QUOTE DOES NOT INCLUDE ANY DISCONNECTS OR PULL BOXES.
- G) QUOTE DOES NOT INCLUDE ANY IMPULSE PIPING OR PROCESS TAPS.
- H) QUOTE DOES NOT INCLUDE ANY VALVES OR VALVE ACTUATOR ACTUATOR.
- I) QUOTE DOES NOT INCLUDE HPP-9 VARIABLE FREQUNCY DRIVE.

#### ITEM NO.1

VALVE CONTROL PANEL PCPMOVRO2 MODIFICATIONS (CV-1*34 SWING PUMP VALVES)	
EATON / CUTLER HAMMER AN56BNOAC NEMA SIZE 0 3-PHASE REVERSING STARTER	3
EATON / CUTLER HAMMER H2005B-3 CLASS 20 HEATER PACKS, 1.2-1.96A, 3/CARTON	3
EATON / CUTLER HAMMER GMCP003AOC 3A 3-POLE G-FRAME BREAKER	3
EATON / CUTLER HAMMER 1294C01H01 BREAKER LOCK DOG	3
ALLEN-BRADLEY 1492-GH005 1P 120V 0.5A CIRCUIT BREAKER	3
ALLEN-BRADLEY 1492-GH050 1P 120V 5A CIRCUIT BREAKER	3
WIRES, TERMINALS, NAMEPLATES	LOT
ITEM NO.2	
HS2-1634, HS2-1734, HS2-1834 SWING PUMP VALVES OPERATOR STATION (3-REQ'D)	
SQUARE-D 9001SKY3 3-HOLE POLYMERIC CONTROL STATION	3

3

SQD 9001SKS43B 3 POSITION SELECTOR SWITCH

SQD 9001SKR1U 30MM MOMENTARY PUSH BUTTON OPERATOR SQD 9001KA1 30MM CONTACT BLOCK, 10A, (1)NO / (1)NC, SCREW CLAMP TERMINAL LABELS	6 12 LOT
ITEM NO.3	
HIGH PRESSURE PUMP NO.9 OPERATOR PUSH BUTTON STATION	
SQUARE-D 9001SKY111 1-HOLE POLYMERIC CONTROL STATION WITH HOA SELECTOR	1
ITEM NO.4	
HPP-9 PUMP INLET PRESSURE GAUGE ASSEMBLY	
ASHCROFT 45-1279AS-04L-XNHPD-100# DURAGAUGE PLUS 4.5" DIAL PROCESS GAUGE	1
A) RANGE: 0 TO 100 PSI	
B) 316L STAINLESS STEEL BOURDON TUEB AND SOCKET	
C) 1/2 IN MNPT LOWER STEM CONNECTION	
D) SEAL: BUNA-N	
E) ACRYLIC WINDOW, SILICONE FILL	
F) TAGS: <b>PI-1940</b> ASHCROFT 02-1112SD-25 PRESSURE SNUBBER, 303 SST. BODY	INCL
ASHCROFT 50-201SS-02T-XCKPUSE SERIES THREADED DIAPHRAGM SEAL	INCL
A) 1/2" NPT FEMALE PROCESS CONNECTION	
B) 1/2" NPT FEMALE INSTRUMENT CONNECTION	
C) 316L STAINLESS STEEL HOUSING	
D) 316L STAINLESS STEEL DIAPHRAGM MATERIAL	
E) 1/4" FLUSHING PORT IN LOWER HOUSING	
JAMESBURY 1/4-33-3600TL 1/4" 316 S.S. BALL VALVE	1
JAMESBURY 1/2-33-3600TL 1/2" 316 S.S. BALL VALVE 1/4" x 2" 316 STAINLESS STEEL NIPPLE	1 2
1/4" STAINLESS STEEL ELBOW	1
1/2" x 2" 316 STAINLESS STEEL NIPPLE	2
1/2" x 4" 316 STAINLESS STEEL NIPPLE	1
ITEM NO.5	
HPP-9 PUMP INLET PRESSURE TRANSMITTER ASSEMBLY	
ROSEMOUNT 3051S PRESSURE TRANSMITTER	1
A) RANGE: -14 TO 2000 PSI	
B) OUTPUT: 4-20MADC WITH HART	
C) PROCESS CONN.: 316L TRADITIONAL FLANGE 1/4-18 NPT	
D) HOUSING: ALUMINUM WITH 1/2-14 NPT	
F) DISPLAY: PLANTWEB LCD	
H) ASSEMBLE TO ROSEMOUNT CONVENSIONAL 304 INTEGRAL MANIFOLD  I) TAGS: <b>PIT-1940</b>	
ROSEMOUNT 0304 IN-LINE MANIFOLD WITH THE FOLLOWING:	1
A) MANIFOLD STYLE: THREADED	_
B) MANIFOLD TYPE: 2-VALVE	
C) BODY   BONNET   STEM   TIP: SST   SST   SST   316 SST	
D) PROCESS CONN. 1/2-14 FNPT	
E) PACKING MATERIAL: PTFE	
F) VALVE SEAT: INTEGRAL SQD SSP030SSE10HC 4/20MA PIPE STYLE SURGE ARRESTER	1
JAMESBURY 1/2-33-3600TL 1/2" 316 S.S. BALL VALVE	1 2
1/2" STAINLESS STEEL TEE	1
1/2" x 2" 316 STAINLESS STEEL NIPPLE	3
1/2" x 4" 316 STAINLESS STEEL NIPPLE	1
2" X 60" ALUMINUM PIPE STANCHION W/ 10" X 10" X 1/2" ALUMINUM BASE	1
MISC. BRACKET HARWARE	LOT

#### ITEM NO.6

ITEM NO.6	
HPP-9 PUMP OUTLET PRESSURE GAUGE ASSEMBLY	
ASHCROFT 1279 DURAGAUGE PLUS 4.5" DIAL PROCESS GAUGE	1
A) RANGE: 0 TO 200 PSI	
B) 316L STAINLESS STEEL BOURDON TUEB AND SOCKET	
C) 1/2 IN MNPT LOWER STEM CONNECTION	
D) SEAL: BUNA-N	
E) ACRYLIC WINDOW, SILICONE FILL	
F) TAGS: <b>PI-1942</b>	
ASHCROFT 02-1112SD-25 PRESSURE SNUBBER, 303 SST. BODY	INCL
ASHCROFT 50-201SS-02T-XCKPUSE SERIES THREADED DIAPHRAGM SEAL	INCL
A) 1/2" NPT FEMALE PROCESS CONNECTION	
B) 1/2" NPT FEMALE INSTRUMENT CONNECTION	
C) 316L STAINLESS STEEL HOUSING	
D) 316L STAINLESS STEEL DIAPHRAGM MATERIAL	
E) 1/4" FLUSHING PORT IN LOWER HOUSING	
JAMESBURY 1/4-33-3600TL 1/4" 316 S.S. BALL VALVE	1
JAMESBURY 1/2-33-3600TL 1/2" 316 S.S. BALL VALVE	1
1/4" x 2" 316 STAINLESS STEEL NIPPLE	2
1/4" STAINLESS STEEL ELBOW	1
1/2" x 2" 316 STAINLESS STEEL NIPPLE	2
1/2" x 4" 316 STAINLESS STEEL NIPPLE	1
1/2 X4 S10 STAINCESS STEEL NIFFEE	1
ITEM NO.7	
HPP-9 PUMP OUTLET PRESSURE TRANSMITTER ASSEMBLY ROSEMOUNT 3051S PRESSURE TRANSMITTER	1
	1
A) RANGE: -14 TO 2000 PSI	
B) OUTPUT: 4-20MADC WITH HART	
C) PROCESS CONN.: 316L TRADITIONAL FLANGE 1/4-18 NPT	
D) HOUSING: ALUMINUM WITH 1/2-14 NPT	
F) DISPLAY: PLANTWEB LCD	
H) ASSEMBLE TO ROSEMOUNT CONVENSIONAL 304 INTEGRAL MANIFOLD	
I) TAGS: <b>PIT-1942</b>	
ROSEMOUNT 0304 IN-LINE MANIFOLD WITH THE FOLLOWING:	1
A) MANIFOLD STYLE: THREADED	
B) MANIFOLD TYPE: 2-VALVE	
C) BODY   BONNET   STEM   TIP: SST   SST   SST   316 SST	
D) PROCESS CONN. 1/2-14 FNPT	
E) PACKING MATERIAL: PTFE	
F) VALVE SEAT: INTEGRAL	
SQD SSP030SSE10HC 4/20MA PIPE STYLE SURGE ARRESTER	1
JAMESBURY 1/2-33-3600TL 1/2" 316 S.S. BALL VALVE	2
1/2" STAINLESS STEEL TEE	1
1/2" x 2" 316 STAINLESS STEEL NIPPLE	3
1/2" x 4" 316 STAINLESS STEEL NIPPLE	1
2" X 60" ALUMINUM PIPE STANCHION W/ 10" X 10" X 1/2" ALUMINUM BASE	1
MISC. BRACKET HARWARE	LOT
ITEM NO.8	
PROJECT SERVICES	
ENGINEERING	LOT
SUBMITTALS	LOT
PLC PROGRAMMING	LOT
SCADA PROGRAMMING	LOT
0	201

TESTING START-UP	LOT LOT	
TRAINING	LOT	
O & M MANUALS	LOT	
WARRANTY, 1-YEAR	LOT	
********* BID ALTERNATIVE #1 ****************	:	
ITEM NO.9		
VALVE CONTROL PANEL PCPMOVRO2 MODIFICATIONS (CV-1*20 CONCENTRATE VALVES)		
EATON / CUTLER HAMMER ANS6BNOAC NEMA SIZE 0 3-PHASE REVERSING STARTER	3	
EATON / CUTLER HAMMER H2005B-3 CLASS 20 HEATER PACKS, 1.2-1.96A, 3/CARTON	3	
EATON / CUTLER HAMMER GMCP003AOC 3A 3-POLE G-FRAME BREAKER	3	
EATON / CUTLER HAMMER 1294C01H01 BREAKER LOCK DOG	3	
ALLEN-BRADLEY 1492-GH005 1P 120V 0.5A CIRCUIT BREAKER	3	
ALLEN-BRADLEY 1492-GH050 1P 120V 5A CIRCUIT BREAKER	LOT	
WIRES, TERMINALS, NAMEPLATES	LUI	
ITEM NO.10		
HS1-1620, HS1-1720, HS1-1820 CONCENTRATE VALVES OPERATOR STATION (3 REQ'D)		
SQUARE-D 9001SKY3 3-HOLE POLYMERIC CONTROL STATION	3	
SQD 9001SKS43B 3 POSITION SELECTOR SWITCH	3	
SQD 9001SKR1U 30MM MOMENTARY PUSH BUTTON OPERATOR	6	
SQD 9001KA1 30MM CONTACT BLOCK, 10A, (1)NO / (1)NC, SCREW CLAMP TERMINAL	12	
LABELS	LOT	
ITEM NO.11  MAIN CONTROL PANEL PLC-RO2 MODIFICATIONS		
ALLEN-BRADLEY 1756-A7 CONTROLLOGIX 7-SLOT MOUNTING CHASSIS RACK	1	
ALLEN-BRADLEY 1756-PA72 CONTROLLOGIX POWER SUPPLY, 85-256VAC, 75W	1	
ALLEN-BRADLEY 1756-IB16 CONTROLLOGIX DIGITAL INPUT, 16-POINT, 24VDC	1	
ALLEN-BRADLEY 1756-OB16I CONTROLLOGIX ISOLATED DIGITAL OUTPUT, 16-POINT, 12/24VDC	1	
ALLEN BRADLEY 1756-TBCH TERMINAL BLOCK, 36-PIN CAGE CLAMP BLOCK	2	
PHOENIX CONTACT 2838322 PT 4X1-24DC-ST PLUGTRAB PT SURGE PROTECTION PLUG	4	
PHOENIX CONTACT 2839363 PT 4X1-BE PLUGTRAB PT SURGE PROTECTION BASE	4	
FINDER 60.13.9.024.0070 60 SERIES RELAYS, 3PDT, 10A, 24VDC, LED	8	
FINDER 90.27SMA DIN RAIL 11-PINS RELAY SOCKET, SCREW TERMINAL	8	
WIRES, TERMINALS, LABELS	LOT	
ITEM NO.12		
ADDITONAL PROJECT SERVICES	LOT	
ENGINEERING SUBMITTALS	LOT	
SUBMITTALS PLC PROGRAMMING	LOT	
TESTING	LOT LOT	
START-UP	LOT	
O & M MANUALS	LOT	
WARRANTY, 1-YEAR	LOT	
CLIMAMADV		CELL
SUMMARY ITEMS NO.1 THRU NO.8 HIGH PRESSURE PUMP #9 ADDITION (BASE BID)		<b>SELL</b> \$72,700.00
ITEMS NO.1 THRU NO.8 HIGH PRESSURE PUMP #9 ADDITION (BASE BID)  CONCENTRATE PIPING IMPROVEMENTS (BID ALTERNATIVE #1)		\$42,700.00
CONCENTRATE PIPING IMPROVEMENTS (BID ALTERNATIVE #1)		\$42,700.00

TOTAL: \$115,400.00 PLUS TAX

**SUBMITTAL:** 6-8 WEEKS (AFTER RECEIPT OF PURCHASE ORDER)

**DELIVERY:** 18-20 WEEKS (AFTER APPROVED DRAWINGS)

FOB: JOB SITE

TERMS: NET 30 DAYS (SUBJECT TO CREDIT APPROVAL)

WARRANTY: ALL WARRANTIES SHALL EXPIRE ONE (1) YEAR FROM DATE OF START-UP

FROM SELLER TO BUYER UNLESS SPECIALLY INDICATED OTHERWISE AND WILL BE NULL AND VOID UNLESS MATERIALS ARE STORED UNDER PROPER


CONDITIONS DETERMINED BY C.C. CONTROL CORP.

JUAN REYES

<u>ireyes@cccontrolcorp.com</u>



## **SECTION 4 – EXHIBIT R3 CONSTRUCTION SCHEDULE**



VOW WTP HPP 9	9 Improvements						Village	of Wellingto	on																	29-Au	ug-25 08:49
ctivity ID	Activity Name	Original Duration	Actual Duration	Remaining Duration	Duration % Complete	Start	Finish	Total Float	Oct Nov	/ Dec	c Jan	Feb	Mar	Apr	May	2026 Jun	3 Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb I	2027 Mar Apr	May	Jun Jul
A1640	Install Variable Frequency Drive	5	0	5	0%	20-Jan-27	27-Jan-27	0	oci Ivov	, Dec	o Jan	100	IVIGI	, Api	iviay	Juli	Jui	Aug	ОСР	OCI	1404	DCC			ble Frequenc		Juli Juli
A1660	HPP 9 Instrumentation & Controls Modifications	10	0	10	0%	27-Jan-27	10-Feb-27	0					¦	†	·				 	† <u> </u>				HPP 9	Instrumentatio	n & Contr	rols Modifcation
A1620	HPP 9 Painting & Coatings	3	0	3	0%	28-Jan-27	30-Jan-27	11																HPP 9 Pa	nting & Coatin	igs	
A1630	HPP 9 Piping & Valve Modifications Tie-In	5	0	5	0%	10-Feb-27	17-Feb-27	0							į									HPP	9 Piping & Val	lve Modific	cations Tie-In
Start Up & Tes	sting	10	0	10	0%	17-Feb-27	03-Mar-27	0																1 1	3-Mar-27, Sta		
A1580	Start Up & Test HPP 9 & Cartridge Filter	10	0	10	0%	17-Feb-27	03-Mar-27	0							į		- 1		ļ					:	Start Up & Test	HPP9&	Cartridge Filter
Alt Bid - Cond	centrate Piping Improvements Trains 6, 7, & 8	112	0	112	0%	08-Sep-26	11-Feb-27	14											_					11-Fel	-27, Alt Bid - C	concentra	ate Piping Impro
NF Train 6 Mod	difications	25	0	25	0%	08-Sep-26	13-Oct-26	0									į		-		Oct-26, N			cations			
A2060	Train 6 Pipe and Valve Modifications	5	0	5	0%	08-Sep-26	15-Sep-26	0		İ					į		į		_ T	rain 6 Pipe	and Val	ve Modifi	cations				
A2070	Train 6 Electrical Modifications	15	0	15	0%	15-Sep-26	06-Oct-26	0											_	<b>T</b> rain	6 Electric	al Modific	cations				
A2080	Train 6 Instrumentation & Controls Modifications	5	0	5	0%	06-Oct-26	13-Oct-26	0							į					■ Tra				ntrols Modific			
NF Train 7 Mod	difications	25	0	25	0%	04-Nov-26	09-Dec-26	0											-					NF Train 7 M			
A2020	Train 7 Pipe and Valve Modifications	5	0	5	0%	04-Nov-26	11-Nov-26	0							į		1				_ ;	' ;		ve Modification			
A2030	Train 7 Electrical Modifications	15	0	15	0%	11-Nov-26	02-Dec-26	0		İ	i				į		İ		i				i	al Modification	i i		
A2040	Train 7 Instrumentation & Controls Modifications	5	0	5	0%	02-Dec-26	09-Dec-26	0							į		1					Train		1 1 1	Controls Mod	: :	; ;
NF Train 8 Mod	difications	25	0	25	0%	31-Dec-26	04-Feb-27	14		!				jj					1						27, NF Train 8		ons
A1710	Train 8 Pipe and Valve Modifications	5	0	5	0%	31-Dec-26	07-Jan-27	14														ţ		1 1	Valve Modifica	i i	
A1720	Train 8 Electrical Modifications	15	0	15	0%	07-Jan-27	28-Jan-27	14									1							1	ctrica¦l Modifica	1 1	
A1730	Train 8 Instrumentation & Controls Modifications	5	0	5	0%	28-Jan-27	04-Feb-27	14							}		1		-					T :	1	: :	ols Modification
Start Up & Tes	5	87	0	87		13-Oct-26	11-Feb-27	14									1					:		1 .	-27, Start Up	& Testing	
A2110	Start Up & Test Train 6 Concentrate Control Valves	5	0	5	-	13-Oct-26	20-Oct-26	0												<b> </b> Si	tart Up &			ncentrate Co		:	
A2100	Start Up & Test Train 7 Concentrate Control Valves	5	0	5	0%	09-Dec-26	16-Dec-26	0							1		-		-			Sta	art Up &	, ,	Concentrate (		
A1310	Start Up & Test Train 8 Concentrate Control Valves	5	0	5	0%	04-Feb-27	11-Feb-27	14									Ì		}					Start U	p & Test Train	8 Concer	ntrate Control \

Milestone

Summary

Wellington High Pressure Pump 9 Improvements Owner: Village of Wellington Engineer: Kimley-Horn Contractor: Wharton-Smith Construction Group

Data Date: 11-Nov-25 Finish Date: 16-Apr-27 Page 2 of 2







### **SECTION 5 – EXHIBIT R4 CONSTRUCTION MANAGER'S ALLOWANCES**

The GMP includes the following Allowances for work items with undefined scopes at this time. Please note that the allowances are currently shown below the line without fee, fee to be included on allowance usage once brought into the project as approved by the Village of Wellington.

- Base Bid:
  - a. Coatings \$35,000
  - b. Independent Testing \$10,000
  - c. Flow Meter Installation \$130,000
- Alternate Bid: None



#### SECTION 6 – EXHIBIT R5 ASSUMPTIONS AND CLARIFICATIONS

Please note the following assumptions and clarifications regarding this proposal:

- 1. The work is in accordance with Kimley-Horn's "Membrane Plant #2 (M2) High Pressure Pump 9 Improvements" conformed documents dated May 2025. Please refer to Section 2 for the Drawings and Specifications.
- 2. The GMP includes work for High Pressure Pump 9 along with the associated piping and Trains 6, 7, and 8 concentrate piping modifications. Pricing for the bid proposals received will remain valid for a period of one hundred and eighty (180) days after the bid date.
- 3. We have included an Owner Controlled Contingency of \$98,829.00. Please note that this contingency is currently shown below the line without fee, fee to be included on contingency usage once brought into the project as approved by the Village of Wellington.
- 4. We have included the following allowances for work items with undefined scopes at this time. Please note that the allowances are currently shown below the line without fee, fee to be included on allowance usage once brought into the project as approved by the Village of Wellington.
  - a. Coatings \$35,000
  - b. Independent Testing \$10,000
  - c. Flow Meter Installation \$130,000
- 5. We have included a performance and payment bond and insurance.
- 6. ERP, FDEP, FDOT, & ROW permit fees are by others.
- 7. Village of Wellington Building Department fees are by others.
- 8. Costs associated with Davis-Bacon Wages & AIS requirements have not been included.
- 9. It is assumed that the Village of Wellington will provide power and water for use during construction and startup at no cost.
- 10. We have not included any costs for Lead/Asbestos Survey nor abatement of any kind.
- 11. Pricing includes no knowledge of buried or concealed conditions beyond what is indicated or shown on documents received to date. Unforeseen conflicts and utilities will be submitted as additional costs.
- 12. All Pricing (Labor, Material, Equipment, Subcontract) is based on current market value with no escalation or inflation adjustment. Duration of Material lead times are based on current market conditions.
- 13. The following is Owner furnished equipment:
  - a. High Pressure Pump 9, Motor and Can
  - b. Cartridge Filter Housing
  - c. Micron Filters
  - d. VFD
- 14. Owner furnished Equipment is subject to Engineer's shop drawing submittal review and approval. The Equipment services and features specified within Bid Documents are to be verified by Direct Purchaser prior to their system integration by Contractor.
- 15. We have included administrative costs to coordinate field services with Owner furnished equipment vendors. This is limited to communication and scheduling. Wharton Smith and subcontractors are not responsible for delays associated with these vendors.
- 16. Procurement, review, submission, and copies of Operation and Maintenance Manuals for Owner Furnished Equipment is excluded. It is the Owner's responsibility to coordinate this effort and share all pertinent information with Wharton Smith in a timely manner.
- 17. All work required per Specification Section 02670 *Flushing, Testing and Disinfection* is excluded as no discharge and bacteriological sampling locations have been identified in the bid drawings. Wharton Smith responsibility will be limited to swabbing all new piping to be installed on the Raw Water Feed System. If



required, additional form of disinfection, temporary piping, flushing, and bacteriological sampling will be coordinated with the Owner and submitted as additional cost.

- 18. Spare Parts for all Owner Furnished Equipment are excluded.
- 19. Factory testing for all Owner Furnished Equipment is excluded. This includes coordinating, reviewing test reports, and submission.
- 20. Vibration testing costs per Specification Section 11936 *Vertical Turbine High Pressure Pump* and Specification Section 13080 *Vibration and Alignment*, are excluded as these costs were carried by Afton for Owner Furnished HPP 9. Wharton Smith responsibility will be limited to coordinating with Afton.
- 21. Part 1 of Specification Sections 16480 and 16485/16495 is excluded since the manufacturer's services were included in the direct Purchase Order from the Village of Wellington to Schneider.
- 22. Offloading and storage of Owner Furnished Equipment is excluded.
- 23. Part 3.1 of Specification Section 16485/16495 states that a 10% payment retainage will be released to Contractor upon final acceptance of the work. Per Executed CMAR Agreement, a 5% retainage will be held.
- 24. Additional material cost or delays to the Project Schedule due to Owner or Owner's contracted Supplier will be assessed and Contractor reserves the right to submit any applicable claims within the Terms and Conditions of the Contract.
- 25. It is assumed that the 10" 90° bends can be modified and reinstalled, therefore, we have included cost for these modifications per General Note No. 9 on Sheet M-2. If for reasons outside of our control, new 90° bends are required, a Contingency Authorization Request will be submitted for the additional cost.
- 26. Cost to modify existing grating is included as shown in the bid documents. Additional modifications will be submitted as additional cost.
- 27. As requested by the Village of Wellington, cost to furnish the micron filters is not included.
- 28. Coiling, hanging, or arranging of existing wiring and other items present within existing PLC-RO2 or PCPMOVRO2 is excluded.
- 29. Contractor has excluded cost to perform post-construction inspection referenced in Spec Section 01700-1.9. It is the Owner's responsibility to send notification of any deficiencies concerning material, equipment, and workmanship furnished by Wharton Smith within the warranty period established in the bid documents. Deficiencies relating to Owner Furnished Equipment will be the sole responsibility of the Owner.
- 30. It is assumed that Engineer and Owner will review and return submittals within 14 calendar days. RFIs and resubmittals shall be returned within 7 calendar days.
- 31. It is assumed that Contractor will utilize the Owner's existing gantry crane and that the crane's capacity is sufficient for the cartridge filter and HPP. Should the gantry crane capacity not be sufficient, Contractor will seek alternate method of hoisting for additional cost.
- 32. Pricing only includes materials and equipment specified in the bid documents. As there are no references to the Village's Approved Product List (APL), those approved products have been excluded.
- 33. Please refer to Section 4 for the proposed GMP schedule. Please note that the P6 schedule is referenced in "work days" as the program automatically accounts for weekends and holidays. The contract time is expressed in "calendar days". 508 calendar days from Notice of Commencement to Final Completion indicated equates to the 522 work days shown in the P6 schedule. Our current estimated duration of onsite construction is 8 months.



#### **SECTION 7 – EXHIBIT R6 LIST OF EXTENDED WARRANTIES**

The Construction Manager's warranty and the warranty of all subcontractors and suppliers will be in accordance with the Construction Manager at Risk Agreement and the Contract Documents. All work shall be warranted for a period of one (1) year from date of final acceptance by the owner or the manufacturer's standard warranty period, whichever is greater.

Extended warranties as required by the contract specifications will be furnished to the Owner during the closeout phase and prior to receipt of final payment.



## **SECTION 8 – EXHIBIT R7 GENERAL CONDITIONS AND GENERAL REQUIREMENTS**



# Wharton-Smith, Inc. CONSTRUCTION GROUP

	JOB NAME:	VOW WTP Mem	nbrane Plant #2	(M2) HPP 9 Im	provements – BASI	
	ESTIMATE #:	1				

				DIRECT MANH				MANWEEKS								
GENERAL CONDITIONS	DURATION =		5	MONTHS, PLA	NNED		2	MEN								
			MH/	BASE		LABOR			EQUIP	MENT	N	IATERIAL		SUBCONT	RACTS	
DESCRIPTION	QTY	UNIT	UNIT	RATE	U/P	TOTAL MH	\$ AMOUNT	HR/UNIT R	ATE	\$ AMOUNT	U/P	\$ AMOUNT	\$ AMOUNT	U/P	\$ AMOUNT	\$ TOTALS
PROJECT MANAGEMENT TEAM													W/ 7% TAX			
FIELD STAFF																
SUPERINTENDENT	22	WK	40	\$157.00	\$6,280	\$866	\$135,962			\$0		\$0	\$0		\$0	\$135,962
OFFICE STAFF																
PROJECT MANAGER		WK	40	\$157.00	\$6,280	\$866	\$135,962			\$0		\$0			\$0	\$135,962
PROJECT ENGINEER		WK	40	\$96.00	\$3,840	\$866	\$83,136			\$0		\$0			\$0	\$83,136
PROJECT ASSISTANT	22	WK	24	\$80.00	\$1,920	\$520	\$41,568			\$0		\$0	\$0		\$0	\$41,568
OTHER STAFF																
COST ACCOUNTANT		WK	16	\$124.00	\$1,984	\$346	\$42,954			\$0		\$0			\$0	\$42,954
SAFETY COORDINATOR	22	WK	4	\$140.00	\$560	\$87	\$12,124			\$0		\$0	\$0		\$0	\$12,124
RELATED MANAGEMENT COSTS		,														
SOFTWARE COSTS	1	LS		\$50.00	\$0	\$0	\$0			\$0		\$0	\$0	\$3,932	\$3,932	\$3,932
TEMP.FACILITIES & UTILITIES																
WATER, MONTHLY	5	МО		\$50.00	\$0	\$0	\$0			\$0	\$250	\$1,250	\$1,338		\$0	\$1,338
INTERNET/TELEPHONE, MONTHLY CHARGES - W-S	5	МО		\$50.00	\$0	\$0	\$0			\$0	\$200	\$1,000			\$0	\$1,070
CELLULAR TELEPHONE, MONTHLY CHARGES	5	МО		\$50.00	\$0	\$0	\$0			\$0	\$300	\$1,500	\$1,605		\$0	\$1,605
FIELD OFFICE, WHARTON SMITH INC	5	МО	5	\$50.00	\$250	\$25	\$1,250			\$0	\$8,000	\$40,000	\$42,800		\$0	\$44,050
JOB OFFICE SUPPLIES	5	МО		\$50.00	\$0	\$0	\$0			\$0	\$750	\$3,750	\$4,013		\$0	\$4,013
COMPUTER EQUIPMENT FOR FIELD OFFICE - W-S	1	LS		\$50.00	\$0	\$0	\$0			\$0	\$2,000	\$2,000	\$2,140		\$0	\$2,140
TOOL TRAILERS - 1 REQUIRED	5	МО		\$50.00	\$0	\$0	\$0			\$0	\$250	\$1,250	\$1,338		\$0	\$1,338
TEMPORARY TOILETS - 1 REQUIRED	5	МО		\$50.00	\$0	\$0	\$0			\$0	\$150	\$750	\$803		\$0	\$803
TEMPORARY SEWAGE HOLDING TANKS - ENGINEER & W-S	5	МО		\$50.00	\$0	\$0	\$0			\$0	\$300	\$1,500	\$1,605		\$0	\$1,605
CONSTRUCTION EQUIPMENT & TOOLS																
SMALL TOOLS AND SUPPLIES	1	LS		\$50.00	\$0	\$0	\$0			\$0	\$4,800	\$4,800	\$5,136		\$0	\$5,136
SAFETY & HEALTH & HOUSEKEEPING			<u>"</u>	"		<u>"</u>					"		"		·	
SAFETY DEVICES	1	LS		\$50.00	\$0	\$0	\$0			\$0	\$3,000	\$3,000	\$3,210		\$0	\$3,210
CLEAN-UP AT END OF PROJECT	1	LS	80	\$50.00	\$4,000	\$80	\$4,000			\$0		\$0	\$0		\$0	\$4,000
CLEAN-UP THROUGHOUT DURATION OF PROJECT	22	WK	4	\$50.00	\$200	\$87	\$4,330			\$0		\$0	\$0		\$0	\$4,330
DUMPSTERS	5	МО		\$50.00	\$0	\$0	\$0			\$0	\$1,250	\$6,250	\$6,688		\$0	\$6,688
JANITORIAL	22	WK		\$50.00	\$0	\$0	\$0			\$0		\$0	\$0	\$280	\$6,062	\$6,062
TOTAL GENERAL CONDITIONS						\$3,742	\$461,287			\$0			\$71,744		\$9,994	\$543,023
																40 10 10 10
GENERAL REQUIREMENTS																
PERMITS, FEES, INSURANCE, LEGAL, ETC.																
BUILDER'S RISK INSURANCE-COASTAL COUNTY	F	МО		\$50.00	¢^	\$0	\$0			\$0		\$0	\$0	\$250	\$2,850	\$2,850
PROJECT DOCUMENTATION AND SERVICES	3	IVIO		\$ 3U.UU	\$0	20	<b>3</b> 0			30		\$0	20	\$230	\$2,030	\$2,650
PHOTOGRAPHS	F	МО		\$50.00	40	¢0	40			40	\$150	\$750	\$803		40	¢ 0 ^ 2
					\$0 \$0		\$0			\$0	\$130			¢2 E00	\$0	\$803
PRE-CONSTRUCTION AUDIO-VIDEO DOCUMENTATION	ı	LS		\$50.00	\$0	\$0	\$0			\$0		\$0	\$0	\$2,500	\$2,500	\$2,500

							JOB NAME: VO	W WTP Membra	ane Plant #2	(M2) HPP 9 Im	provements – BAS	SE	
							ESTIMATE #: 1						
			What cons		Smith,								
DESIGN SERVICES (CADD) – AS-BUILTS	1 LS	40	\$65.00	\$2,600	\$40	\$2,600	 \$0		\$0	\$0		\$0	\$2,600
PLANS & SPECIFICATIONS REPRODUCTION COSTS	1 LS		\$50.00	\$0	\$0	\$0	\$0	\$1,500	\$1,500	\$1,605		\$0	\$1,605
TOTAL GENERAL REQUIREMENTS					\$40	\$2,600	\$0			\$2,408		\$5,351	\$10,358



# Wharton-Smith, Inc. CONSTRUCTION GROUP

JOB NAME:	VOW WTP Men	/OW WTP Membrane Plant #2 (M2) HPP 9 Improvements - BASE											
ESTIMATE #:	1												

			960	DIRECT MANH				MANWEEKS								
GENERAL CONDITIONS	DURATION =		2.0	MONTHS, PLAI	NNED		1	MEN								
			MH/	BASE		LABOR			EQUIPI	MENT	N	MATERIAL		SUBCONT	RACTS	
DESCRIPTION	QTY	UNIT	UNIT	RATE	U/P	TOTAL MH	\$ AMOUNT	HR/UNIT	RATE	\$ AMOUNT	U/P	\$ AMOUNT	\$ AMOUNT	U/P	\$ AMOUNT	\$ TOTALS
PROJECT MANAGEMENT TEAM													W/ 7% TAX			
FIELD STAFF																
SUPERINTENDENT	9	WK	24	\$157.00	\$3,768	\$208	\$32,706			\$0		\$0	\$0		\$0	\$32,706
OFFICE STAFF																
PROJECT MANAGER	9	WK	16	\$157.00	\$2,512	\$139	\$21,804			\$0		\$0	\$0		\$0	\$21,804
PROJECT ENGINEER	9	WK	24	\$96.00	\$2,304	\$208	\$19,999			\$0		\$0	\$0		\$0	\$19,999
PROJECT ASSISTANT	9	WK	8	\$80.00	\$640	\$69	\$5,555			\$0		\$0	\$0		\$0	\$5,555
OTHER STAFF																
COST ACCOUNTANT	9	WK	4	\$124.00	\$496	\$35	\$4,305			\$0		\$0	\$0		\$0	\$4,305
SAFETY COORDINATOR	9	WK	4	\$140.00	\$560	\$35	\$4,861			\$0		\$0	\$0		\$0	\$4,861
RELATED MANAGEMENT COSTS		'	,	·	'	<u>'</u>		,		'	'	'			'	
SOFTWARE COSTS	1	LS		\$50.00	\$0	\$0	\$0			\$0		\$0	\$0	\$880	\$880	\$880
TEMP.FACILITIES & UTILITIES		,		,		,		,		'	'	'			,	
WATER, MONTHLY	2	МО		\$50.00	\$0	\$0	\$0			\$0	\$250	\$500	\$535		\$0	\$535
INTERNET/TELEPHONE, MONTHLY CHARGES - W-S	2	МО		\$50.00	\$0	\$0	\$0			\$0	\$200	\$400	\$428		\$0	\$428
CELLULAR TELEPHONE, MONTHLY CHARGES	2	МО		\$50.00	\$0	\$0	\$0			\$0	\$300	\$600	\$642		\$0	\$642
FIELD OFFICE, WHARTON SMITH INC	2	МО	5	\$50.00	\$250	\$10	\$500			\$0	\$8,000	\$16,000	\$17,120		\$0	\$17,620
JOB OFFICE SUPPLIES	2	МО		\$50.00	\$0	\$0	\$0			\$0	\$750	\$1,500	\$1,605		\$0	\$1,605
COMPUTER EQUIPMENT FOR FIELD OFFICE - W-S	1	LS		\$50.00	\$0	\$0	\$0			\$0	\$2,000	\$2,000	\$2,140		\$0	\$2,140
Tool trailers - <u>1</u> <b>required</b>	2	МО		\$50.00	\$0	\$0	\$0			\$0	\$250	\$500	\$535		\$0	\$535
TEMPORARY TOILETS - 1 REQUIRED	2	МО		\$50.00	\$0	\$0	\$0			\$0	\$150	\$300	\$321		\$0	\$321
TEMPORARY SEWAGE HOLDING TANKS - ENGINEER & W-S	2	МО		\$50.00	\$0	\$0	\$0			\$0	\$300	\$600	\$642		\$0	\$642
CONSTRUCTION EQUIPMENT & TOOLS		1			ļ			1								
SMALL TOOLS AND SUPPLIES	1	LS		\$50.00	\$0	\$0	\$0			\$0	\$2,880	\$2,880	\$3,082		\$0	\$3,082
SAFETY & HEALTH & HOUSEKEEPING		' '														
SAFETY DEVICES	1	LS		\$50.00	\$0	\$0	\$0			\$0	\$1,000	\$1,000	\$1,070		\$0	\$1,070
CLEAN-UP AT END OF PROJECT	1	LS	40	\$50.00	\$2,000	\$40	\$2,000			\$0		\$0	\$0		\$0	\$2,000
CLEAN-UP THROUGHOUT DURATION OF PROJECT	9	WK	4	\$50.00	\$200	\$35	\$1,736			\$0		\$0	\$0		\$0	\$1,736
DUMPSTERS	2	МО		\$50.00	\$0	\$0	\$0			\$0	\$1,250	\$2,500	\$2,675		\$0	\$2,675
JANITORIAL	9	WK		\$50.00	\$0	\$0	\$0			\$0		\$0	\$0	\$280	\$2,430	\$2,430
TOTAL GENERAL CONDITIONS						\$779	\$93,467			\$0			\$30,795		\$3,310	\$127,571
TOTAL GLIVERAL CONDITIONS													•			\$127,571
CENERAL REQUIREMENTS																
GENERAL REQUIREMENTS																
PERMITS, FEES, INSURANCE, LEGAL, ETC. BUILDER'S RISK INSURANCE-COASTAL COUNTY		1		. 1								. 1	, 1			
	2	MO		\$50.00	\$0.00		0.00			\$0		\$0				\$150
TOTAL GENERAL REQUIREMENTS						0.00	0.00			\$0			\$0		\$150	\$150



## **SECTION 9 – EXHIBIT R8 SUBMITTAL SCHEDULE**



## Wharton-Smith, Inc. CONSTRUCTION GROUP

		Sı	ubmittal Log: WTP Membrane Plant	#2 (M2) High Pı	ressure Pump 9 Improvements
Package	Submittal	Rev.	Title	Status	Comments
Div. 01			Schedule of Values	UNS	
			Preconstruction Video	UNS	
			Construction Schedule	UNS	
Div. 03			Concrete	UNS	
			Concrete Reinforcement	UNS	
Div. 09			Painting & Coatings	UNS	
Div. 11			Cartridge Filter Elements	UNS	
			Control Valves and Pipe Accessories	UNS	
Div. 15			Stainless Steel Piping	UNS	
Div. 16			Electrical	UNS	
Div. 17			Instrumentation & Controls	UNS	