



Central Division 400
 101 Sansbury's Way 332
 West Palm Beach, FL 33411
 Phone: (561) 793-9400
 Fax: (561) 790-4332
www.rangerconstruction.com

QUOTATION

Submitted To: Village of Wellington	Date: 04-Nov-21
Address: 14000 Greenbriar Boulevard Wellington, FL 33414	Phone: (954) 551 7567
Contact: Dennis Flaherty	Fax:
	Job Name: Aeroclub Dr.
	Job Location: Village of Wellington
	Prop. Owned By:

AEROCLUB DR

ITEM No.	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	EXTENSION
MILLING AND OVERLAY (overlay existing road + 3.5' widening final lift)					
1	Mill existing asphalt pavement (1.5")	38,000.00	SY	\$2.15	\$81,700.00
2	SP 12.5 Level C (>300 Tons Orders)	3,766.00	TN	\$100.00	\$376,600.00
INCLUDES MILLING 1.5" AND OVERLAY 1 1/2" (@165 LB/SY) ON 45,650 SY (3,766 TONS)					

SUBTOTAL **\$458,300.00**

WIDENING

3	MILL EXISTING ASPHALT 6.5" (Excavation)	8700	SY	\$2.15	\$18,705.00
4	ASPHALT OVERBUILD FULL DEPTH (OBG-01 >5" RAP) INCLUDES RAP MATERIAL 8,700 SY @ 525 LB/SY = 2,284 TONS	2284	TN	\$110.00	\$251,240.00

SUBTOTAL **\$269,945.00**

TOTAL **\$728,245.00**

1) This proposal specifically **EXCLUDES**:

- **Permitting**
- **Testing (by Engineer)**
- **survey/layout**
- **Excavation / Volume Replacement of unsuitable materials (muck, rock, gumbo, etc.)**
- **Landscaping**
- **Irrigation**
- **Tree Relocation / Root Pruning**
- **Retaining Walls**
- **Fencing**

Ranger Construction Industries, Inc.

101 Sansbury's Way
West Palm Beach, FL 33411

Phone: (561) 793-9400

Fax: (561) 790-4332

www.rangerconstruction.com

- **As built**
- **Erosion Control Plan**
- **Concrete repairs**
- **Concrete demolition**
- **Grading of swale/slope, backfill against widening section**
- **Proposed pavement markings, RPM's**
- **MOW strip, sod-grassing**
- **Final quantities based on field measurements**

2) INCLUSIONS:

- **Maintenance of Traffic**
- **Hauling and Disposal of excavated material**