

## **HOURLY PROPOSAL**

To: The Village of Wellington Date: 1/20/2017 Attn: Terry Narrow Quote Num: 16-5003R

Phone: (561) 312-5950 Page: 1 of 2

Email: <a href="mailto:tnarrow@wellingtonfl.gov">tnarrow@wellingtonfl.gov</a>

Job Location: Forest Hill Blvd & Polo Club Road

Job Description: Install 4' Square Conflict Structure with 2' Sump under 12 Reclaim Water Main.

Dear Mr. Narrow,

The following is a quote from D. S. Eakins Construction Corp. for the above referenced project based upon The Village of Wellington Annual Public Works Contract ITB#007-15/DZ.

Item #	Description	Quantity		<b>Unit Price</b>	Price
	Labor & Equipment				
37	Pipe Crew (up to 12" Dia PVC)	90.0 Hours	<u>@</u>	\$300.00 Per Hour	\$27,000.00
29	Dewatering System	120.0 Hours	<u>@</u>	\$45.00 Per Hour	\$5,400.00
8	Dump Truck Tri-Axle (18 CY)	45.0 Hours	@	\$70.00 Per Hour	\$3,150.00
			T	otal Labor Estimate =	\$35,550.00
	Materials				
	MOT Setup	1.0 EA	<u>@</u>	\$3,438.50 Each	\$3,438.50
	MOT	15.0 Days	<u>@</u>	\$258.75 Per Day	\$3,881.25
	Densities (Allowance)				\$900.00
	Precast Concrete Structure with R/C	1.0 EA	@	\$3,500.00 Each	\$3,500.00
	FDOT Reclaimed Concrete Agg. Base	18.0 CY	@	\$12.00 Per CY	\$216.00
	SP-12.5 Asphalt (For Patch)	10.0 Tons	@	\$75.00 Per Ton	\$750.00
	Excavatable Flowable Fill (Allowance)	8.0 CY	@	\$120.00 Per CY	\$960.00
	F Curb Replacement	1 LS	@	\$1,500.00 Each	\$1,500.00
	Paver Replacement (Allowance)	1 LS	@	\$3,750.00 Each	\$3,750.00
	Mill & Overlay 1 Lane 120 LF	1 LS	@	\$12,225.00 Each	\$12,225.00
	Thermo Pavement Markings	1 LS	@	\$2,500.00 Each	\$2,500.00
		Total Material Estimate =			

Note: All materials will be billed @ cost plus 10% mark up, which is included in above pricing.

**Total Estimate =** \$69,170.75



## **HOURLY PROPOSAL**

To: The Village of Wellington Date: 1/20/2017

Attn: Terry Narrow Quote Num: 16-5003R Phone: (561) 312-5950 Page: 2 of 2

Email: tnarrow@wellingtonfl.gov

Job Location: Forest Hill Blvd & Polo Club Road

Job Description: Install 4' Square Conflict Structure with 2' Sump under 12 Reclaim Water Main.

## **Project Schedule**

1 Toject Beneduie						
Task Name	Duration					
17-0006 Village of Wellington - Forest Hill Blvd. Conflict Structure	9 days					
Mobilize, Set up MOT, Saw Cut Asphalt/Concrete, Pot Hole Utilities Remove Pavers and Stack on Site	1 day					
Remove Asphalt/Concrete/Base & Install Dewatering System.	1.5 day					
Excavate, Shore/Sheet as Necessary, & Install Conflict Structure.	2 day					
Backfill, Compact, Remove Shoring/Sheeting & Remove Dewatering.	2 day					
Install 16" of Base Rock, Finish, & Install 3" of Asphalt.	1.5 days					
Clean up, Demobilize & Remove MOT	1 day					

Does Not Include: Permits, Permit Fees, Asbuilts, Survey, or Disposal of unsuitable materials.

Respectfully,

D. Steven Eakins

Vice President

D. S. Eakins Construction