

BID ACKNOWLEDGEMENT COVER PAGE

SUBMIT BIDS TO:

Wellington
Attn: Clerk's Office
12300 Forest Hill Blvd
Wellington, FL 33414

REFER ALL INQUIRIES TO PRIMARY CONTACT:

Purchasing Division
12300 Forest Hill Blvd
Wellington, FL 33414
Ph: 561-791-4107

Wellington INVITATION TO BID

BID TITLE:

Wastewater Treatment Facility Renewal and Rehabilitation Project

BID NO:

003-19/DZ

NAME OF FIRM, ENTITY, or ORGANIZATION:

Wharton-Smith, Inc.

NAME OF CONTACT PERSON

Sean White

VENDOR MAILING ADDRESS:

750 Monroe Rd
125 Indiantown Rd, Ste 201

CITY:

Sanford
Jupiter

ZIP:

32771
33458

STATE:

Florida
Florida

TITLE

Director of Preconstruction Services

VENDOR HEADQUARTERS ADDRESS (IF DIFFERENT):

750 Monroe Road

CITY:

Sanford

ZIP:

32771

STATE:

Florida

PHONE NUMBER:

Corporate: 407.321.8410

Local: 561.748-5956

FEDERAL EMPLOYER IDENTIFICATION NUMBER (EIN):

59-2392802

EMAIL ADDRESS:

swhite@whartonsmith.com

STATE OF FLORIDA BUSINESS LICENSE NUMBER (IF APPLICABLE)

CGC1511243

FAX NUMBER:

Corporate: 407.327.6984
Local: 561.748-5958

ORGANIZATIONAL STRUCTURE (Please Check One):

Corporation ☒

Partnership ☐

PROPRIETORSHIP ☐

Joint Venture ☐

Other ☐

If Corporation, please provide the following:

(A) Date of Incorporation: 04/02/1984

Month / Day / Year

(B) State or Country of Incorporation: Florida

BID PROPOSAL CHECKLIST

Please submit your proposal in this order

- YES X NO ___ 1. Bid submittal – one (1) original and one (1) PDF (CD) Copy
- YES X NO ___ 2. Bid Form signed by authorized representative
- YES X NO ___ 3. Acknowledgment of addendums
- YES X NO ___ 4. Bid Bond/Security or Cashier's Check
- YES X NO ___ 5. Schedule of Value
- YES X NO ___ 6. Schedule of Subcontractor/Supplies
- YES X NO ___ 7. Schedule of Equipment and Materials
- YES X NO ___ 8. Sworn Statement under Section 287.133(3) (a)
- YES X NO ___ 9. Drug Free Workplace
- YES X NO ___ 10. Trench Safety Affidavit
- YES X NO ___ 11. Questionnaire
- YES X NO ___ 12. References
- YES X NO ___ 13. Insurance Certificates
- YES X NO ___ 14. Copy of Appropriate Licenses
- YES X NO ___ 15. Proof of Workers Compensation Insurance/Workers Compensation Exemption
- YES X NO ___ 16. Local Preference Affidavit
- YES X NO ___ 17. Conflict of Interest Statement
- YES X NO ___ 18. Non-Collusion Affidavit
- YES X NO ___ 19. References and Prior Experience Form
- YES X NO ___ 20. Certification Pursuant To Florida Statute § 215.4725

BID FORM

(FAILURE TO COMPLETE THIS FORM MAY RESULT IN THE BID BEING DECLARED NON-RESPONSIVE)

PROJECT: Wastewater Treatment Facility Renewal and Rehabilitation Project Date: 02/06/2019

BIDDER: Wharton-Smith, Inc.

THIS BID IS SUBMITTED TO:

Wellington
Clerk's Office
12300 Forest Hill Boulevard
Wellington, FL 33414

1. The undersigned BIDDER proposes and agrees, if this Bid is accepted, to enter into an Agreement with OWNER in the form included in the Contract Documents to perform and furnish all Work as specified or indicated in the Contract Documents for the Contract Price and within the Contract Time indicated in this Bid and in accordance with the other terms and conditions of the Contract Documents.
2. BIDDER accepts all of the terms and conditions of the Advertisement or Invitation to Bid and Instructions to Bidders, including without limitation those dealing with the disposition of Bid security. This Bid will remain subject to acceptance for 180 days after the posting of the recommended award. BIDDER will sign and submit the Agreement with the Bonds and other documents required by the Bidding Requirements within 15 days after the date of OWNER'S Notice of Award.
3. In submitting this Bid, BIDDER represents, as more fully set forth in the Agreement, that:

(a) BIDDER has examined copies of all the Bidding Documents and of the following Addenda (receipt of all which is hereby acknowledged):

One	11/30/18
Two	12/17/18
Date Three	Addenda Number 11/30/18
Date Four	Addenda Number 01/04/19
Date Five	Addenda Number 01/23/19
Six	02/01/19

(b) BIDDER has familiarized itself with the nature and extent of the Contract Documents, Work, Site, locality, and all local conditions, Laws, and Regulations that in any manner may affect cost, progress, performance, or furnishing of the Work.

(c) BIDDER has studied carefully all reports and drawings of subsurface conditions and drawings of physical conditions which, if any, are attached to the Contract Documents, and accepts the determination as set forth in the Bidding Documents of the extent of the technical data contained in such reports and drawings upon which BIDDER is entitled to rely.

(d) BIDDER has obtained and carefully studied (or assumes responsibility for obtaining and carefully studying) all such examinations, investigations, explorations, tests and studies (in addition to or to supplement those referred to in (c) above) which pertain to the subsurface or physical conditions at the site or otherwise may affect the cost, progress, performance or furnishing of the Work as BIDDER considers necessary for the performance or furnishing of the Work at the Contract Price, within the Contract Time and in accordance with the other terms and conditions of the Contract Documents, and no additional examinations, investigations, explorations, tests, reports or similar information or data are or will be required by BIDDER for such purposes.

(e) BIDDER has reviewed and checked all information and data shown or indicated on the Contract Documents with respect to existing Underground Facilities at or contiguous to the site and assumes responsibility for the accurate location of said Underground Facilities. No additional examinations, investigations, explorations, tests, reports or similar information or data in respect of said Underground Facilities are or will be required by BIDDER in order to perform and furnish the Work at the Contract price, within the Contract Time and in accordance with the other terms and conditions of the Contract Documents.

(f) BIDDER has correlated the results of all such observations, examinations, investigations, explorations, tests, reports, and studies with the terms and conditions of the Contract Documents.

(g) BIDDER has given OWNER written notice of all conflicts, errors or discrepancies that it has discovered in the Contract Documents and the written resolution thereof by ENGINEER is acceptable to BIDDER.

(h) This Bid is genuine and not made in the interest of or on behalf of any undisclosed person, firm, or corporation and is not submitted in conformity with any agreement or rules of any group, association, organization or corporation; BIDDER has not directly or indirectly induced or solicited any other Bidder to submit a false or sham Bid; BIDDER has not solicited or induced any person, firm or corporation to refrain from bidding; and BIDDER has not sought by collusion to obtain for itself any advantage over any other Bidder or over OWNER.

4. BIDDER agrees to perform all the Work described in Contract Documents, subject to adjustments as provided therein, for the Prices BIDDER provides on the Schedule of Values.
5. BIDDER declares it understands that the unit quantities shown on the Bid Form Unit Price Schedule are approximate only and not guaranteed and are subject to either increase or decrease; and that should the quantities of any of the items of Work be increased, the BIDDER agrees to do the additional Work at the unit prices set out herein, and should the quantities be decreased, BIDDER also understands that final payment shall be made on actual quantities completed at the unit prices, and shall make no claims for anticipated profits for any decrease in the quantities.
6. The BIDDER further declares its understands the OWNER may elect to construct only a portion of the Work covered by these Documents and BIDDER agrees to perform that portion of the Work for which BIDDER is awarded a Contract at the unit prices quoted herein.
7. BIDDER agrees that the Work:

Wastewater Treatment Facility Renewal and Rehabilitation Project shall be Substantially Complete within 540 days of Notice to Proceed and Finally Complete within 600 days of Notice to Proceed. Work hours 7:00am to 5:00pm Monday – Friday, excluding holidays.

BIDDER accepts the provisions of the Agreement as to liquidated damages in the event of failure to complete the Work on time.

8. The following documents are attached to and made a condition of this Bid:

- (a) Required Bid security in the form of Bid Bond.
- (b) Schedule of Values.
- (c) List other documents as pertinent.

9. Communications concerning this Bid shall be telephoned or addressed to:

Name: Wharton-Smith, Inc.

Address: 125 Indiantown Road, Ste 201, Jupiter, FL 33458

Phone No.: 561.748.5956 Fax: 561.748.5958

10. BIDDER'S Florida Contractor's License No. CGC1511243

11. BIDDER covenants that it is qualified to do business in the State of Florida and has attached evidence of BIDDER'S qualification to do business in the State of Florida, or if not attached, BIDDER covenants to obtain such evidence within five days of request by OWNER to provide evidence.

If BIDDER is

An Individual

Name N/A (SEAL)

Signature: N/A

Doing business as N/A

Business Address: N/A

Phone Number: N/A

Fax Number N/A

A Partnership

Firm's Name N/A (SEAL)

General Partner Signature: N/A

Business Address: N/A

Phone Number: N/A

Fax Number N/A

A Corporation

Corporation's Name Wharton-Smith, Inc. (SEAL)

State of Incorporation Florida

Authorized Person: Ronald F. Davoli

Title: President/CEO

Signature: 
Ronald F. Davoli, President/CEO

Attest: Devon A. Lewis, Corporate Secretary (Secretary)

Signature: 
Devon A. Lewis, Corporate Secretary

Business Address: Corporate: 750 Monroe Road, Sanford, FL 32771

Local: 125 Indiantown Road, Jupiter, FL 33458

Phone Number: 407.321.8410

Fax Number 407.327.6984

Local: 561.748.5956

561.748.5958



Council

Anne Gerwig, Mayor
Michael Drahos, Vice Mayor
John T. McGovern, Councilman
Michael J. Napoleone, Councilman
Tanya Siskind, Councilwoman

Manager
Paul Schofield

ITB 003-19/DZ

Title: Wastewater Treatment Renewal and Rehabilitation Project

Opening Date: January 9, 2019 at 2:00pm

Addendum Date: November 30, 2018

ADDENDUM NO. ONE

PURPOSE: The purpose of this Addendum/NOTICE is to make changes, additions, deletions, revisions, and clarifications to the (ITB) Invitation to Bid documents for the Wastewater Treatment Renewal and Rehabilitation Project. Bidder shall review the Addendum/NOTICE work and requirements in detail and incorporate any effects the Addendum/NOTICE may have in their proposal price.

1. **Question:** What is the Engineer/Budget/Project Estimate for ITB-003-19/DZ - Wastewater Treatment Facility Renewal and Replacement Project? Is the bid bond of 10% is correct or a typographical error, because normally it is 5%? Please advise.

Response: The estimate is \$17,450,000 and the bid bond required is 10%.

2. **Question:** Is there any odor control on the below project?

Response: The description mentions that there is demolition and replacement of the headworks odor control system. See highlighted below

The scope of this Contract includes the installation of an influent flow meter, structural and mechanical rehabilitation of the headworks, demolition and replacement of the *headworks odor control system*, improvements to the filter backwash mudwell, installation of a new tertiary Filter No. 4, various improvements to the dewatered biosolids systems, construction of a new Control Building, Reuse Building, and Blower Building, modifications to the Existing Operator's Building, replacement of the existing sodium hypochlorite and sodium hydroxide chemical feed loop piping, painting and coating all new and existing infrastructure, miscellaneous concrete crack repair, site civil improvements including paving, grading, and drainage, various walkway, stairway, and handrail rehabilitation and improvements, corresponding demolition work, supporting electrical and instrumentation systems. Additionally, Alternate Bid Item No. 1 for Clarifier No. 3 Demo and Rehabilitation.

3. **Bid Documents, Schedule of Values** – Page 24- Remove and replace the Schedule of Values in its entirety with the attached form
- Changed Item #10 : Owner controlled Contingency to be 10% of Item No. 3
 - Changed Item #3 and #A1 : To place "X" in "Unit Price" box as these are Lump Sum values.
4. **Bid Documents, List of Drawings** – Page 54, Sheet No. I-54. Replace the word "WATER" with "WASTEWATER".
5. **General Plan Sheets G-02 and G-03**– Remove and replace with the attached
6. **Electrical Plan Sheets E-00, E-33, E-34A, E-34B, E-47, E-61**– Remove and replace with the attached

7. **Electrical Plan Sheet E-29, Notes, 3 (lower righthand corner)** – Replace “See Dwg E-48” to “See Dwg E-44”

8. **Instrumentation Plan Sheet I-54**– Remove and replace with the attached

9. **Specification Section 11315**– Add the attached specification section 11315 Grit Classifier to the Technical Specifications.

10. **Specification Section Table of Contents, Page v**– Add the following after Section 11310:

“Section 11315, Grit Classifier

11315-1 thru 11315-6”

11. **Specification Section 11219, 1.04** – Delete last sentence and replace with the following:

“The package shall be manufactured by Aerzen, Atlas Copco or Kaeser.”

12. **Specification Section 11219, 2.01 B** – Delete fourth sentence and replace with the following:

“Equipment provided shall be a rotary lobe compressor package by one of the following: Aerzen Delta Hybrid Model D985, Atlas Copco Model ZS90, or Kaeser Model FB660S-L.”

13. **Specification Section 11226, 2.02 A** – Delete Section title and replace with the following:

“Center Drive Assembly”.


14. **Specification Section 11301, 2.02** – Delete paragraph and replace with the following:

“2.02 LEVEL MONITORING SYSTEM AND GROUNDING SYSTEMS: The existing tanks have a level monitoring and grounding system. The new tanks shall be equipped with nozzles to accommodate removal and installation of the existing level monitoring system to achieve a fully functional level system. The existing cabling and air terminal/grounding system shall be removed and re-installed. The existing cabling and air terminals may be re-used if not damaged during removal. New fasteners shall be provided. The fasteners shall be Erico Series 809/810 adhesive cable holders. The adhesive must bond bronze or aluminum holders to an HDPE tank. The proposed adhesive must be approved by the Engineer prior to use. All components not specified above are to be replaced with new components to match the existing and yield a fully functional system.”

15. **Specification Section 11364, 1.04** – Delete second sentence and replace with the following:

“The positive displacement progressive cavity pump shall be manufactured by Seepex”.

ACKNOWLEDGEMENT: Bidder must acknowledge receipt of any and all Addenda in the space provided on the Bidder Submittal Form. Failure to do so may result in rejection of the Proposal. All requirements of the proposal documents remain unchanged except as cited herein.



Signature of Bidder Acknowledging Receipt of
Addendum No. (1) One to be attached in front of Bid

Ronald F. Davoli, President/CEO
Wharton-Smith, Inc.

Council

Anne Gerwig, Mayor
Michael Drahos, Vice Mayor
John T. McGovern, Councilman
Michael J. Napoleone, Councilman
Tanya Siskind, Councilwoman

Manager
Paul Schofield

ITB 003-19/DZ

Title: Wastewater Treatment Renewal and Rehabilitation Project

Opening Date: January 9, 2019 at 2:00pm

Addendum Date: December 17, 2018


ADDENDUM NO. TWO

PURPOSE: The purpose of this Addendum/NOTICE is to make changes, additions, deletions, revisions, and clarifications to the (ITB) Invitation to Bid documents for the Wastewater Treatment Renewal and Rehabilitation Project. Bidder shall review the Addendum/NOTICE work and requirements in detail and incorporate any effects the Addendum/NOTICE may have in their proposal price.

- 1. Question: We request additional job site visits in order to evaluate and do a take-off on existing items not on the drawings. Given the size of the painting scope we feel the need for 1 or more additional job site visits.**

Response: An additional site visit will be held for painters only on Wednesday, December 19, 2018 at 8am at the Waste Water Treatment site located at 11860 Pierson Road. No questions will be answered during the site visit.

ACKNOWLEDGEMENT: Bidder must acknowledge receipt of any and all Addenda in the space provided on the Bidder Submittal Form. Failure to do so may result in rejection of the Proposal. All requirements of the proposal documents remain unchanged except as cited herein.



Signature of Bidder Acknowledging Receipt of
Addendum No. (2) Two to be attached in front of Bid
Ronald F. Davoli, President/CEO
Wharton-Smith, Inc.

Council

Anne Gerwig, Mayor
Michael Drahos, Vice Mayor
John T. McGovern, Councilman
Michael J. Napoleone, Councilman
Tanya Siskind, Councilwoman

Manager
Paul Schofield

ITB 003-19/DZ

Title: Wastewater Treatment Renewal and Rehabilitation Project

Opening Date: February 6, 2019 at 2:00 PM Local Time


Addendum Date: November 30, 2018

ADDENDUM NO. THREE

PURPOSE: The purpose of this Addendum/NOTICE is to make changes, additions, deletions, revisions, and clarifications to the (ITB) Invitation to Bid documents for the Wastewater Treatment Renewal and Rehabilitation Project. Bidder shall review the Addendum/NOTICE work and requirements in detail and incorporate any effects the Addendum/NOTICE may have in their proposal price.

The Bid Opening date is hereby changed from January 9, 2019 to February 6, 2019 at 2:00 PM Local Time.

ACKNOWLEDGEMENT: Bidder must acknowledge receipt of any and all Addenda in the space provided on the Bidder Submittal Form. Failure to do so may result in rejection of the Proposal. All requirements of the proposal documents remain unchanged except as cited herein.



Signature of Bidder Acknowledging Receipt of
Addendum No. (3) Three to be attached in front of Bid

Ronald F. Davoli, President/CEO
Wharton-Smith, Inc.

Council

Anne Gerwig, Mayor
Michael Drahos, Vice Mayor
John T. McGovern, Councilman
Michael J. Napoleone, Councilman
Tanya Siskind, Councilwoman

Manager
Paul Schofield

ITB 003-19/DZ

Title: Wastewater Treatment Renewal and Rehabilitation Project

Opening Date: February 6, 2019 at 2:00pm

Addendum Date: January 4, 2019

ADDENDUM NO. FOUR

PURPOSE: The purpose of this Addendum/NOTICE is to make changes, additions, deletions, revisions, and clarifications to the (ITB) Invitation to Bid documents for the Wastewater Treatment Renewal and Rehabilitation Project. Bidder shall review the Addendum/NOTICE work and requirements in detail and incorporate any effects the Addendum/NOTICE may have in their proposal price.

1. Question Specification Section 01019, 1.06 WATER:

"The Contractor shall provide and maintain, at his own expense, an adequate supply of water for his use for construction and domestic consumption...Water for all testing shall be at the Contractor's expense" What rate will be charged to the Contractor for water?

Response: Contractor will be required to obtain a Village provided water meter with refundable deposit in order to track onsite water consumption for construction and testing activities, however water consumption will not be billed unless usage is determined to be excessive or abusive by the Owner.

Specification Section 01019, 1.06 WATER, insert the following into the first sentence; "...an adequate supply of water, *or connection to the Village potable water system* for his use for construction and domestic consumption..."

Specification Section 01019, 1.06 WATER, delete entire last sentence and replace with the following; ***"Water consumed by the Contractor for all on-site activities shall be metered but not billed to Contractor unless usage is determined to be excessive or abusive at the Owner's sole discretion."***

2. Question Specification Section 01019, 1.07 ELECTRICITY:

"All power consumed for start-up, testing and system use prior to substantial completion shall be paid by the Contractor" How will the consumption be measured and at what rate will the contractor be charged?

Response: Contractor will not be billed for electricity consumption related to construction activities unless usage is determined to be excessive or abusive by the Owner. Contractor will however be required to coordinate, obtain and pay for any new service connections and equipment with the electrical utility provider.

Specification Section 01019, 1.07 ELECTRICITY, delete first sentence in its entirety.

Specification Section 01019, 1.07 ELECTRICITY, delete entire last sentence and replace with the following; ***"Electricity consumed by the Contractor for all on-site activities shall be metered but not billed to Contractor unless usage is determined to be excessive or abusive at the Owner's sole discretion."***

3. Question Specification Section 01019, 1.10 WORKING HOURS:

"The Contractor shall be obligated to pay costs associated with site presence of the Engineer's representative resulting from work beyond normal working hours" What will be the hourly rate charge for the Engineer's representative?

Response: Every effort shall be made to conduct activities requiring the presence of the Owner's Engineering Representative during normal working hours. In the event that certain site activities necessitate the Engineer's presence outside of normal hours, the Contractor shall not be required to pay the Engineer's fees. Please note that normal working hours shall be as detailed in Article 6.02 of Exhibit "A", Standard General Conditions for the contract as found in the bid documents.

Specification Section 01019, 1.10 WORKING HOURS: in the first sentence delete "4 P.M." and replace with "5 P.M."

Specification Section 01019, 1.10 WORKING HOURS: in the second sentence remove and replace "5 P.M." with "6 P.M."

Specification Section 01019, 1.10 WORKING HOURS: delete the last sentence in its entirety.

4. Question Specification Section 01019, 1.28.A SHUTDOWNS AND WORK SEQUENCING:

"Contractor is specifically advised that the Engineer reserves the right to require the scheduling of shutdowns at certain periods of the day and/or year when flows to the facility are generally lowest...In general, the Contractor shall be required to take all steps necessary to minimize the duration of a partial shutdown. This shall include, but not limited to, work after hours and/or on weekends." In the event that the Engineer dictates work activities be performed beyond normal working hours, will the Contractor be responsible to pay costs associated with Engineer's representative being present as stated in paragraph 1.10?

Response: Every effort shall be made to conduct activities requiring the presence of the Owner's Engineering Representative during normal working hours. In the event that certain site activities necessitate the Engineer's presence outside of normal hours, the Contractor shall not be required to pay the Engineer's fees. Please note that normal working hours shall be as detailed in Article 6.02 of Exhibit "A", Standard General Conditions for the contract as found in the bid documents.

5. Question Specification Section 01019, 1.28.A.9 Sludge Cake Belt Conveyor:

"All work on the Sludge Cake Belt Conveyor shall proceed continuously, 24-hours a day, starting after 5 P.M. on a Thursday for a duration not to exceed 3 days (Sunday, 5 P.M)." Will the Contractor be responsible to pay costs associated with Engineer's representative being present as stated in paragraph 1.10?

Response: Every effort shall be made to schedule the Engineering Representative's presence for the sludge cake belt conveyor work within normal working hours. To the extent that this is not practical or there is an overriding need for the Engineer to be present outside of normal working hours, the Contractor shall not be required to pay the Engineer's fees. Please note that normal working hours shall be as detailed in Article 6.02 of Exhibit "A", Standard General Conditions for the contract as found in the bid documents.

6. Question Specification Section 16040, 1.05:

Specification 16040, 1.05 lists equal manufacturers are allowed for the front access switchgear. Schneider Electric has an equal product and is listed as an approved manufacturer for other key items such as the Motor Control Center. Please confirm Schneider Electric is thus an approved equal for the switchgear.

Response: Schneider Electric may be approved as an equal only if they meet all requirements of the plans and specifications. Additionally, Contractor shall be required to submit an "approved equal" request upon contract award which will be evaluated consistent with established procedures contained within the bid documents.

7. Question Specification Section 16000 3.12:

Specification 16000-3.12 Duct Banks. Please provide duct bank detail and schedule as none are shown in the contract documents.

Response: Conduit tag numbers for duct banks are shown on the drawings. The required conduit spacing (between conduits and to earth) is given in specification section 16000, 3.12. The minimum duct bank conduit size is also given in section 16000, 3.12. The actual configuration of the duct bank, within the stated minimums, is left to the Contractor to allow for reaction to field placement conditions.

8. Question Specification Section 16000 2.12:

SPECIFICATION #: 16000-2.12 Manholes. Please provide manhole sizes required as detail on E-44 only shows a minimum manhole size.

Response: The minimum manhole dimensions and other details are given on Sheet E-44. The required manhole size, if greater than the minimum, shall be established by the window size (which is based on the duct bank configuration selected by Contractor according to the criteria described in Item #7 above).

9. Question Specification Section 16000 2.06A and 3.02B:

Specification Section 16000 2.06A (Conduit and fittings) doesn't mention the use of EMT for interior office space. Please confirm the use of EMT for branch power and lighting circuits is acceptable.

Response: Specification Section 16000 2.06A and 3.02B, add the following sentence just ahead of the last sentence in paragraph 2.06A and after the last sentence in paragraph 3.02B.

"The only exception to the requirements set forth in this paragraph is that EMT with compression fittings may be used when concealed inside furred or stud walls or above concealed ceilings, including acoustic tile."

10. Question Specification Section 16000 2.06 & 3.02:

Specification 16000 2.06 & 3.02 require all above grade conduit to be Rigid Aluminum. Can EMT with steel connectors be used in the new Control building and the existing Control building for the branch circuits?

Response: See response to Question No. 9.

11. Question Specification Section 16000 2.07A:

Spec Section 16000 2.07A (Boxes and Fittings) doesn't mention the use of 4 square metal boxes with mud rings for interior office space. Please confirm the use of 4 square metal boxes for branch power and lighting circuits is acceptable.

Response: Specification Section 16000 2.07A, add the following paragraph immediately after the last sentence

"Four-inch square metal boxes with adapter rings to mount the wiring devices in the interior walls of interior office spaces may be used. The depth of the 4-inch square boxes shall be minimum 1 ½-inch and they shall be sized to meet the NEC requirements for volume inside the box for all wires in and out of the boxes and terminated inside the box."

12. Question Specification Section 16000 2.07:

Specification 16000 2.07 requires all interior outlet boxes to be weatherproof cast aluminum. Can 4" square Steel boxes with plaster rings be used in the new and existing control buildings when installed in stud walls?

Response: See response to Question No. 11.

13. Question: From drawings E-04 and E-33, please provide conduit in wire for PLC3000/PCP9020/UPS.

Response: **Electrical Plan Sheets E-33-** See replacement Electrical Sheet E-33 provided with this Addendum.

14. Question: E-13 Note 2 – need detail of pipe bridge.

Response: **Electrical Plan Sheets E-44-** See replacement Electrical Sheet E-44 provided with this Addendum.

15. Question: E-13 Note 3 – need detail of pipe rack.

Response: **Electrical Plan Sheets E-44-** See replacement Electrical Sheet E-44 provided with this Addendum.

16. Question: E-13 Need detail of manholes.

Response: Please see response to Question No. 8 above.

17. Question Specification Section 02640, 2.06: Can you get clarification on "geared handwheel operator" from page 4 in the specifications?

Response: **Specification Section 02640, 2.06,** delete the last sentence and replace with the following:

"Above grade valves shall be equipped with a handwheel operator."

18. Question: I would like to ask question about Addendum one for Wellington. On page 4 are some pages marked as revised per Addendum but I could not find these in this document. Can you please let me know if they are somewhere to be found or another addendum will provide those pages to us?

Thank you very much and have a great day.

Response:

Only drawing G-02 was changed. Drawing C-05, C-06, and C-07 were not changed. The revision noted sheet G-02 updated the drawing name on the index.

19. Question: Do you require the bid acknowledgement cover page to be submitted with the bid or prior to the bid date?

Response: Please submit the cover page with the bid.

20. Specification Section 01150 1.08 Specific Bid Allowances: Add the following to the list of Allowance items after "Switchgear Maintenance"

"New FPL Underground/Backup Feeder."

21. Specification Section 02050 1.01A: Add the following to the list of items to be demolished:

"Concrete equipment pad for the existing headworks odor control system."

22. Specification Section 01019 1.19 – Delete the fourth sentence and replace with the following:

"The Owner Field Trailer shall contain two separate offices equipped and sized as set forth below, as well as, kitchen facilities to include a kitchen sink, water/sewer service, minimum 8-ft of counter space, with drawers, an under-counter refrigerator, 4-ft of cupboard space and receptacles for appliance plug in."

23. Specification Section 01019 1.28A.13 New Control Building. – Delete and replace with the following:

"New Control Building: The project includes a new Control Building to house a new Control Room, Laboratory, Storage Room, Locker Rooms and Mechanical Room. The existing Laboratory, Vestibule/Control Room, Office, Restroom and IT Room located in the existing Operator's Building shall not be removed from service or have any improvements commenced until the new corresponding facilities located in the new Control Building are complete, fully functional and ready to be occupied. The new Control Building shall be complete and fully functional including, but not limited to, issuance of a Certificate of Occupancy within 395 days of the Notice to Proceed date."

24. Specification Section 16920 1.02A – Delete the last sentence and replace with the following:

"The Contractor shall contract with and utilize the services of Process Control Consultants, Inc. for screen development and OIT programming. The Contractor shall coordinate the activities of the system integrator for all PLC programming and system integration work with the work of Process Control Consultants, Inc."

25. Specification Section 02050 1.01A – Delete "Existing Lime Feed Equipment" from the list of items to be demolished and replace with the following:

"Existing Lime Feed Equipment including, but not limited to, the lime feeder, the lime silo (including contents), brackets, supports and peripheral items. Contractor shall assume the silo is full of hydrated lime."

26. Plan Sheets C-08, HW-01, HW-12 – Delete and replace with the attached.

27. Electrical Plan Sheets E-9, E-10, E-33, E-34A, E-44– Remove and replace with the attached.

28. Bid Documents page 56, Article 4, item 4.1 Time of Commencement and Completion:


Replace "540 calendar days" with ***"600 calendar days"***.

29. Bid Documents, Schedule of Values – Page 24- Remove and replace the Schedule of Values in its entirety with the attached form

- Added new Allowance item #10 : "Allowance for New FPL Underground/Backup Feeder"
- Renumbered "Owner Controlled Contingency" from #10 to #11.

30. Owner Clarification – The Owner has undertaken additional investigatory work to the on-site lime silo scheduled to be demolished. Physical probing of silo contents 10 feet from top and approximately 5 ft from bottom access port have indicated that lime material remains in powder form. Contractor will be expected to remove and safely dispose of any silo contents as part of the demolition activity associated with this equipment item.

ACKNOWLEDGEMENT: Bidder must acknowledge receipt of any and all Addenda in the space provided on the Bidder Submittal Form. Failure to do so may result in rejection of the Proposal. All requirements of the proposal documents remain unchanged except as cited herein.



Signature of Bidder Acknowledging Receipt of
Addendum No. (4) Four to be attached in front of Bid

Ronald F. Davoli, President/CEO
Wharton-Smith, Inc.

Council

Anne Gerwig, Mayor
Michael Drahos, Vice Mayor
John T. McGovern, Councilman
Michael J. Napoleone, Councilman
Tanya Siskind, Councilwoman

Manager
Paul Schofield

ITB 003-19/DZ

Title: Wastewater Treatment Renewal and Rehabilitation Project

Opening Date: February 6, 2019 at 2:00pm

Addendum Date: January 23, 2019

ADDENDUM NO. FIVE

PURPOSE: The purpose of this Addendum/NOTICE is to make changes, additions, deletions, revisions, and clarifications to the (ITB) Invitation to Bid documents for the Wastewater Treatment Renewal and Rehabilitation Project. Bidder shall review the Addendum/NOTICE work and requirements in detail and incorporate any effects the Addendum/NOTICE may have in their proposal price.

1. Question:

The plans call for acoustic CMU on the Blower and Reuse Buildings. We would like to know if you had any information regarding this: a. Manufacturer b. Size of acoustic CMU c. Are there sills d. Header information. Please get back to us at your earliest convenience. Until we receive answers regarding the information requested, the Blower Building and Reuse Building are not included in any proposal sent in.

Response: The acoustical CMUs are specified in specification section 04200, 2.01 B. Lintels are conventional precast concrete.

2. Question:

Tie beam TB2 on sheet DB-06 is call out as 8" x 20" on schedule sheet DB-05 is call out as 8" x 20". Which is correct?

Response: There is no lintel. TB2 runs from the door frame to the top of the adjacent building tie beam. The actual dimension will depend on the door installation details and frame dimension, which will depend on the door manufacturer.

3. Question:

Provide size of existing foundation support for metal pole barn. size and high of columns and roof.

Response: See item No. 43

4. Question:

Provide more information on existing reuse building and concrete slab with curb removal.

Response: See item No. 44

5. Question:

Need elevation of existing buildings that required demo and replacement of any kind to be able to determine quantities.

Response: The following buildings are to be demolished as shown on the plans:

- Equipment Pole Barn: Demolition shown on Digester Plan Sheet DB-01. See item No. 43
- Reuse Building: Demolition shown on Reuse Building Plan Sheet RB-01. See item No. 44
- Storage/Sodium Hypochlorite Pump Building: Demolition shown on Operator's Building Plan Sheet OB-01. See item No. 45

6. Question:

Are the Aluminum Shutters part of the coatings portion for the Control Building structure No. 3 per the drawing MU-01? If so, what system would apply in the 09800 Section of the specifications?

Response: No. The Aluminum Shutters are not part of the coatings portion for the Existing Control Building (structure No. 3).

7. Question:

Per the drawings structure No. 31 is labeled Sodium Hydroxide Bulk Storage Containment. During the Site Visit it was noticed that there are diesel storage fuel tanks in this location. Are these diesel tanks and its containment structure to be coated? If so, what system is to apply in the 09800 section of the specifications?

Response: Per the revised Plan Sheet MU-01, structure No. 31 is labeled Sodium Hypochlorite Bulk Storage Containment. The Diesel storage fuel tanks labeled structure No. 49 are to be coated. See item No. 40, No. 52, and No. 53.

8. Question:

Is the Canopy of the structure No. 11 the Drum Storage area to be coated as a part of this project?

Response: No. The Canopy of structure No. 11 is not to be coated.

9. Question:

Are the interior surfaces of structure No. 23, the injection well, to be coated as a part of this project?

Response: Yes. See item No. 40, No. 52, and No. 53.

10. Question:

Please confirm the scope of work for the structure No. 23 the truck loading building and truck canopy? Is all the primary and secondary framing to be restored along with the concrete slab? Please confirm?

Response: The scope of work includes removing insulation (truck loading building), pressure washing, sand blasting (locations shown on plan sheets), coating and surface preparation of existing and new structural members per Specification Section 09800 as shown on plan sheets, and replacement of existing structural members. Portions of the primary and secondary framing are to be restored.

The truck loading building concrete slab is not to be restored. The asphalt paving under the truck canopy structure is to be milled and resurfaced per Plan Sheet C-06.

For estimating member replacement quantities, see item No. 46.

11. Question:

Structure No. 17, the sludge dewatering facility is marked out on the drawings as if it's not a part of the overall scope of work for this project. Please confirm whether it is or it is not to be completed? If it is decided that it is included, can you please confirm the scope of work that is to be completed on this structure?

Response: The exterior of the existing Structure No. 17, the sludge dewatering facility, is to be coated in accordance with Specification Section 09800. See item No. 40 and No. 52.

12. Question:

Is the interior surfaces of the walls and the interior submerged/non-submerged piping to be coated on Structure No. 4 Process Basin or will this be excluded from the project?

Response: See item No. 41.

13. Question:

During the site visit there were many areas and structures shown and looked at that are not identified in any of the site maps on the current drawing set. Also the current drawing set references as built drawings that is not in the current bid documents package. Is it possible that we can get a set of the as built drawings of every structure that is to be coated that is existing and not included in the current drawing set?

Response: The facility was initially constructed 40 years ago with multiple modifications and expansions since then. Record drawings of every structure to be coated are not available however the available and applicable record drawings are included as attachments to this addendum.

A total of 91 record drawings marked 2007 Arcadis G&M, Inc and October 1996 Hazen & Sawyer have been included as reference documents.

14. Question:

Is the PVC piping throughout this treatment plant to be coated? If so, is it color coded or labeled in any way? Please confirm.

Response: New and existing PVC piping shall be coated in accordance with Specification Section 09800, 2.04 D. and 09800, 2.04 E. Piping shall be color coded in accordance with Section 09800, 2.02. Piping shall be labeled in accordance with Specification Section 10400.

15. Question:

Are the light posts to be coated as a part of this project as well as any existing bollards throughout the plant? If so can you please confirm the quantity of the items mentioned.

Response: Light posts are not to be coated as part of this project. The twenty (20) existing bollards are to be coated throughout the plant.

16. Question:

Can you please confirm the warranty for this project? The standard warranty is a 1 year from substantial completion.

Response: The warranty period is 1 year from substantial completion.

17. Question:

Section 09800 2.05 Crack Repair and Resurfacing states that Tnemec Series 130 or Thoroseal is an acceptable product for this type of repair. The Thoroseal can resurface up to a 1/8" thick. However the Tnemec Series 130 cannot resurface but maybe up to a 1/32" thick. Anything generally needing to be resurfaced or repaired by building out gets Tnemec Series 218 Mortarclad up to a 1/2" thick in 1/4" lifts and Tnemec Series 217 on anything from 1/4" thick to 4" thick. Please confirm the intent of using Series 130 and Thoroseal and if Series 218/217 is suitable?

Response: **Specification Section 09800, 2.05** – Delete third sentence and replace with the following:

"Materials used for resurfacing shall be Tnemec Series 130-6603, Thoroseal, Tnemec Series 218 Mortarclad, or Tnemec Series 217 as appropriate for the nature and magnitude of the area and characteristics of the damaged area and as approved by the Engineer."

18. Question:

Section 09800 2.04 Q Containment Areas (Interior) and Cast-In-Place Tops line No. 2 is using Tnemec Series 63-1500 filler. This is no longer a product supplied by Tnemec. If any filler or resurfacer is required depending upon the depth of repair we suggest that Tnemec Series 218 or 215 and even 215 be utilized in this application.

Response: Specification Section 09800, 2.04 Q.2 – Delete paragraph and replace with the following:

“2. Intermediate Coat: Tnemec Series 218 Mortarclad, Tnemec Series 217, or Tnemec Series 215 filler and surfacer as appropriate. Trowel apply and squeegee as required to fill big holes.”

19. Question:

Please confirm whether or not all buildings that are to receive stucco is to receive coatings per the 09800 section. It is not clear whether or not the stucco color is integral or not.

Response: Stucco shall be painted in accordance with Specification Section 09800, 2.04.

20. Question:

There are multiple containment structures that are being restored. Can you please confirm the system that is to be applied in these exterior containment areas? There is a system for the Aerobic Digesters that is a Chemical resistant Vinester (System K). There is a system for interior floors of the building (System M). There is a system for interior Containments (System Q). But there is not any for the exterior containments. Is System Q mentioned for the interior suitable for the exterior containments as well?

Response: No. The exterior surfaces of the containments shall be coated in accordance with Specification Section 09800.

Section 09800, 2.04 H:

- New Headworks Odor Control containment area (Plan Sheet MU-01, Structure No. 49)

Section 09800, 2.04 I:

- Exterior of Injection Well Containment Area (Plan Sheet MU-01, Structure No. 23). See item No. 40 and No. 52.
- Exterior of Sodium Hypochlorite Bulk Storage Containment (Plan Sheet MU-01, Structure No. 31). See item No. 40 and No. 52.
- Exterior of Existing Fuel Storage Tank Containment Area (Plan Sheet MU-01, Structure No. 49). See item No. 40 and No. 52.
- Exterior of Existing Odor Control Scrubber System Containment – Sludge Drying Building (Plan Sheet MU-01, Structure No. 63). See item No. 40 and No. 52.
- Exterior of Bulk Sodium Hydroxide Storage Facility (Plan Sheet MU-01, Structure No. 48). See item No. 40 and No. 52.

21. Question:

I've been asked to find out if all Mechanical Joint and Flange Fittings for the Wellington WWTF Rehab project bidding 1/9/19 need to be domestically sourced. We currently have them as import and will need to get them re-priced if they need to be domestic.

Also, has there been any discussion of a bid date push, as this project bids soon after the holidays? Please advise.

Response: The bid due date was extended under Addendum No. 3. All mechanical joint and flange fittings shall be domestically sourced. All product and equipment procurement for the project shall conform to the Village of Wellington Approved Product List which is part of the "Water and Wastewater Systems: Construction Specifications and Standard Details Manual", available on the Village website under the following link;

<https://www.wellingtonfl.gov/government/departments/utilities/utilities-permitting-process-information/water-and-wastewater-standards-information-4184>

22. Question:

Section 01019, 1.28(A)(13) Positive Displacement Blowers: "...The Contractor shall then relocate and start-up one blower at a time." (reference to the three existing blowers). However, Section 01650 Starting of Systems: 1.01(1) refers only to the New Blower. What are the start-up requirement(s) for the existing blowers? Who is the manufacturer of the three existing blowers?

Response: See item No. 47.

23. Question:

Are the diffusers in the Digesters (Typical of 4) being provided by the Manufacturer? Where would you like us to end our pipe? (Plan Sheet number DB-22)

Response: The diffusers shall be provided in accordance with Specification Section 11901, Coarse Bubble Aeration System. The air manifold piping shall have flanged end connections complete with "O" ring gasket in accordance with Specification Section 11901, 2.04 and as indicated on the Contract Drawings.

24. Question:

If we are providing the diffusers, the Material List shows it as 4" but is scaled to the rest of the 6" piping with no reducers drawn. Is this supposed to be 6"? (Plan Sheet number DB-22).

Response: The piping shall be 4" 316 SS. See item No. 48.

25. Question:

What is the operating pressure of the Air Piping?

Response: The operating pressure of the Aerobic Digester air piping varies. In accordance with Specification Section 11901, 1.01 B, the Aerobic Digester design maximum side water depth is 15.0-ft and is subject to wide fluctuations. Per Specification Section 11901, 2.01 F, the rotary lobe compressor discharge shall be rated for 8.5 psig continuous service.

26. Question:

On the sludge piping, would you like us to include the 316 S.S Wet Product Influent Flume? (Plan Sheet number BS-08).

Response: The 316 S.S. wet product influent flume is included in the project work.

27. Question:

There is a blast gate located before the Tee where the Air Supply tie's into the existing line that we will not include. Will this have flanges to install to? In the spec there is to be no field welding and in the material list this is listed as a 20" 316 SS Blast Gate, PE/PE. (Plan Sheet number DB-21).

Response: The blast gate located before the Tee where the Air Supply ties into the existing line is included in the scope of work. Per Specification Section 11901, 2.03 C, "Field welding will not be permitted, unless otherwise specifically indicated." The PE/PE connection indicated shall be field welded.

28. Question:

E-34A Conduit schedule – Need conduit size and wire or cable for all conduits PC/FCV24001 thru I24407. Also need to know the type of conduit required for each conduit.

Response: See item No. 49.

29. Question:

E-34B Conduit schedule – Need conduit size, type and wire or cable for all conduits S/MDP1 thru MDP/CP1/UPS

Response: See item No. 49.

30. Question:

Need a plan showing routing of the following conduits:

CP1HUB/PLC900/FOETH, MCP900/SDW, SBPLC/MCP2HUB/FOETH, MCP2HUB/PLC3000/FOETH
MCP2HUB/PLC5000/FOETH, CP9005-2/MCP2/ETH AND CP2000/MCP2/ETH

Response: The routing of the named conduits can be determined from the following Plan Sheets:

E-13, E-14, E-15, E-45, E-54, E-57, E-58, and I-54.

31. Question:

Need panel schedule for UPSPLCCP1

Response: The panel schedule for UPSPLCCP1 is shown on I-53.

32. Question:

Need panel schedule for UPSCB-PP.

Response: The panel schedule for UPSCB-PP is shown on I-53.

33. Question:

Need location of CATV j-box at the west property line per note 9 E-27.

Response: The Contractor shall assume the CATV j-box is located at the Northeast corner of the property line near the entrance gate.

34. Question:

Please provide conduit size, wire and conduit routing for C416 and P416 as schedule on sheet E-34A is empty for these items.

Response: C416: 12-No. 14, 1-No. 14 GND, THHN/THWN, 3/4" aluminum conduit
P416: 3-No. 12, 2-No. 14, 1-No. 12 GND, THHN/THWN, 3/4" aluminum conduit

35. Question:

Regarding sheet E-16, Note 1. Please provide which fixture type should be used to replace the existing truck load area lighting.

Response: Fixture type 'M' as shown on Sheet E-24.

36. Question:

Will the Village consider a Bidder to be qualified if Bidder submit information that it's direct employees, agents and subcontractors meet the qualifications as outlined in Article 3? We request that the current workload, WIP, or Work In Place be listed in the qualification documents as a consideration as to whether the low bidder is able to perform the work.

Response: Bidder qualifications will remain unchanged and can be found in the Instructions to Bidders, page 5 of the Bid Documents under Article 3, Qualifications of Bidders

37. Question:

Drawing RB-03 shown Slab level at 19.0 feet. Typical wall section on page RB-04 call out for elevation 18.5 feet. Please confirm elevation of slab at reuse building.

Response: Reuse Building Plan Sheet RB-04, Typical Wall Section – Change finished floor slab elevation from 18.5 ft. to 19.0 ft.

38. Question:

Addendum one is showing revised sheet of C-05, C-06, C-07, OB—25, DB-01, DB-07 but those are not included in this addendum.

Response: Addendum No. 1 reflects changes made to the presentation of the listed sheets on the Index of Sheets (G-02 and G-03) only. The individual sheets themselves were not modified under the referenced item.

39. Question:

My company provides an alternative air scrubbing system than what was specified in the proposal. What process should I follow to get my unit approved and vetted before the Feb. due date.

Response: Bidders need to bid on the requirements as set forth in the Contract Documents. Equal products may be considered after receipt of bids and award of project to responsive and responsible low bidder

40. Question:

We respectfully submit for your consideration a request to approve products as an accepted substitute on Wastewater Treatment Facility Renewal & Rehabilitation (18-867432).

Response: Bidders need to bid on the requirements as set forth in the Contract Documents. Equal products may be considered after receipt of bids and award of project to responsive and responsible low bidder

41. Addendum No. 1, Item #4 – Delete the words "Page 54".

42. Miscellaneous Plan Sheet MU-01 – Remove and replace with the attached.

43. Miscellaneous Plan Sheet MU-05 – Add General Note No. 1 as follows:

"The interior surfaces of the walls and the interior non-submerged piping on Structure No. 4 (Process Basin) are to be coated in accordance with Specification Section 09800"

44. Headworks Plan Sheet HW-10 – Remove and replace General Note No. 3 with the following:

"Concrete point repairs and T-Lock liner shall be included in the base bid. The general areas for the repairs are shown on the plans. The Engineer shall identify the required repair/replacement areas in the field after the flow is bypassed and the structures can be investigated/inspected. The Contractor shall assume there will be 200 sq. ft. of concrete point repairs and 200 sq. ft. of T-Lock liner repair/replacement. Concrete point repair shall be performed using the Tnemec 217 System or Tnemec 218 System as required."

45. Plan DB-01 – Add General Note No. 1 as follows:

“The pole barn is supported by fourteen steel columns that each sit on concrete pads (flush at grade). Ten of the pads are 4' x 4', and four are 5' x 5'. Thickness is unknown but estimated to be 24-inches. The pole barn is approximately 12'- 6" high from grade to roof.”

46. Reuse Building Plan Sheet RB-01 – Add General Note No. 6 as follows:

“The building height is approximately 9'-0" from the slab. The building is a conventional metal building erected to the building standards applicable in approximately 1990. The slab depth measures 18-inches thick at the edge.”

47. Operator's Building Plan Sheet OB-01 – Add General Note No. 3 as follows:

“The Storage/Sodium Hypochlorite Pump Building height is approximately 12'-0" from the slab. The building is a conventional CMU erected to the building standards applicable in approximately 1980. The concrete slab thickness is unknown but estimated to be 18-inches.”

48. Biosolids Plan Sheet BS-09 – Remove and replace General Note No. 3 with the following:

“The existing condition shown on the photos are taken from the site. However, all existing conditions are not shown on the photos. All deteriorated members shall be replaced and rusted members shall be cleaned and repainted. The estimated amount of replacement members follows: 75'-0" of 3" x 3" x 16 Gauge Base Angle, 75'-0" of 8" x 3.5" x 12 Gauge Eave Strut, 30'-0" of 8" x 3.5" x 12 Gauge C-Girt, and 250'-0" of 8" x 3.5" x 12 Gauge Z-Girt.”

49. Digester Plan Sheet DB-11 – Remove and replace General Note No. 5 with the following:

“The Contractor shall be responsible for the relocation of the existing blowers as required to facilitate installation of the blowers at the new location shown. The Contractor shall provide for the presence of competent personnel representing the manufacturer of the existing blowers to check the re-installation, adjust the setting as required, and place the re-installed blowers in service one at a time. The Engineer shall be given 7 days advance notice of the desired start-up date and time. The existing blowers are manufactured by Roots.”

50. Digester Plan Sheet DB-22 – Remove and replace with the attached.

51. Electrical Plan Sheets E-34A and E-34B – Remove and replace with the attached.

52. Specification Section 01150, 1.08 Specific Bid Allowances, Remove the following sentence in its entirety from the list of specified allowances.

“headworks concrete point repairs, T-Lock liner repair, and new T-Lock liner”

53. Specification Section 09800, 3.08 L. – Delete entire paragraph and replace with the following:

“L. Interior Block Walls of New and Existing Buildings:

- 1. Interior block walls of the New Operator's Building***
- 2. Interior block walls of the New Blower Building***
- 3. Interior block walls of the New Reuse Building***
- 4. Interior block walls of the Existing Control Building***
- 5. Interior block walls of the Existing Headworks Screening and Grit Collection Room.”***

54. Specification Section 09800, 3.08 I. – Delete entire paragraph and replace with the following:

"I. New and Existing Above Grade Exterior Stucco, Concrete Block and Cast-In-Place Surfaces (Not otherwise specified):

- 1. Exterior of Existing Headworks (Plan Sheet MU-01, Structure No. 2)***
- 2. Exterior of New Operator's Building (Plan Sheet MU-01, Structure No. 3)***
- 3. Exterior of Existing Control Building (Plan Sheet MU-01, Structure No. 3)***
- 4. Exterior of Existing Process Basin No. 1 and No. 2 (Plan Sheet MU-01, Structure No. 4)***
- 5. Exterior of Existing Aerobic Digester No. 1, No. 2, No. 3, No. 4, No. 5, No. 6 (Plan Sheet MU-01, Structure No. 6 and No. 45)***
- 6. Exterior of Existing Clarifier No. 1, No. 2, No. 3, and No. 4 (Plan Sheet MU-01, Structure No. 7, No. 8, No. 9, No. 41)***
- 7. Exterior of Existing Mixed Liquor Splitter Structure (Plan Sheet MU-01, Structure No. 10)***
- 8. Exterior of Existing Drum Storage Area (previous headworks odor control) (Plan Sheet MU-01, Structure No. 11)***
- 9. Exterior of Existing Chlorine Contact Chamber (CCC) No. 1, No. 2, No. 3 and Reuse wetwell (Plan Sheet MU-01, Structure No. 13, No. 14, No. 15)***
- 10. Exterior of Existing Reuse Wet Well (Plan Sheet MU-01, Structure No. 16)***
- 11. Exterior of Existing Sludge Dewatering Facility (Plan Sheet MU-01, Structure No. 17)***
- 12. Exterior of Filter Backwash Waste Basin (Plan Sheet MU-01, Structure No. 22)***
- 13. Exterior of Injection Well Containment Area (Plan Sheet MU-01, Structure No. 23)***
- 14. Exterior of Filter Dosing Pump Station Building (Plan Sheet MU-01, Structure No. 24)***
- 15. Exterior of Existing O&M Building (Plan Sheet MU-01, Structure No. 28)***
- 16. Exterior of Sodium Hypochlorite Bulk Storage Containment (Plan Sheet MU-01, Structure No. 31)***
- 17. Exterior of Existing Process Basin No. 3 Cast-in-Place and Pre-Cast Top (Plan Sheet MU-01, Structure No. 38)***
- 18. Exterior of Existing Reuse Wet Well #2 (Plan Sheet MU-01, Structure No. 42)***
- 19. Exterior of Existing High-Level Chlorine Contact Tanks (Plan Sheet MU-01, Structure No. 43)***
- 20. Exterior of Existing Effluent Filters (Plan Sheet MU-01, Structure No. 44)***
- 21. Exterior of Existing MCC & Generator Building (Plan Sheet MU-01, Structure No. 46)***
- 22. Exterior of Bulk Sodium Hydroxide Storage Facility (Plan Sheet MU-01, Structure No. 48)***
- 23. Exterior of Existing Fuel Storage Tank Containment Area (Plan Sheet MU-01, Structure No. 49)***
- 24. Exterior of Septage Receiving Station (Plan Sheet MU-01, Structure No. 51)***
- 25. Exterior of New Blower Building (Plan Sheet MU-01, Structure No. 55)***
- 26. Exterior of New Reuse Building (Plan Sheet MU-01, Structure No. 57)***
- 27. Exterior of Existing Odor Control Scrubber System Containment – Sludge Drying Building (Plan Sheet MU-01, Structure No. 63)***
- 28. Exterior of Existing Fuel Storage 10,000 gal Convault Tank (Plan Sheet MU-01, Structure No. 64)***
- 29. All other new and existing miscellaneous Above Grade Exterior Stucco, Concrete Block and Cast-In-Place Surfaces."***

55. Specification Section 09800, 3.08 Q – Delete entire paragraph and replace with the following:

"Q. Containment Areas (Interior) and Exterior of Concrete Tops:

- 1. New Aerobic Digesters No. 7, No. 8, No. 9, and No. 10 – exterior of concrete top***
- 2. Sodium hypochlorite containment area – all interior walls and floor***
- 3. Injection Well Containment Area – all interior walls and floor***
- 4. Fuel Storage Tank areas – all interior walls and floor"***


56. Specification Section 11226, 2.04 A. – Delete first sentence and replace with the following:

"The clarifier shall be provided with a 36 inch clear open width walkway extending the full circumference of the concrete tank as shown on the drawings"

57. Bid Documents, Schedule of Values – Page 24- Remove and replace the Schedule of Values in its entirety with the attached form:

- Removed item #5 : "Allowance for Headworks concrete repairs, T-lock liner repair, new T-lock liner."
- Renumbered subsequent items.

ACKNOWLEDGEMENT: Bidder must acknowledge receipt of any and all Addenda in the space provided on the Bidder Submittal Form. Failure to do so may result in rejection of the Proposal. All requirements of the proposal documents remain unchanged except as cited herein



Signature of Bidder Acknowledging Receipt of
Addendum No. (5) Five to be attached in front of Bid
Ronald F. Davoli, President/CEO
Wharton-Smith, Inc.

Council

Anne Gerwig, Mayor
Michael Drahos, Vice Mayor
John T. McGovern, Councilman
Michael J. Napoleone, Councilman
Tanya Siskind, Councilwoman

Manager
Paul Schofield

ITB 003-19/DZ

Title: Wastewater Treatment Renewal and Rehabilitation Project

Opening Date: February 6, 2019 at 2:00pm

Addendum Date: February 1, 2019

ADDENDUM NO. SIX

PURPOSE: The purpose of this Addendum/NOTICE is to make changes, additions, deletions, revisions, and clarifications to the (ITB) Invitation to Bid documents for the Wastewater Treatment Renewal and Rehabilitation Project. Bidder shall review the Addendum/NOTICE work and requirements in detail and incorporate any effects the Addendum/NOTICE may have in their proposal price.

1. Question:

The bid proposal checklist lists 12. References and 19. References and Prior Experience Form. There is a form for #19 but none for #12. What references are Wellington requesting to fulfill question #12?

Response: The information provided for Item 19 on checklist will fulfill item 12 on the checklist.

2. Question:

Due to the last minute nature of the bidding process is there any way the Village would consider allowing the Prime Contractor the ability to submit the Electrical and I&C subcontractors qualification information within 24 hours of the bid? In addition, do anticipate issuing any further addenda on this project?

Response: Yes, the Village would allow the Electrical and I&C subcontractors qualification information within 24 hours of the bid opening. Wellington will not expect any price changes after the bid opening. We do not anticipate any additional addendums.

3. Question:

The conduits on E-34A, E-34B, E-61 "Conduit & Wire Schedule's" have either no size or wire. Can you please furnish this information?

Response: Electrical Plan Sheets E-33, E-34A, and E-61 – Remove and replace with the attached.

ACKNOWLEDGEMENT: Bidder must acknowledge receipt of any and all Addenda in the space provided on the Bidder Submittal Form. Failure to do so may result in rejection of the Proposal. All requirements of the proposal documents remain unchanged except as cited herein

Signature of Bidder Acknowledging Receipt of
Addendum No. (6) Six to be attached in front of Bid
Ronald F. Davoli, President/CEO
Wharton-Smith, Inc.

BID BOND/SECURITY

(FAILURE TO COMPLETE THIS FORM MAY RESULT IN THE BID BEING DECLARED NON-RESPONSIVE)

KNOW ALL MEN BY THESE PRESENTS, that we Wharton-Smith, Inc.

as Principal, hereinafter called the Principal, and Western Surety Company

a corporation duly organized under the laws of the State of SD as Surety, hereinafter called the Surety, are held and firmly bound unto Wellington, Purchasing Dept., 12300 Forest Hill Boulevard, Wellington, FL 33414


as Oblige, hereinafter called the Oblige, in the sum of Ten Percent (10%) of amount bid for the payment of which sum well and truly to be made, the said Principal and the said Surety, bind ourselves, our heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these presents.

WHEREAS, the said Principal has submitted a bid for Wastewater Treatment Facility Renewal and Rehabilitation Project

NOW, THEREFORE, if the Oblige shall accept the bid of the Principal and the Principal shall enter into a Contract with the Oblige in accordance with the terms of such bid, and give such bond or bonds as may be specified in the bidding or Contract Documents with good and sufficient surety for the faithful performance of such Contract and for the prompt payment of labor and material furnished in the prosecution thereof, or in the event of the failure of the Principal to enter such Contract and give such bond or bonds, if the Principal shall pay to the Oblige the difference not to exceed the penalty hereof between the amount specified in said bid and such larger amount for which the Oblige may in good faith contract with another party to perform the Work covered by said bid, then this obligation shall be null and void, otherwise to remain in full force and effect.

Signed and sealed January 9, 2019

Witnesses:




Angeline Nisa

Wharton-Smith, Inc.

Seal


By:


Ronald F. Davoli, President/CEO

Western Surety Company

Seal

By:


April L. Lively, Attorney-in-Fact & FL Licensed
Resident Agent

Inquiries: (407) 834-0022

Western Surety Company

POWER OF ATTORNEY APPOINTING INDIVIDUAL ATTORNEY-IN-FACT

Know All Men By These Presents, That WESTERN SURETY COMPANY, a South Dakota corporation, is a duly organized and existing corporation having its principal office in the City of Sioux Falls, and State of South Dakota, and that it does by virtue of the signature and seal herein affixed hereby make, constitute and appoint

Eileen C Heard, Bryce R Guignard, M Gary Francis, April L Lively, Paul J Ciambriello, Jennifer L Hindley, Margie L Morris, Deborah Ann DeFoe, Christine A Morton, Individually

of Longwood, FL, its true and lawful Attorney(s)-in-Fact with full power and authority hereby conferred to sign, seal and execute for and on its behalf bonds, undertakings and other obligatory instruments of similar nature

- In Unlimited Amounts -

and to bind it thereby as fully and to the same extent as if such instruments were signed by a duly authorized officer of the corporation and all the acts of said Attorney, pursuant to the authority hereby given, are hereby ratified and confirmed.

This Power of Attorney is made and executed pursuant to and by authority of the By-Law printed on the reverse hereof, duly adopted, as indicated, by the shareholders of the corporation.

In Witness Whereof, WESTERN SURETY COMPANY has caused these presents to be signed by its Vice President and its corporate seal to be hereto affixed on this 17th day of November, 2017.



WESTERN SURETY COMPANY

Paul T. Bruflat, Vice President

State of South Dakota
County of Minnehaha

} ss

On this 17th day of November, 2017, before me personally came Paul T. Bruflat, to me known, who, being by me duly sworn, did depose and say: that he resides in the City of Sioux Falls, State of South Dakota; that he is the Vice President of WESTERN SURETY COMPANY described in and which executed the above instrument; that he knows the seal of said corporation; that the seal affixed to the said instrument is such corporate seal; that it was so affixed pursuant to authority given by the Board of Directors of said corporation and that he signed his name thereto pursuant to like authority, and acknowledges same to be the act and deed of said corporation.

My commission expires

June 23, 2021



J. Mohr, Notary Public

CERTIFICATE

I, L. Nelson, Assistant Secretary of WESTERN SURETY COMPANY do hereby certify that the Power of Attorney hereinabove set forth is still in force, and further certify that the By-Law of the corporation printed on the reverse hereof is still in force. In testimony whereof I have hereunto subscribed my name and affixed the seal of the said corporation this 9th day of January, 2019.



WESTERN SURETY COMPANY

L. Nelson, Assistant Secretary

SCHEDULE OF VALUES (Revised 1/23/19)

(FAILURE TO COMPLETE THIS FORM MAY RESULT IN THE BID BEING DECLARED NON-RESPONSIVE)

Item	Description	Estimated Quantity	Unit of Measure	Unit Price	Total for Item
1	Existing Ferrous Surface Preparation No. 1 (Refer to spec 01150 and 09800). The estimated quantity listed is to be included in the Base Bid	400	SF	6.00	2,400.00
2	Existing Ferrous Surface Preparation No. 2 (Refer to spec 01150 and 09800). The estimated quantity listed is to be included in the Base Bid	400	SF	6.00	2,400.00
3	Furnish all labor and materials to complete the project in accordance with the contract documents and plans	1	LS		16,620,200.00
	TOTAL PRICE IN WORDS 16,625,000.00	sixteen million six hundred twenty five thousand dollars and zero cents			
Allowances and Contingency					
4	Allowance for Operator Workstation and Cabinetry for Sludge Press Building	1	AL	\$50,000	\$50,000
5	Allowances for tension canvas cover for sodium hypochlorite storage tanks	1	AL	\$45,000	\$45,000
6	Allowance for architectural finish upgrades for built-in cabinetry, appliances, and furniture in Existing Operator’s Building and New Control Building	1	AL	\$100,000	\$100,000
7	Allowance for new console for New Operator’s Building	1	AL	\$60,000	\$60,000
8	Allowance for Switchgear Maintenance	1	AL	\$250,000	\$250,000
9	Allowance for new FPL Underground/Backup Feeder	1	AL	\$250,000	\$250,000
10	Owner Controlled Contingency – 10% of Item No. 3	1	AL	1,738,000.00	1,738,000.00
	GRAND TOTAL CONTRACT PRICE				19,118,000.00
	GRAND TOTAL CONTRACT PRICE IN WORDS	nineteen million one hundred eighteen thousand dollars and zero cents			

BIDDER/CONTRACTOR understands and agrees that this is a Lump Sum Contract and that successful contractor shall prepare and submit a detailed Schedule of Values to Wellington for approval prior to first payment application.

Item	Description	Estimated Quantity	Unit of Measure	Unit Price	Total for Item
A1	Alternate Bid Item: Clarifier No. 3 Demo and Rehabilitation	1	LS		1,150,000.00

SCHEDULE OF SUBCONTRACTORS

(FAILURE TO COMPLETE THIS FORM MAY RESULT IN THE BID BEING DECLARED NON-RESPONSIVE)

<u>Discipline</u>	<u>Subcontractor</u>	<u>Address City, ST, Zip</u>	<u>License Number</u>
<u>Electrical</u>	Edwards Electric Corp - 7231 Southern Blvd, WPB, FL 33413 - EC0001100		
<u>Instrumentation</u>	C.C. Controls - 5760 Corp Way, Suite 100, WPB, FL 33407 - N/A		
<u>Coatings</u>	Atlantic Painting & Sandblasting, LLC - 1100 S. Federal Hwy, #4, Boynton Beach, FL 33435 - N/A		

Address of Subcontractor may be considered in accordance with Wellington's Local Preference Policy

SCHEDULE OF EQUIPMENT AND MATERIALS

(FAILURE TO COMPLETE THIS FORM MAY RESULT IN THE BID BEING DECLARED NON-RESPONSIVE)

Item	Manufacturer
Tertiary Filter and Compressed Air System	Parkson
Aerobic Digester Process Blower	Aerzen
Belt Filter Press Feed Pumps	Wemco
Headworks Odor Control System	TSC Jacobs/JAWS
Grit Classifier Effluent Lift Station Pumps	Flygt
Sludge Cake Feed Pump	Seepex
Grit Cyclone and Screw Classifier	Ovivo
Alternate Bid Item: Clarifier No. 3	Ovivo

SWORN STATEMENT UNDER SECTION 287.133(3)(a), FLORIDA STATUTES, ON PUBLIC ENTITY CRIMES

(FAILURE TO COMPLETE THIS FORM MAY RESULT IN THE BID BEING DECLARED NON-RESPONSIVE)

THIS FORM MUST BE SIGNED IN THE PRESENCE OF A NOTARY PUBLIC OR OTHER OFFICER AUTHORIZED TO ADMINISTER OATHS.

1. This sworn statement is submitted to Wharton-Smith, Inc.
by Ronald F. Davoli, President/CEO [print name of the public entity]
[print individual's name and title]
for Wharton-Smith, Inc.
[print name of entity submitting sworn statement]

whose business address is 750 Monroe Road, Sanford, FL 32771

and (if applicable) its Federal Employer Identification Number (FEIN) is 59-2392802

(If the entity has no FEIN, include the Social Security Number of the individual signing this sworn statement: _____.)

2. I understand that a "public entity crime" as defined in Paragraph 287.133(1)(g), Florida Statutes, means a violation of any state or federal law by a person with respect to and directly related to the transaction of business with any public entity or with an agency or political subdivision of any other state or of the United States, including, but not limited to, any bid or contract for goods or services or any contract for the construction or repair of a public building or public work, to be provided to any public entity or an agency or political subdivision of any other state or of the United States and involving antitrust, fraud, theft, bribery, collusion, racketeering, conspiracy, or material misrepresentation.
3. I understand that "convicted" or "conviction" as defined in Paragraph 287.133(1)(b), Florida Statutes, means a finding of guilt or a conviction of a public entity crime, with or without an adjudication of guilt, in any federal or state trial court of record relating to charges brought by indictment or information after July 1, 1989, as a result of jury verdict, nonjury trial, or entry of a plea of guilty or nolo contendere.
4. I understand that an "affiliate" as defined in Paragraph 287.133(1)(a), Florida Statutes, means:
1. A predecessor or successor of a person convicted of a public entity crime; or
 2. An entity under the control of any natural person who is active in the management of the entity and who has been convicted of a public entity crime. The term "affiliate" includes those officers, directors, executives, partners, shareholders, employees, members, and agents who are active in the management of an affiliate. The ownership by one person of shares constituting a controlling interest in another person, or a pooling of equipment or income among persons when not for fair market value under an arm's length agreement, shall be a prima facie case that one person controls another person. A person who knowingly enters into a joint venture with a person who has been convicted of a public entity crime in Florida during the preceding 36 months shall be considered an affiliate.
5. I understand that a "person" as defined in Paragraph 287.133(1)(c), Florida Statutes, means any natural person or entity organized under the laws of any state or of the United States with the legal power to enter into a binding contract and which bids or applies to bid on contracts for the provision of goods or services let by a public entity, or which otherwise transacts or applies to transact business with a public entity. The term "person" includes those officers, directors, executives, partners, shareholders, employees, members, and agents who are active in management of an entity.
6. Based on information and belief, the statement which I have marked below is true in relation to the entity submitting this sworn statement. [Please indicate which statement applies.]

X Neither the entity submitting this sworn statement, nor any officers, directors, executives, partners, shareholders, employees, members, or agents who are active in management of the entity, nor any affiliate of the entity has been charged with and convicted of a public entity crime subsequent to July 1, 1989.

_____ The entity submitting this sworn statement, or one or more of the officers, directors, executives, partners, shareholders, employees, members, or agents who are active in management of the entity, or an affiliate of the entity has been charged with and convicted of a public entity crime subsequent to July 1, 1989.

_____ The entity submitting this sworn statement, or one or more of its officers, directors, executives, partners, shareholders, employees, members, or agents who are active in the management of the entity, or an affiliate of the entity has been charged with and convicted of a public entity crime subsequent to July 1, 1989. However, there has been a subsequent proceeding before a Hearing Officer of the State of Florida, Division of Administrative Hearings and the Final Order entered by the Hearing Officer determined that it was not in the public interest to place the entity submitting this sworn statement on the convicted vendor list. [attach a copy of the final order]

I UNDERSTAND THAT THE SUBMISSION OF THIS FORM TO THE CONTRACTING OFFICER FOR THE PUBLIC ENTITY IDENTIFIED IN PARAGRAPH 1 (ONE) ABOVE IS FOR THAT PUBLIC ENTITY ONLY AND, THAT THIS FORM IS VALID THROUGH DECEMBER 31 OF THE CALENDAR YEAR IN WHICH IT IS FILED. I ALSO UNDERSTAND THAT I AM REQUIRED TO INFORM THE PUBLIC ENTITY PRIOR TO ENTERING INTO A CONTRACT IN EXCESS OF THE THRESHOLD AMOUNT PROVIDED IN SECTION 287.017, FLORIDA STATUTES FOR CATEGORY TWO OF ANY CHANGE IN THE INFORMATION CONTAINED IN THIS FORM

Ronald F. Davoli,
President/CEO

[signature]

February 6, 2019

[date]

STATE OF Florida

COUNTY OF Seminole

Subscribed and Sworn to (or affirmed) before me on February 6, 2019 by

Ronald F. Davoli [date]

He/she is personally known to me or has presented

personally known [name]


[type of identification] as identification.

[Notary's Signature and Seal]

Dawn K. Bragg

GG243561

Print Notary Name and Commission No.



DRUG FREE WORKPLACE

(FAILURE TO COMPLETE THIS FORM MAY RESULT IN THE BID BEING DECLARED NON-RESPONSIVE)

Preference may be given to businesses with drug-free workplace programs. Whenever two or more Bids which are equal with respect to price, quality, and service are received by the Owner for the procurement of commodities or contractual services, a Bid received from a business that certifies that it has implemented a drug-free workplace program may be given preference in the award process. Established procedures for processing tie Bids will be followed if none of the tied vendors have a drug-free workplace program. In order to have a drug-free workplace program, a business must attest to the following:

1. We publish a statement notifying employees that the unlawful manufacture, distribution, dispensing, possession, or use of a controlled substance is prohibited in the workplace and specifying the actions that will be taken against employees for violations of such prohibition.
2. We inform employees about the dangers of drug abuse in the workplace, the business's policy of maintaining a drug-free workplace, any available drug counseling, rehabilitation, and employee assistance programs, and the penalties that may be imposed upon employees for drug abuse violations.
3. We give each employee engaged in providing the commodities or contractual services that are under Bid a copy of the statement specified in subsection (1).
4. We, in the statement specified in subsection (1), notify the employees that, as a condition of working on the commodities or contractual services that are under Bid, the employee will abide by the terms of the statement and will notify the employer of any conviction of, or plea of guilty or nolo contendere to, any violation of Chapter 893 or of any controlled substance law of the United States or any state, for a violation occurring in the workplace no later than five (5) days after such conviction.
5. We impose a sanction on, or require the satisfactory participation in a drug abuse assistance or rehabilitation program if such is available in the employee's community, by any employee who is so convicted.
6. We make a good faith effort to continue to maintain a drug-free workplace through implementation of this section.

As the person authorized to sign the statement, I certify that this firm complies fully with the above requirements.



Contractor's Signature

Ronald F. Davoli, President/CEO
Wharton-Smith, Inc.


TRENCH SAFETY AFFIDAVIT

(FAILURE TO COMPLETE THIS FORM MAY RESULT IN THE BID BEING DECLARED NON-RESPONSIVE)

Wharton-Smith, Inc. (NAME OF FIRM) hereby provides written assurance that compliance with applicable Trench Safety Standards identified in the Occupational Safety and Health Administration's Excavation Safety Standards, (OSHA) 29 C.F.R.S. 1926.650 Subpart P will be adhered to during trench excavation in accordance with Florida Statutes 553.60 through 533.64 inclusive (1990), "Trench Safety Act".

The undersigned acknowledges that included in the various items of the proposal and in the Total Proposal Price are costs for complying with the Florida "Trench Safety Act" as summarized below: (Attach additional sheets as necessary).

Schedule Item	Trench Safety Measure (Slope, Trench Shield, etc.)	Cost
Piping	Open Cut	6,800
	Total	6,800


(Signature)

Ronald F. Davoli, President/CEO

02/06/2019

(Date)

STATE OF Florida

COUNTY OF Seminole


Subscribed and Sworn to (or affirmed) before me on February 6, 2019 by

Ronald F. Davoli, President/CEO He/she is personally known to me or has presented

personally known (type of i.d.) as identification.


Notary Public Signature and Seal

Dawn K. Bragg GG243561
Print Notary Name and Commission No.



QUESTIONNAIRE

The following Questionnaire shall be completed and submitted in Envelope with the Bid. By submission of this Bid, Bidder guarantees the truth and accuracy of all statements and answers herein contained.

1. How many years has your organization been in business? 34 years

2. Have you ever failed to complete work awarded to you? If so, where and why?

No.

3. Has the bidder or his or her representative inspected the proposed project and does the Bidder have a complete plan for its performance?

Yes

4. Will you subcontract any part of this work? If so, give details including a list of each subcontractor(s) that will perform work in excess of the percent (10%) of the contract amount and the work that will be performed by each subcontractor(s).

Subcontractor	Work to be Performed
Yes. Please see attached "Schedule of Subcontractors" on page 25.	

5. What equipment do you own that is available for the work? Please see attached Company Equipment List.

6. What equipment will you purchase for the proposed work? As needed or required.

7. What equipment will you rent for the proposed work? As needed or required.

8. State the name of your proposed project manager and give details of his or her qualifications and experience in managing similar jobs.

Michael Hernandez, Please see attached Resume.

9. State the true, exact, correct and complete name of the partnership, corporation, or trade name under which you do business and the address of the place of business. (If a corporation, state the name of the president and secretary. If a partnership, state the names of all partners. If a trade name, state the names of the individuals who do businesses under the trade name.

10. The correct name of the Bidder is Wharton-Smith, Inc.

11. The partnership is a ☐ Sole Proprietorship, ☐ Partnership, or ☒ Corporation or ☐ Other Type of Entity _____ (Fill In).

12. The address of principal place of business is 750 Monroe Road, Sanford, FL 32771

13. The names of the Corporate Officers, or Partners, or Individuals doing business under a trade name, are as follows:
Ronald F. Davoli, President/CEO & Treasurer, Devon A. Lewis, Corporate Secretary

Executive Vice Presidents: Timothy Smith, Patrick Hewitt, Darin Crafton

Vice President: Clyde Burgess, David Hayes, John Lyons, Devon Lewis, Bob Hahn

14. List all organizations which were predecessors to Bidder or in which the principals or officers of the Bidder were principals or officers.

N/A

15. List and describe all bankruptcy petitions (Voluntary or Involuntary) which have been filed by or against the Bidder, its parent or subsidiaries or predecessor organizations during the past five (5) years. Include in the description the disposition of each such petition.

N/A

16. List and describe all successful Performance or Payment Bond claims made to your surety(ies) during the last five (5) years. The list and descriptions should include claims against the bond of the Bidder and its predecessor organization(s).

N/A

17. List all claims, arbitrations, administrative hearings and lawsuits brought by or against the Bidder or its predecessor organization(s) during the last five (5) years. The list shall include all case names; case, arbitration, or hearing identification numbers; the name of the project over which the dispute arose; and a description of the subject matter of the dispute.

Please see attached Litigation Statement.

18. List and describe all criminal proceedings or hearings concerning business related offenses in which the Bidder, its principals or officers or predecessor organization (s) were defendants.

N/A

19. Has the Bidder, its principals, officers, or predecessor organization(s) been debarred or suspended from bidding by any government during the last five (5) years? If yes, provide details.

N/A

20. List and disclose any and all business relations with any members of Wellington Council.

N/A



Company Owned Equipment List

CAT 420 EIT Backhoe Ext 2007 KMW 01380	Grout Pump
CAT 420D-IT Backhoe 2002 BLN 05082	PC228 Vib Compactor 12EG06686
CAT 420E IT Backhoe 2007 KMW 01408	PC228 Vib Compactor
CAT 420D-IT Backhoe Ext 2005 BLN 12036	JD XUV 620i 2007 MOHXOPA041950- Prod ID MOXUVGT020478
CAT 420D-IT Backhoe Ext 2005 BLN 12067	2015 Polaris Ranger Crew 900 VIN- 3NSRUY875FG494967
CAT 420D-IT Backhoe Ext 2005 BLN 12972	2015 Polaris 570 Ranger VIN- 3NSRMA574FE370079
CAT 420E-IT Backhoe 2010 PHC00841	2015 Polaris 570 Ranger VIN- 3NSRMA574FE370079
Case 580M Backhoe 2wd 2005 NSC390925	2015 Polaris Ranger Crew 570 VIN- 3NSRMA574FE375568
Cat 420 FIT Backhoe Ext 2016 HWD01195	2015 Polaris 570 Ranger MS Crew VIN- 3NSRMA574FE370581
Cat 420 FIT Backhoe Ext 2016 HWD01197	2016 Polaris 570 Ranger MS Crew VIN- 3NSRMA57XGE753281
CAT 320L Trackhoe 2007 PAB 07572	2016 Polaris 570 Ranger MS Crew VIN- 3NSRMA578GE745373
Case mini IC CX47 2004 DFE000268MXME4	Terranite TSS36 Ride On Sweeper
Excavator, Kobelco 2001 sk330c/YC06-U0455	Cat Generator for LM office
CAT 304CCR Excavator 2006 FPK00472	2013 Ford F150 VIN-1FTNF1CF7DKF86619
Cat 320DLRR Excavator 2008 XCK00248	2012 Ford F150 Ext. Cab Long Bed VIN-1FTFX1CFXCKD31169
Cat 320DLRR Excavator 2008 XCK00250	2011 Ford Taurus VIN- 1FAHP2EW3BG180677
Komatsu PC138USLC-2 Excavator 2007 2229	2011 Ford Taurus VIN- 1FAHP2EW3BG180677
Komatsu PC228USLC-3 EO Excavator 2007 40632	2011 Ford Taurus VIN- 1FAHP2EW3BG180677
Komatsu PC228USLC-3 EO Excavator 2007 40396	2013 Ford F150 VIN-1FTNF1CF3DKG12021
Komatsu PC300LC-7EO Excavator 2007 A88715	2013 Ford F150 Ext Cab VIN- 1FTFX1CFXDA68689
Case CX80 Excavator 2005 DAC881161	2013 Ford F150 Ext Cab VIN- 1FTFX1CFXDA68689
CAT 304CCR Excavator 2007 FPK03333	2013 Ford F150 Ext Cab VIN- 1FTFX1CFXDA68689
CAT 336EL Excavator 2015 Serial- BZY02619	2013 Ford F150 Ext Cab VIN- 1FTFX1CFXDA68689
CAT TH360 Mat. Handler 2006 SLE 04746	2011 Chevy Impala VIN- 2G1WT57K891261666
CAT TH360 Mat. Handler 2006 SLE 04747	Dodge 3500 flatbed VIN- 3D6WG48A68G202255
CAT TH360 Mat. Handler 2006 SLE 05400	Dodge 3500 flatbed VIN- 3D6WG48A68G202255
CAT TL642 Mat. Handler 2007 TBK 00809	Dodge 3500 flatbed VIN- 3D6WG48A68G202255
JLG 8042 Skytrack Material Handler 2008 Sn=0160037030	Dodge 3500 flatbed VIN- 3D6WG48A68G202255
CAT TL642C Mat. Handler 2015 THG01537	Dodge 3500 flatbed VIN- 3D6WG48A68G202255
CAT TL642C Mat. Handler 2013 THG00266	Dodge 3500 flatbed VIN- 3D6WG48A68G202255
CAT TL642C Mat. Handler 2013 THG00268	Dodge 3500 flatbed VIN- 3D6WG48A68G202255
Air Comp. Mod 185CA-S/N # 200707050029	2011 Ford Explorer VIN- 1FMHK7D89CGA52885
Air Comp. Mod. 185CA-S/N # 200707050052	2011 Ford Explorer VIN- 1FMHK7D89CGA52885
CFM 185 Air Compressor 139835	2010 Ford F150 Reg Cab VIN- 1FTNF1CV7AKE78665
Air compressor Atlascopco/xas96jd/611284	Dump Truck , Ford 1995/F800/1fdnf80c2sva31555
Air compressor, Atlascopco/xas96jd/611959	Lowe 1655CC Roughneck Boat w/ Tr Vin- LWCJ0229JB09
CFM 200 D21006JD	Steel Equipment Trailer
Air Comp. Mod D-185 Sullivan S/N 16433A	2005 White Utility Trailer 5C7EE182XD000828 (HDPE)
Sullair AC Mod 185DPQP Ser.004149046	Econoline 16 Ton Trailer
Welder Miller Big 40 kh486545	8x20 10K Flatbed Trailer 4P5L62020F3014275
Welder Miller Big 50 kf992212	2005 Wood Deck Equipment 4Y3US18235S015824
Coleman GenPak Generator C14L17GP Serial- 7983054	7X14 10K Lb. Dump Tr 2015
HDPE Welder	Enclosed trailer TA BP 7x16 2016 VIN- 50XBE1621GA000203
Miller Bobcat 250 Welder/Generator SN- MF420169R	Enclosed trailer TA BP 7x16 2016 VIN 50XBE1627GA001128
Massy Ferg Fork lift	7x16 7K Equipment Trailer TA BP 2016 VIN- 5BFAF1624GM031396
Linde H25D Fork Lift 2004 H2X392R03058	Equip. Manager Misc. (Code 4001)
CAT 928G Loader 2007 DJD 02879	La. Mechanic Expendable's
Komatsu WA200PZ-6 Loader 2009 70752 L-2	WS Logo Extension Cord qty-12
Cat 289C Compact Track Loader 2010 JMP00968	WS Logo Extension Cord qty-4
Cat 289C Compact Track Loader 2012 RTD00815	WS Logo Extension Cord qty-3
Wacker Light Tower Model # LTC4L Serial # 5753512	Connex Rental
	Miscellaneous Tools
Total Approximate Value: \$2,135,800.00	

Wharton-Smith, Inc. will lease or rent as needed and/or required by the specific project requirements. In order to expedite repair and maintain equipment, Wharton-Smith, Inc. will utilize an equipment manufacturer within a 50 mile radius of the jobsite to ensure minimum delay.

Mike Hernandez

Project Manager

KEY QUALIFICATIONS

18+ years of experience
with Water/Wastewater
construction

EDUCATION

B.S., Mechanical
Engineering, Polytechnic
University of Puerto Rico,
1999

YEARS OF EXPERIENCE

1—Wharton-Smith
18—Total

REGISTRATIONS / LICENSES / CERTIFICATIONS

30 HR OSHA

Mike has eighteen years of construction experience and is responsible for all construction phases of water treatment plants. He works with Owners and design consultants to execute these projects. His primary focus is in the reviews, scheduling, value engineering and cost estimates, submitting and releasing long lead material items, and contract administration (subcontracts, purchase orders, change orders, etc.). Mike remains involved in all work through completion including plant start-up activities, close-out and warranty. Mike resolves issues that arise throughout the construction phase.

Project Experience

- Sunrise Southwest WTP Rehab, City of Sunrise, FL (\$13.8 million)
- Reclaimed Water System Expansion Ph1, City of Miramar, FL (\$1.8 million)

Previous Experience:

- Rehab of Duplex Wastewater Pump Stations, Collier County, FL (\$3.8 million)
- Lilly del Caribe WWTP Upgrades (\$5.5 million)
- Vega Alta WWTP, Design Build (\$2.2 million)
- Improvements to Palmarego Pump Station (\$3.3 million)
- Caguas WWTP Improvements (\$2.9 million)
- Energy Conservation Program WWTP Caguas & Barceloneta (\$2 million)
- Puerto Nuevo Regional WWTP General Upgrades (\$18.2 million)
- Water Transmission Line from Juana Diaz - Coamo (\$2.6 million)
- Guayama WTP Compliance (\$8.3 million)
- Caguas Norte WTP (\$7.6 million)
- Upgrade for Compliance in Water Filtration Plant Sergio Cuevas (\$10.2 million)
- Expansion to Water Filtration Plant in Lajas (\$12 million)



Guy Diorio

Project Superintendent

KEY QUALIFICATIONS

33 years of experience in the Construction Industry

YEARS OF EXPERIENCE

10—Wharton-Smith
33—Total

REGISTRATIONS / LICENSES / CERTIFICATIONS

Certified Florida Building Contractors License
CPR, First Aid and Safety
OSHA - 10 Hour
Competent Person:

- Confined Space Entry
 - Trenching & Excavation
 - Scaffolding
 - Fall Protection
 - Intermediate MOT Certification
 - Lull, Forklift
- Member of ABC
Member of AGC

Guy is responsible for supervision and coordination of the day-to-day activities of the subcontractors and Wharton-Smith employees. He will oversee safety & building inspections, schedule requirements and quality compliance. Guy will complete daily reports, two-week look ahead schedules, weekly jobsite meetings, material delivery coordination, storage and installation requirements, project final quality and start up planning.

Project Experience

- Southwest WTP Rehab, City of Sunrise, FL (\$13.8 million)
- Wellington WWTP Headworks Repairs, Village of Wellington, FL (\$375,000)
- KLWTD Chemical Upgrades, Key Largo Wastewater Treatment District, FL (\$400,000)
- KLWTD Biosolids Digester, Key Largo Wastewater Treatment District, FL (\$4 million)
- Cudjoe Key AWRF, Cudjoe Key, FL (\$21.9 million)
- KWRU WWTP Expansion, Key West Utility Corporation, FL (\$4.3 million)
- SWA Injection Well Pump Station, Solid Waste Auth of PBC, FL (\$1.6 million)
- Key West George Street Stormwater Basin, Key West, FL (\$3.2 million)
- East Central Regional Water Reclamation Facility, NextEra Energy (FP&L), FL (\$17 million)
- Wellington WWTP Expansion, City of Wellington, FL (\$21.6 million)
- West Regional WWTF, Indian River County, FL (\$23 million)





LITIGATION AND CLAIMS HISTORY

Wharton-Smith believes that potential conflicts can easily be avoided by developing trustworthy relationships early on with all parties involved on a project and by encouraging open communications. The successes we have had on our projects are due in large part to our commitment to partnering and conflict prevention and resolution. Occasionally, a situation arises where a third-party mediation is needed, despite all efforts to avoid it. ***Our litigation record for the past five years is as follows:***

OWNER/CLIENTS:

UCF Stadium Corporation f/k/a Golden Knights Corporation, et al. vs. Dant Clayton Corporation, Wharton-Smith, Inc., et al. (Case No. 2017-CA-008259-O, The Circuit Court, Ninth Judicial Circuit, Orange County, Florida): In September 2017, UCF filed suit against Dant Clayton Corporation, Wharton-Smith and others over alleged breach of contract regarding the design-build contracts for the construction of their stadium. Wharton-Smith was then dismissed from the suit with a Tolling Agreement that they could be brought back in before April 1, 2019. In December 2018, Wharton-Smith was brought back into the lawsuit. ***The suit is presently being mediated and is in the early stages of discovery.***

SUBCONTRACTORS/SUBCONSULTANTS:

Southern Atlantic Companies, LLC vs. Wharton-Smith, Inc. (Case No. 10CA-7820-11-G, The Circuit Court of the 18th Judicial Circuit, Seminole County, Florida): In December 2010, Southern Atlantic Companies, LLC, filed suit against Wharton-Smith, Inc. over 1) alleged misrepresentations during a bidding process and for 2) alleged interference with their business relationships subsequent to the bidding. ***This case was dismissed in April 2015.***

Emerald Utilities & Site Development, Inc. vs. Wharton-Smith, Inc. (Case No. 2012-CA-015654-O, The Circuit Court, Ninth Judicial Circuit, Orange County, Florida): In September 2012, Emerald Utilities filed suit against Wharton-Smith over alleged breach of contract regarding a claim on the Orange County Southern Regional Water Supply Facility. Wharton-Smith maintains that the claim, if valid, is a pass through claim to the owner, Orange County Public Utilities, which has denied the claim. ***This case settled during mediation in March 2014.***

Wharton-Smith, Inc. vs. Sitek Corp. and Allegheny Casualty Co. (Case No. 2015-CA-002755-15-G, The Circuit Court of the 18th Judicial Circuit for Seminole County, Florida): In November 2015, Wharton-Smith filed suit against Sitek for breach of contract. They had been terminated from the Cypress Creek High School project for their failure to complete their subcontract work. ***This case was settled during mediation in January 2018.***

Suwannee Valley Grassing, Inc. vs. Wester Surety Co., Wharton-Smith, Inc. and Barco-Duval Engineering, Inc. (Case No. 2015-CA-4388, In the Circuit Court of the Eighth Judicial Circuit in Alachua County, Florida): In December 2015, Suwannee filed suit for breach of Contract regarding a subcontract they had with Barco-Duval. Barco-Duval was a subcontractor to Wharton-Smith on the Paynes Prairie Sheetflow Restoration project and has a dispute with Suwannee over non-performance and work not completed. ***Barco-Duval has assumed the defense obligations of Wharton-Smith in accordance with their subcontract. Wharton-Smith was dismissed from the case in September 2016.***

THIRD-PARTY:

J.D. Fields & Company, Inc. vs. Nottingham Construction Company, LLC, Wharton-Smith, Inc., and Professional Construction Services, Inc. (Case No. 2012-0002517, 21st Judicial District Court for the Parish of Tangipahoa, State of Louisiana): In August of 2012, J.D. Fields filed suit against Wharton-Smith over a dispute



they had with Nottingham and Professional Construction Services in 2006. Wharton-Smith had purchased selected assets only from Nottingham in August 2010 and did not purchase this project or assume any liability in this dispute. ***Wharton-Smith was dismissed from this suit in September 2014.***

REQUEST FOR PROOF OF WORKERS COMPENSATION INSURANCE OR EXEMPTION

Dear Provider of Services or Goods:

In order to provide services or goods to Wellington, we require that you provide us either proof of workers compensation coverage or proof of exemption.

Employers conducting work in the State of Florida are required to provide workers' compensation insurance for their employees. Specific employer coverage requirements are based on the type of industry, number of employees and entity organization. To determine coverage requirements for a specific employer, the following information is provided by the Bureau of Compliance.

Construction Industry - One (1) or more employees, including the owner of the business who are corporate officers or Limited Liability Company (LLC) members. For a list of the trades considered to be in the construction industry see 69L-6.021 Florida Administrative Code.

Non-Construction Industry - Four (4) or more employees, including business owners who are corporate officers or Limited Liability Company (LLC) members.

Please note: Non-construction industry Sole Proprietors or partners in a Partnership are not employees unless they want to be included on the business' Workers' Compensation Insurance policy and file a form DWC 251 with the Division of Workers' Compensation.

Agricultural Industry - Six (6) regular employees and/or twelve (12) seasonal workers who work more than 30 days during a season but no more than a total of 45 days in a calendar year.

Out of State Employers must notify their insurance carrier that they are working in Florida. If there is no insurance, the out of state employer is required to obtain a Florida Workers' Compensation Insurance policy with a Florida approved insurance carrier which meets the requirements of Florida law and the Florida Insurance Code. This means that "Florida" must be specifically listed in Section 3A of the policy (on the Information Page).

An Extraterritorial Reciprocity clause in the home state's statute allows some out of state Employers to work in Florida temporarily using their home state's Workers' Compensation insurance policy.

Contractors are required to make certain that all sub-contractors have the required Workers' Compensation Insurance **before** they begin work on a project. To see the documentation that is required from a sub-contractor, see 69L-6.032 Florida Administrative Code.

If the sub-contractor does not have Workers' Compensation Insurance for its employees, those workers become the employees of the contractor. If an injury occurs, the contractor is responsible for paying the benefits for the work related injury, illness or fatality.

If you meet the above criteria to be exempt, you **MUST** provide us with one of the following:

- If your business is a sole proprietorship or unincorporated business: provide us a Verification of Automatic Exempt Certificate. This verification is a letter that is issued by the State of Florida Department of Financial Services. To receive a letter from the State, complete the following directions: 1) Call the National Council of Compensation Insurance 1-800-622-4123, Option 5, and ask them for the class code for your type of business. 2) Once you have received this code, call the Department of Financial Services at 1-850-413-1601 and provide them your business name, class code, mailing address, and contact phone number. They will send you the Verification of Automatic Exempt Certificate. 3) Provide us a copy of the Verification of Automatic Exempt Certificate.
- If your business is a corporation (including a professional association or limited liability company), and you are not required to have workers compensation insurance as per the requirements as outlined above, you must provide the Village with a copy of your Florida Division of Workers' Compensation Certificate of Election to be Exempt.

If you are an employer that meets the requirements of workers compensation and needs to obtain coverage, contact your current business insurance agent, or you may use the following resources to locate an agent: www.faia.com, www.piafl.org/wc-info.pdf, or call (850) 893-8245.

Please be reminded that the furnishing of this information to Wellington is a non-negotiable requirement to perform services for us. Failure to provide this timely may result in either termination of your services or delay of payment for services. Your workers compensation Certificate of Coverage, of Workers' Compensation Certificate of Election to be Exempt, or Verification of Automatic Exempt Certificate must be delivered or mailed to the Purchasing Department located at 12300 Forest Hill Boulevard, Wellington, Florida, 33414.

ACORD™

CERTIFICATE OF LIABILITY INSURANCE

DATE (MM/DD/YYYY)

4/30/2018

THIS CERTIFICATE IS ISSUED AS A MATTER OF INFORMATION ONLY AND CONFERS NO RIGHTS UPON THE CERTIFICATE HOLDER. THIS CERTIFICATE DOES NOT AFFIRMATIVELY OR NEGATIVELY AMEND, EXTEND OR ALTER THE COVERAGE AFFORDED BY THE POLICIES BELOW. THIS CERTIFICATE OF INSURANCE DOES NOT CONSTITUTE A CONTRACT BETWEEN THE ISSUING INSURER(S), AUTHORIZED REPRESENTATIVE OR PRODUCER, AND THE CERTIFICATE HOLDER.

IMPORTANT: If the certificate holder is an ADDITIONAL INSURED, the policy(ies) must have ADDITIONAL INSURED provisions or be endorsed. If SUBROGATION IS WAIVED, subject to the terms and conditions of the policy, certain policies may require an endorsement. A statement on this certificate does not confer any rights to the certificate holder in lieu of such endorsement(s).

PRODUCER Bouchard Insurance Inc. 101 N Starcrest Dr. Clearwater, FL 33765 727 447-6481		CONTACT NAME: PHONE (A/C, No, Ext): 727 447-6481 FAX (A/C, No): 727 449-1267 E-MAIL ADDRESS: certificates@bouchardinsurance.com															
INSURED Wharton-Smith, Inc. PO Box 471028 Lake Monroe, FL 32747		INSURER(S) AFFORDING COVERAGE <table border="1"> <tr> <th>INSURER</th> <th>NAIC #</th> </tr> <tr> <td>INSURER A : Amerisure Insurance Company</td> <td>19488</td> </tr> <tr> <td>INSURER B : Liberty Insurance Underwriters</td> <td>19917</td> </tr> <tr> <td>INSURER C : Starr Indemnity & Liability Co</td> <td>38318</td> </tr> <tr> <td>INSURER D : XL Specialty Insurance Co</td> <td>37885</td> </tr> <tr> <td>INSURER E : Berkley Assurance Company</td> <td>39462</td> </tr> <tr> <td>INSURER F :</td> <td></td> </tr> </table>		INSURER	NAIC #	INSURER A : Amerisure Insurance Company	19488	INSURER B : Liberty Insurance Underwriters	19917	INSURER C : Starr Indemnity & Liability Co	38318	INSURER D : XL Specialty Insurance Co	37885	INSURER E : Berkley Assurance Company	39462	INSURER F :	
INSURER	NAIC #																
INSURER A : Amerisure Insurance Company	19488																
INSURER B : Liberty Insurance Underwriters	19917																
INSURER C : Starr Indemnity & Liability Co	38318																
INSURER D : XL Specialty Insurance Co	37885																
INSURER E : Berkley Assurance Company	39462																
INSURER F :																	

COVERAGES

CERTIFICATE NUMBER:

REVISION NUMBER:

THIS IS TO CERTIFY THAT THE POLICIES OF INSURANCE LISTED BELOW HAVE BEEN ISSUED TO THE INSURED NAMED ABOVE FOR THE POLICY PERIOD INDICATED. NOTWITHSTANDING ANY REQUIREMENT, TERM OR CONDITION OF ANY CONTRACT OR OTHER DOCUMENT WITH RESPECT TO WHICH THIS CERTIFICATE MAY BE ISSUED OR MAY PERTAIN, THE INSURANCE AFFORDED BY THE POLICIES DESCRIBED HEREIN IS SUBJECT TO ALL THE TERMS, EXCLUSIONS AND CONDITIONS OF SUCH POLICIES. LIMITS SHOWN MAY HAVE BEEN REDUCED BY PAID CLAIMS.

INSR LTR	TYPE OF INSURANCE	ADDL INSR	SUBR WVD	POLICY NUMBER	POLICY EFF (MM/DD/YYYY)	POLICY EXP (MM/DD/YYYY)	LIMITS
A	<input checked="" type="checkbox"/> COMMERCIAL GENERAL LIABILITY <input type="checkbox"/> CLAIMS-MADE <input checked="" type="checkbox"/> OCCUR <input checked="" type="checkbox"/> Contractual Liab <input checked="" type="checkbox"/> XCU Included GEN'L AGGREGATE LIMIT APPLIES PER: <input type="checkbox"/> POLICY <input checked="" type="checkbox"/> PRO-JECT <input type="checkbox"/> LOC OTHER:	Y	Y	GL20361081301	04/01/2018	04/01/2019	EACH OCCURRENCE \$1,000,000 DAMAGE TO RENTED PREMISES (Ea occurrence) \$1,000,000 MED EXP (Any one person) \$10,000 PERSONAL & ADV INJURY \$1,000,000 GENERAL AGGREGATE \$2,000,000 PRODUCTS - COMP/OP AGG \$2,000,000 \$
A	AUTOMOBILE LIABILITY <input checked="" type="checkbox"/> ANY AUTO OWNED AUTOS ONLY <input checked="" type="checkbox"/> HIRED AUTOS ONLY <input type="checkbox"/> SCHEDULED AUTOS NON-OWNED AUTOS ONLY	Y	Y	CA20361071301	04/01/2018	04/01/2019	COMBINED SINGLE LIMIT (Ea accident) \$1,000,000 BODILY INJURY (Per person) \$ BODILY INJURY (Per accident) \$ PROPERTY DAMAGE (Per accident) \$ \$
B	UMBRELLA LIAB <input checked="" type="checkbox"/> OCCUR <input checked="" type="checkbox"/> EXCESS LIAB <input type="checkbox"/> CLAIMS-MADE DED RETENTION \$	Y	Y	100008433605	04/01/2018	04/01/2019	EACH OCCURRENCE \$20,000,000
C		Y	Y	1000585014181	04/01/2018	04/01/2019	AGGREGATE \$20,000,000
A	WORKERS COMPENSATION AND EMPLOYERS' LIABILITY ANY PROPRIETOR/PARTNER/EXECUTIVE OFFICER/MEMBER EXCLUDED? <input checked="" type="checkbox"/> Y/N (Mandatory in NH) If yes, describe under DESCRIPTION OF OPERATIONS below:		Y	WC203610912	04/01/2018	04/01/2019	<input checked="" type="checkbox"/> PER STATUTE <input type="checkbox"/> OTH-ER E.L. EACH ACCIDENT \$1,000,000 E.L. DISEASE - EA EMPLOYEE \$1,000,000 E.L. DISEASE - POLICY LIMIT \$1,000,000
D	Rented Equipment			UM00024961MA18A	04/01/2018	04/01/2019	2,000,000
E	Pollution Liab			PCADB50038590418	04/01/2018	04/01/2019	5,000,000
E	Professional Liab			PCADB50038590418	04/01/2018	04/01/2019	5,000,000

DESCRIPTION OF OPERATIONS / LOCATIONS / VEHICLES (ACORD 101, Additional Remarks Schedule, may be attached if more space is required)

Certificate holder is additional insured as respects General Liability, Automobile Liability and Excess/Umbrella Liability only if required by written contract, and subject to the terms, conditions and exclusions as specified in the policy.

Coverage is primary as respects to General Liability Automobile Liability and non-contributory as subject (See Attached Descriptions)

CERTIFICATE HOLDER

CANCELLATION

FOR INFORMATION ONLY

SHOULD ANY OF THE ABOVE DESCRIBED POLICIES BE CANCELLED BEFORE THE EXPIRATION DATE THEREOF, NOTICE WILL BE DELIVERED IN ACCORDANCE WITH THE POLICY PROVISIONS.

AUTHORIZED REPRESENTATIVE



DESCRIPTIONS (Continued from Page 1)

to the terms, conditions and exclusions of your policy.

Waiver of subrogation applies in favor of certificate holder as respects General Liability, Automobile Liability and Workers Compensation only if required by written contract, and subject to the terms, conditions and exclusions as specified in the policy.

It is agreed by endorsement to the General Liability, Automobile Liability and Workers Compensation policies that these policies shall not be cancelled by the insurance carrier without first giving thirty (30) days prior written notice except for nonpayment of premium or if the first named insured elects to non renew.

Blanket Loss Payee applies for Rented and Leased Equipment.

Rented and Leased Equipment deductible:

\$2,500 standard deductible.

2% subject to \$10K minimum deductible applies to all rented cranes, directional boring equipment and items valued over \$750,000

See Attached Builders Risk Policy Information

BUILDER'S RISK COVERAGE

NAMED INSURED: Wharton-Smith, Inc.
COMPANY: XL Specialty Insurance Company
NAIC #37885 AM Best Rating: A (Excellent), XV (\$2 Billion or greater)
POLICY TERM: 4/1/2018-4/1/2019
POLICY NUMBER: UM00024960MA18A

COVERED PROPERTY AND PREMISES DESCRIPTION

New construction and remodeling of waste water treatment plans; new construction and non-structural renovations of commercial buildings at various premises within the state of Georgia, Florida, North Carolina, South Carolina, Virginia, Mississippi, Alabama, Louisiana, Texas and Tennessee

SUMMARY

COVERAGE	LIMIT OF INSURANCE
Covered Property at Premises Described Above – Consisting of Frame or Joisted Masonry Construction	\$2,500,000
Covered Property at Premises Described Above – Consisting of Non-Combustible, Masonry Non-Combustible, Semi Fire-Resistive and Fire-Resistive Construction (Including Water Treatment Plants Except on Islands)	\$50,000,000
Covered Property at Premises Described Above – On Islands (Water Treatment Plant Projects Only)	\$5,000,000
Soft Costs	\$1,000,000

DEDUCTIBLE OR WAITING PERIOD

COVERAGE	DEDUCTIBLE OR WAITING PERIOD
All Coverages Unless Otherwise Specified Below	\$2,500
Named Storm – On Islands	\$1,000,000
Named Storm – Water Treatment Plant Projects Only	2%, Subject to \$2,500 Minimum
Named Storm – Frame, Joisted Masonry or Non-Combustible Construction	5%, Subject to \$2,500 Minimum
Named Storm – Masonry Non-Combustible, Semi Fire-Resistive or Fire-Resistive Construction	2%, Subject to \$2,500 Minimum
Flood – Zones C or X (Unshaded)	\$25,000
Flood – Zone B or Shaded X	\$50,000
Flood – All Other Zones and Water Treatment Projects on Islands	\$500,000

SUBLIMITS

COVERAGE	LIMIT OF INSURANCE
Flood – Per Occurrence – Zone C or Unshaded X	\$50,000,000
Flood – Per Occurrence – Zones B & Shaded X	\$15,000,000
Flood – Per Occurrence – All Other Zones	\$1,000,000
Flood – Per Occurrence – Islands (Waste Water Treatment Plants Only)	\$500,00
Flood Annual Aggregate	\$50,000,000
Earth Movement and Volcanic Eruption – Pacific Northwest Seismic Area, High Hazard Seismic Zones	\$1,000,000
Earth Movement and Volcanic Eruption – New Madrid Seismic Area	\$10,000,000
Earth Movement and Volcanic Eruption – Per Occurrence	\$50,000,000
Earth Movement and Volcanic Eruption – Annual Aggregate	\$50,000,000
Windstorm or Hail – Premises Located on Islands	\$2,500,000

COVERAGE TERMS

- ◆ Maximum Limit of Insurance: \$50,000,000
- ◆ Valuation Clause: Replacement Cost
- ◆ Co-Insurance: 0%
- ◆ Additional Coverages – Testing: Electrical, Mechanical, Pneumatic and Hydrostatic
- ◆ Equipment Breakdown Endorsement
- ◆ Loss of Use Coverage Endorsement
- ◆ Permission to Occupy Endorsement
- ◆ Additional Coverage Limit for Valuable Papers - \$250,000

ADDITIONAL COVERAGE	LIMIT OF INSURANCE
Contract Penalty	\$250,000
Debris Removal	\$500,000 / 25%
Extra and Expediting Expenses	\$50,000
Fire Department Service Charge	\$25,000
Fire Protection Systems	\$25,000
Increase in Construction Costs	\$200,000 / 10%
Landscaping and Signs	\$100,000
Limited Coverage for "Fungi", Wet Rot and Dry Rot	\$25,000
Loss Adjustment Expenses	\$5,000
Demolition Cost and Increased Cost of Construction	\$500,000
Pollutant Cleanup and Removal	\$25,000
Preservation of Property	Covered
Property in the Open	\$25,000
Property that Supports your Business	\$50,000
Reimbursement for Returning Stolen Property	\$10,000
Reward Coverage	\$5,000
Site Preparation	Covered
Sewer and Drain Backup	Covered
Sinkhole Collapse	Covered
Temporary Premises	\$1,000,000
Temporary Structures	\$25,000
Transit	\$1,000,000
Unintentional Errors and Omissions	\$25,000
Virus, Harmful Code or Similar Instruction	\$10,000
Voluntary Parting	\$25,000

This page has been left blank intentionally.

 RICK SCOTT, GOVERNOR

JONATHAN ZACHEM, SECRETARY



STATE OF FLORIDA
DEPARTMENT OF BUSINESS AND PROFESSIONAL REGULATION

CONSTRUCTION INDUSTRY LICENSING BOARD

THE GENERAL CONTRACTOR HEREIN IS CERTIFIED UNDER THE
PROVISIONS OF CHAPTER 489, FLORIDA STATUTES

SMITH, TIMOTHY SCOT

WHARTON-SMITH INC
PO BOX 471028
LAKE MONROE FL 32747

LICENSE NUMBER: CGC1511243

EXPIRATION DATE: AUGUST 31, 2020

Always verify licenses online at MyFloridaLicense.com



Do not alter this document in any form.

This is your license. It is unlawful for anyone other than the licensee to use this document.

 RICK SCOTT, GOVERNOR

JONATHAN ZACHEM, SECRETARY



STATE OF FLORIDA
DEPARTMENT OF BUSINESS AND PROFESSIONAL REGULATION

CONSTRUCTION INDUSTRY LICENSING BOARD

THE GENERAL CONTRACTOR HEREIN IS CERTIFIED UNDER THE
PROVISIONS OF CHAPTER 489, FLORIDA STATUTES

HEWITT, PATRICK JOHN

WHARTON-SMITH, INC.
750 MONROE ROAD
SANFORD FL 32771

LICENSE NUMBER: CGC055975

EXPIRATION DATE: AUGUST 31, 2020

Always verify licenses online at MyFloridaLicense.com



Do not alter this document in any form.

This is your license. It is unlawful for anyone other than the licensee to use this document.



 RICK SCOTT, GOVERNOR

JONATHAN ZACHEM, SECRETARY



STATE OF FLORIDA
DEPARTMENT OF BUSINESS AND PROFESSIONAL REGULATION
CONSTRUCTION INDUSTRY LICENSING BOARD

THE UNDERGROUND UTILITY & EXCAVATION CO HEREIN IS CERTIFIED UNDER THE
PROVISIONS OF CHAPTER 489, FLORIDA STATUTES

DAVOLI, RONALD FRANK
WHARTON-SMITH INC
750 COUNTY RD 15
PO BOX 471028
LAKE MONROE FL 32747-1028

LICENSE NUMBER: CUC056506
EXPIRATION DATE: AUGUST 31, 2020
Always verify licenses online at MyFloridaLicense.com



Do not alter this document in any form.
This is your license. It is unlawful for anyone other than the licensee to use this document.

 RICK SCOTT, GOVERNOR

JONATHAN ZACHEM, SECRETARY



STATE OF FLORIDA
DEPARTMENT OF BUSINESS AND PROFESSIONAL REGULATION
CONSTRUCTION INDUSTRY LICENSING BOARD

THE MECHANICAL CONTRACTOR HEREIN IS CERTIFIED UNDER THE
PROVISIONS OF CHAPTER 489, FLORIDA STATUTES

HEWITT, PATRICK JOHN
WHARTON-SMITH INC
2606 CHIPPEWA TRAIL
MAITLAND FL 32751

LICENSE NUMBER: CMC1249482
EXPIRATION DATE: AUGUST 31, 2020
Always verify licenses online at MyFloridaLicense.com



Do not alter this document in any form.
This is your license. It is unlawful for anyone other than the licensee to use this document.





RICK SCOTT, GOVERNOR

JONATHAN ZACHEM, SECRETARY



STATE OF FLORIDA
DEPARTMENT OF BUSINESS AND PROFESSIONAL REGULATION
CONSTRUCTION INDUSTRY LICENSING BOARD

THE PLUMBING CONTRACTOR HEREIN IS CERTIFIED UNDER THE
PROVISIONS OF CHAPTER 489, FLORIDA STATUTES

SMITH, TIMOTHY SCOT
WHARTON-SMITH, INC
750 MONROE ROAD
SANFORD FL 32771

LICENSE NUMBER: CFC1427566
EXPIRATION DATE: AUGUST 31, 2020
Always verify licenses online at MyFloridaLicense.com



Do not alter this document in any form.
This is your license. It is unlawful for anyone other than the licensee to use this document.



RICK SCOTT, GOVERNOR

JONATHAN ZACHEM, SECRETARY



STATE OF FLORIDA
DEPARTMENT OF BUSINESS AND PROFESSIONAL REGULATION
CONSTRUCTION INDUSTRY LICENSING BOARD

THE POLLUTANT STORAGE SYSTEMS CONTRACTOR HEREIN IS CERTIFIED UNDER THE
PROVISIONS OF CHAPTER 489, FLORIDA STATUTES

SMITH, TIMOTHY SCOT
WHARTON-SMITH, INC
750 MONROE ROAD
SANFORD FL 32771

LICENSE NUMBER: PCC1256921
EXPIRATION DATE: AUGUST 31, 2020
Always verify licenses online at MyFloridaLicense.com



Do not alter this document in any form.
This is your license. It is unlawful for anyone other than the licensee to use this document.



State of Florida

Board of Professional Engineers

Attests that
Wharton-Smith, Inc.



Is authorized under the provisions of Section 471.023, Florida Statutes, to offer engineering services to the public through a Professional Engineer, duly licensed under Chapter 471, Florida Statutes.

Expiration: 2/28/2019

Audit No: 228201903959 R

CA Lic. No:

1813



SEMINOLE COUNTY BUSINESS TAX RECEIPT

JOEL M. GREENBERG, SEMINOLE COUNTY TAX COLLECTOR

PO BOX 630 | SANFORD, FL 32772 | 407-665-1000

WWW.SEMINOLECOUNTY.TAX

VALID THROUGH 09/30/19

WHARTON-SMITH INC
750 MONROE RD
SANFORD, FL 32771

Account #:022717

GEORGE E SMITH (OFFICER)
TIMOTHY SMITH (OFFICER)

REGULATED
License # - CGC1511243 / CFC1427566
Qualifier- TIMOTHY S SMITH

Receipt #: WEB#2018070916752

Amount Paid: \$ 45.00

Date Paid: 07/09/2018



State of Florida

Department of State

I certify from the records of this office that WHARTON-SMITH, INC. is a corporation organized under the laws of the State of Florida, filed on April 3, 1984, effective April 2, 1984.

The document number of this corporation is G94383.

I further certify that said corporation has paid all fees due this office through December 31, 2018, that its most recent annual report/uniform business report was filed on January 2, 2018, and that its status is active.

I further certify that said corporation has not filed Articles of Dissolution.

*Given under my hand and the
Great Seal of the State of Florida
at Tallahassee, the Capital, this
the Second day of January, 2018*



Ken Reitzner
Secretary of State

Tracking Number: CC2671502072

To authenticate this certificate, visit the following site, enter this number, and then follow the instructions displayed.

<https://services.sunbiz.org/Filings/CertificateOfStatus/CertificateAuthentication>





ANNE M. GANNON
CONSTITUTIONAL TAX COLLECTOR
Serving Palm Beach County

P.O. Box 3353, West Palm Beach, FL 33402-3353
 www.pbctax.com Tel: (561) 355-2264

****LOCATED AT****

125 West INDIANTOWN RD Ste 201
 JUPITER, FL 33458

Serving you.

TYPE OF BUSINESS	OWNER	CERTIFICATION #	RECEIPT #/DATE PAID	AMT PAID	BILL #
23-0051 GENERAL CONTRACTOR	SMITH TIMOTHY SCOT	CGC1511243	818 491522 - 07/09/18	\$27.50	840150228

This document is valid only when received by the Tax Collector's Office.

B3 - 331

WHARTON SMITH INC
 WHARTON SMITH INC
 PO BOX 471028
 SANFORD, FL 32771

STATE OF FLORIDA
PALM BEACH COUNTY
2018/2019 LOCAL BUSINESS TAX RECEIPT

LBTR Number: 201364913
EXPIRES: SEPTEMBER 30, 2019

This receipt grants the privilege of engaging in or managing any business profession or occupation within its jurisdiction and MUST be conspicuously displayed at the place of business and in such a manner as to be open to the view of the public.



City of Miramar

Business Tax Receipt

Issue Date: 10/01/2018

Expiration Date: 09/30/2019

Business ID

18000462

WHARTON-SMITH, INC
 RONALD DAVOLI
 P O BOX 471028
 LAKE MONROE, FL 32747

(954) 602-3040 or (954) 602-3061 Phone
 (954) 602-3470 or (954) 602-4498 Fax
 businesstax@miramarfl.gov

BUSINESS TAX RECEIPT

This is to certify that the person or firm named herein has paid into my hands minimum payment of tax as set out herein for the use and benefit of the City aforesaid, and is licensed to engage in the business of:

CONTRACTOR	CONTRACTOR	27699
BUS/RET/WH	PER SQ FT	27700
FIRE ALARM	FIRE ALARM	27701
FIXED FIRE	FIXED FIRE	27702

Home-Based Restrictions Only

Mail & Phone Only
 No Employees at Home
 No Work on Premises
 No Clients at Home
 No Deliveries to Home
 Office Only

Cottage-Based Restrictions

Cottage food businesses are allowed in accordance with Florida Statute 500.80, except that the home shall not be used for retail. Please see regulations title 21 part 101.
 Only one employee allowed which includes family members residing at the home. No commercial vehicles parked overnight on the premises.

Business Location:

10350 USA TODAY WAY
 MIRAMAR FL 33025



**2018 / 2019
MONROE COUNTY BUSINESS TAX RECEIPT
EXPIRES SEPTEMBER 30, 2019**

Business Name: WHARTON SMITH INC

RECEIPT# 30140-104363

Owner Name: RONALD F DAVOLI

Business Location: MO CTY
KEY WEST, FL 33040

Mailing Address:

PO BOX 471028
LAKE MONROE, FL 32747Business Phone: 407-321-8410
Business Type: CONTRACTOR (GENERAL CONTRACTOR &
PLUMBING (CFC1427566)

Employees 10

STATE LICENSE: CGC032669 & CFC1427566

Tax Amount	Transfer Fee	Sub-Total	Penalty	Prior Years	Collection Cost	Total Paid
25.00	0.00	25.00	0.00	0.00	0.00	25.00

Paid 000-17-00022599 07/05/2018 25.00

THIS BECOMES A TAX RECEIPT
WHEN VALIDATED**Danise D. Henriquez, CFC, Tax Collector**
PO Box 1129, Key West, FL 33041THIS IS ONLY A TAX.
YOU MUST MEET ALL
COUNTY AND/OR
MUNICIPALITY PLANNING
AND ZONING REQUIREMENTS.

WELLINGTON LOCAL PREFERENCE

APPLICATION TO BE CONSIDERED A LOCAL BUSINESS IN ACCORDANCE WITH VILLAGE OF WELLINGTON FLORIDA'S LOCAL PREFERENCE POLICY

Wellington gives preference to local businesses in certain purchasing situations as set forth in Chapter 9 of Wellington's Purchasing and Procurement Manual. In order to be considered a local business, entitled to be given preference, the business must make application with Wellington and meet one of the following criteria as such is more fully set forth in Chapter 9, of Wellington's Purchasing and Procurement Manual:

Chapter 9, LOCAL PREFERENCE

Western Communities Local Business - For the purpose of determining a "Western Communities local business" a vendor must have a principal permanent business location and headquarters within Wellington of Wellington, Florida or west of the Florida Turnpike to the Palm Beach County western boundary line. This applies to all entity formations, including, but not limited to, limited liability companies, partnerships, limited partnerships and the like or sole proprietors. Further, the entity or sole proprietor must provide that it, he or she has been domiciled and headquartered in the jurisdictional boundaries of the Western Communities for at least six months prior to the solicitation. Post Office boxes will not be considered a permanent business location within the Western Communities. Home business offices shall be considered as a business location if it otherwise meets the requirements herein. In order to be eligible for such local preference the vendor shall have a local business tax receipt pursuant to the County's and/or municipalities' Code of Ordinances, having jurisdiction over the location of the business, unless otherwise exempt therefrom. Further, the vendor must be properly licensed and authorized by law to provide the goods, services or professional services to the extent applicable and the location of the business must be properly zoned in order for the vendor to conduct its business.

Palm Beach County local business - For the purpose of determining a "Palm Beach County local business" a vendor must have a principal permanent business location and headquarters within Palm Beach County, Florida. This applies to all entity formations, including, but not limited to, limited liability companies, partnerships, limited partnerships and the like or sole proprietors. Further, the entity or sole proprietor must provide that it, he or she has been headquartered and domiciled in the jurisdictional boundaries of Palm Beach County, Florida for at least six months prior to the solicitation. Post Office boxes will not be considered a permanent business location within Palm Beach County, Florida. Home business offices shall be considered as a business location if it otherwise meets the requirements herein. In order to be eligible for such local preference the vendor shall have a local business tax receipt pursuant to the Palm Beach County Code of Ordinances as amended from time to time, unless otherwise exempt there from. Further, the vendor must be properly licensed and authorized by law to provide the goods, services or professional services to the extent applicable and the location of the business must be properly zoned in order for the vendor to conduct its business.

Subcontractor utilization - In competitive bid situations, a business may also qualify as either a Palm Beach County or Western Community local business if they are utilizing subcontractors to perform the work or materialmen to supply the job and more than fifty (50%) percent of their proposed bid price will be paid to subcontractors and/or materialmen who qualify, under the above standards, as Palm Beach County and/or Western Community local businesses.

Please check the box below indicating which preference category your business is applying for:

☐ Western Communities Local Business

☒ Palm Beach County Local Business

☐ Subcontractor Utilization

1. The name of the business is: Wharton-Smith, Inc.
2. The address of the business is: 125 W. Indiantown Road, Ste 201, Jupiter, FL 33458
3. How long has the business been located at its current address: Since 02/07/2014
4. If the business has relocated within the last six months, please provide the answers to questions 1-3 for the previous location:
N/A
5. The previous name of the business is: N/A
6. The previous address of the business is: 3547 SW Corporate Parkway,
Palm City, FL 34990
7. How long was this business at the previous location: Since 1996

8. If the business is attempting to qualify under the subcontractor utilization provision, please provide a breakdown of the subcontractors who would qualify for either the Palm Beach County or Western Community, business classification, the requisite information, provide their responses to the above 1 - 7 questions and for each of the subcontractors, indicate the amount that they are proposed to be compensated at under the bid price.

9. The business as a local business tax receipt from: (1) Palm Beach County ☒ (2) the following municipality: _____ (3) located in unincorporated Palm Beach County: ☐

10. Please provide a copy of Local Business Tax Receipts from Palm Beach County and the applicable municipality are attached.

11. Please provide a Certificate of Good Standing indicating the formation or domestication of the entity in and for the State of Florida is attached.

12. Please provide copies of licenses if applicable from the State of Florida authorizing the business to provide the good services or professional services contemplated in the bid documents.

By signing below, I hereby certify that under penalty of perjury I believe my business qualifies as a Palm Beach County, Western Community or subcontractor utilization business in accordance with Wellington's Local Preference Policy and that I have submitted current and accurate information and documents relating to my qualifications. I further acknowledge and agree that any fraudulent or duplicitous information submitted in furtherance of this application will be grounds for disqualification from bidding on this project and doing business with Wellington in the future.

Applicants Federal Tax ID Number - 59-2392802 Applicants Business Address 125 W. Indiantown Road, Ste 201
Jupiter, FL 33458

Signature of Authorized Representative of Corporation, Partnership, or other business entity:

[Signature]

Print Name: Ronald F. Davoli

Title: President/CEO

Date: 02/06/2019

CITY OF: Sanford


COUNTY OF: Seminole

SUBSCRIBED AND SWORN TO (or affirmed) before me on this 6 day of February, 2019, by Ronald F. Davoli. He/She is personally known to me or has presented

personally known as identification.

[Signature]
(Signature of Notary)

Dawn K. Bragg
(Print or Stamp Name of Notary)



Notary Public Florida
(State)

Notary Seal

Signature of Individual if Sole Proprietor:

N/A

Print Name: N/A

Date: N/A

CITY OF: N/A

COUNTY OF: N/A

SUBSCRIBED AND SWORN TO (or affirmed) before me on this ____ day of N/A, 201__, by N/A. He/She is personally known to me or has presented

N/A as identification.

N/A
(Signature of Notary)

N/A
(Print or Stamp Name of Notary)

Notary Public N/A
(State)

Notary Seal

CONFLICT OF INTEREST STATEMENT

This Proposal/Agreement (whichever is applicable) is subject to the conflict of interest provisions of the policies and Code of Ordinances of WELLINGTON, the Palm Beach County Code of Ethics, and the Florida Statutes. During the term of this Agreement and any renewals or extensions thereof, the VENDOR shall disclose to WELLINGTON any possible conflicts of interests. The VENDOR's duty to disclose is of a continuing nature and any conflict of interest shall be immediately brought to the attention of WELLINGTON. The terms below shall be defined in accordance with the policies and Code of Ordinances of WELLINGTON, the Palm Beach County Code of Ethics, and Ch. 112, Part III, Florida Statutes.

CHECK ALL THAT APPLY.

- ☒ To the best of our knowledge, the undersigned business has no potential conflict of interest for this Agreement due to any other clients, contracts, or property interests.
- ☒ To the best of our knowledge, the undersigned business has no employment or other contractual relationship with any WELLINGTON employee, elected official or appointed official.
- ☒ To the best of our knowledge, the undersigned business has no officer, director, partner or proprietor that is a WELLINGTON purchasing agent, other employee, elected official or appointed official. The term "purchasing agent", "elected official" or "appointed official", as used in this paragraph, shall include the respective individual's spouse or child, as defined in Ch. 112, Part III, Florida Statutes.
- ☒ To the best of our knowledge, no WELLINGTON employee, elected official or appointed official has a material or ownership interest (5% ownership) in our business. The term "employee", "elected official" and "appointed official", as used in this paragraph, shall include such respective individual's relatives and household members as described and defined in the Palm Beach County Code of Ethics.
- ☒ To the best of our knowledge, the undersigned business has no current clients that are presently subject to the jurisdiction of WELLINGTON's Planning, Zoning and Building Department.

CONFLICT:

☐ The undersigned business, by attachment to this form, submits information which may be a potential conflict of interest due to any of the above listed reasons or otherwise.

THE UNDERSIGNED UNDERSTANDS AND AGREES THAT THE FAILURE TO CHECK THE APPROPRIATE BLOCKS ABOVE OR TO ATTACH THE DOCUMENTATION OF ANY POSSIBLE CONFLICTS OF INTEREST MAY RESULT IN DISQUALIFICATION OF YOUR BID/PROPOSAL OR IN THE IMMEDIATE CANCELLATION OF YOUR AGREEMENT, WHICHEVER IS APPLICABLE.

Wharton-Smith, Inc.

COMPANY NAME



AUTHORIZED SIGNATURE

Ronald F. Davoli

NAME (PRINT OR TYPE)

President/CEO

TITLE

NON-COLLUSION AFFIDAVIT

State of Florida

County of Seminole

Being duly sworn deposes and says:

That he/she is an officer of the parties making the forgoing bid submittal, that such bid submittal is genuine and not collusive or sham, that said Bidder has not colluded, conspired, connived or agreed, directly or indirectly with any bidder or person, to put in a sham bid or to retrain from bidding and has not in any manner, directly, or indirectly, sought by agreement of collusion or communication or conference with any person, to fix the price of affiant or any other bidder, or to fix any overhead, profit of cost element of said price, or that of any other bidder, or to secure any advantage against the authority, of any person interested in the proposed contract and that all statements in said bid is true.

Wharton-Smith, Inc.

Name of Bidder

Ronald F. Davoli, President/CEO

Print name of designated signatory



Signature

Ronald F. Davoli, President/CEO

Title

On this 6 day of February, 2019, before me appeared Ronald F. Davoli personally known to me to be the person described in and who executed this personally known and acknowledged that (she/he) signed the name freely and voluntarily for the uses and purposes therein described.

In witness thereof, I have hereunto set my hand and affixed seal the day and year last written above.



Signature

Notary Public in and for the State of Florida

(Affix Seal Here)




Devon A. Lewis, Corporate Secretary

(Name Printed)

Residing at Seminole Co, Florida

My commission expires October 24, 2022



REFERENCES AND PRIOR EXPERIENCE
(Form to be used by Prime Contractor, Electrical and Instrumentation Subcontractors)

Bidder Company Name: Wharton-Smith, Inc.

PROJECT NAME: Cudjoe Key AWRP

Owner/Reference Name: Florida Keys Aqueduct Authority

Owner/Reference Contact: Stephanie Bruno Construction Contracts Administrator
Name Title

305.295.2140 sbruno@fkaa.com
Phone Email

Project Location: Cudjoe Key, FL

Project Description: Please see attached Project Description.

Was the Bidder Prime Contractor or Subcontractor? Prime

List project scope similarities: Please see attached Project Description.

Project Cost:	Initial Contract Value	<u>\$ 21,872,000</u>
	Change Orders	<u>\$ 4,402,430</u>
	Final Contract Price	<u>\$ 26,274,430</u>

Explain Reason(s) for Change Orders: Owner added/changed scope

Project Timeline:	Start Date	<u>01/24/2013</u>
	Contract Time Extension	<u>yes</u>
	Completion Date	<u>04/15/2015</u>

Explain Reason(s) for Time Extension: Time extension given for owner added/changed scope

NOTE: Include additional pages with the same format to list other projects as proof of prior experience. List a minimum of five (5) similar projects for prime contractor.

FAILURE TO COMPLETE THIS FORM MAY RESULT IN THE BID BEING DECLARED NON-RESPONSIVE

REFERENCES AND PRIOR EXPERIENCE
(Form to be used by Prime Contractor, Electrical and Instrumentation Subcontractors)

Bidder Company Name: Wharton-Smith, Inc.

PROJECT NAME: St. Lucie West WWTP Expansion

Owner/Reference Name: St. Lucie West Services District

Owner/Reference Contact: Dennis Pickle, District Manager

Name

Title

772.340.0220 ext 103

dpickle@slwsd.org

Phone

Email

Project Location: Port St. Lucie, FL

Project Description: Please see attached Project Description.

Was the Bidder Prime Contractor or Subcontractor? Prime

List project scope similarities: Please see attached Project Description.

Project Cost:	Initial Contract Value	\$ <u>10,830,500</u>
	Change Orders	\$ <u>(386,516)</u>
	Final Contract Price	\$ <u>10,443,984</u>

Explain Reason(s) for Change Orders: Owner added/changed scope

Project Timeline: Start Date 03/10/2014

Contract Time Extension Yes

Completion Date 08/31/2015

Explain Reason(s) for Time Extension: Time added for owner added/changed scope

NOTE: Include additional pages with the same format to list other projects as proof of prior experience. List a minimum of five (5) similar projects for prime contractor.

FAILURE TO COMPLETE THIS FORM MAY RESULT IN THE BID BEING DECLARED NON-RESPONSIVE

REFERENCES AND PRIOR EXPERIENCE
(Form to be used by Prime Contractor, Electrical and Instrumentation Subcontractors)

Bidder Company Name: Wharton-Smith, Inc.

PROJECT NAME: Altamonte Springs RWRF Headworks Improvements

Owner/Reference Name: City of Altamonte Springs, FL

Owner/Reference Contact: Karen McCullen, Sr. Engineering Project Manager
Name Title

407.571.8335 kmccullen@altamonte.org
Phone Email

Project Location: Altamonte Springs, FL

Project Description: Please see attached Project Description.

Was the Bidder Prime Contractor or Subcontractor? Prime

List project scope similarities: Please see attached Project Description.

Project Cost:	Initial Contract Value	<u>\$ 10,378,014</u>
	Change Orders	<u>\$ (2,325,593)</u>
	Final Contract Price	<u>\$ 8,052,421</u>

Explain Reason(s) for Change Orders: Value Engineering and unforeseen field conditions and to perform additional work associated with the project.

Project Timeline:	Start Date	<u>05/13/2016</u>
	Contract Time Extension	<u>yes</u>
	Completion Date	<u>03/23/2018</u>

Explain Reason(s) for Time Extension: Unforeseen field conditions and to perform and additional work associated with the project.

NOTE: Include additional pages with the same format to list other projects as proof of prior experience. List a minimum of five (5) similar projects for prime contractor.

FAILURE TO COMPLETE THIS FORM MAY RESULT IN THE BID BEING DECLARED NON-RESPONSIVE

REFERENCES AND PRIOR EXPERIENCE
(Form to be used by Prime Contractor, Electrical and Instrumentation Subcontractors)

Bidder Company Name: Wharton-Smith, Inc.

PROJECT NAME: Northeast Regional Wastewater Treatment Facility Expansion

Owner/Reference Name: Polk County

Owner/Reference Contact: Mark Addison, P.E., CIP Project Manager

Name

Title

863.298.4214

mark.addison@polk-county.net

Phone

Email

Project Location: Polk County, FL

Project Description: Please see attached Project Description.

Was the Bidder Prime Contractor or Subcontractor? Prime

List project scope similarities: Please see attached Project Description.

Project Cost: Initial Contract Value \$ 34,915,082

Change Orders \$ (2,903,116)

Final Contract Price \$ 32,244,965

Explain Reason(s) for Change Orders: Value engineering

Project Timeline: Start Date February 19, 2009

Contract Time Extension yes

Completion Date November 28, 2013

Explain Reason(s) for Time Extension: Owner added scope.

NOTE: Include additional pages with the same format to list other projects as proof of prior experience. List a minimum of five (5) similar projects for prime contractor.

FAILURE TO COMPLETE THIS FORM MAY RESULT IN THE BID BEING DECLARED NON-RESPONSIVE

REFERENCES AND PRIOR EXPERIENCE
(Form to be used by Prime Contractor, Electrical and Instrumentation Subcontractors)

Bidder Company Name: Wharton-Smith, Inc.

PROJECT NAME: Cocoa Beach WRF Upgrades and Process Conversion

Owner/Reference Name: City of Cocoa Beach

Owner/Reference Contact: Jack Shelton, Director of Water Reclamation Dept.

<u>321.868.3243</u>	<u>jshelton@cityofcocoabeach.com</u>
Phone	Email

Project Location: Cocoa Beach, FL

Project Description: Please see attached Project Description

Was the Bidder Prime Contractor or Subcontractor? Prime

List project scope similarities: Please see attached Project Description

Project Cost:	Initial Contract Value	\$ <u>15,142,000</u>
	Change Orders	\$ <u>277,581</u>
	Final Contract Price	\$ <u>15,419,581</u>

Explain Reason(s) for Change Orders: Additional owner added scope

Project Timeline:	Start Date	<u>October 17, 2011</u>
	Contract Time Extension	<u>Yes</u>
	Completion Date	<u>March 1, 2013</u>

Explain Reason(s) for Time Extension: Additional time given for owner added scope.

NOTE: Include additional pages with the same format to list other projects as proof of prior experience. List a minimum of five (5) similar projects for prime contractor.

FAILURE TO COMPLETE THIS FORM MAY RESULT IN THE BID BEING DECLARED NON-RESPONSIVE

REFERENCES AND PRIOR EXPERIENCE
(Form to be used by Prime Contractor, Electrical and Instrumentation Subcontractors)

Bidder Company Name: Wharton-Smith, Inc.

PROJECT NAME: Southwest Regional WRF Biological Nutrient Removal

Owner/Reference Name: Volusia County

Owner/Reference Contact: Michael Ulrich, Director

Name	Title
<u>386.736.5935</u>	<u>mulrich@volusia.org</u>
Phone	Email

Project Location: Debary, FL

Project Description: Please see attached Project Description.

Was the Bidder Prime Contractor or Subcontractor? Prime

List project scope similarities: Please see attached Project Description.

Project Cost:	Initial Contract Value	\$ <u>12,129,500</u>
	Change Orders	\$ <u>0</u>
	Final Contract Price	\$ <u>12,129,500</u>

Explain Reason(s) for Change Orders: N/A

Project Timeline:	Start Date	<u>05/23/2016</u>
	Contract Time Extension	<u>Yes</u>
	Completion Date	<u>01/12/2018</u>

Explain Reason(s) for Time Extension: Time extension given due to Hurricane Irma

NOTE: Include additional pages with the same format to list other projects as proof of prior experience. List a minimum of five (5) similar projects for prime contractor.

FAILURE TO COMPLETE THIS FORM MAY RESULT IN THE BID BEING DECLARED NON-RESPONSIVE



PROJECT DESCRIPTIONS REFERENCES AND PRIOR EXPERIENCE

Cudjoe Key Advanced Water Reclamation Facility

Project Description: Construction of new offsite influent 16" HDPE force main and 6" HDPE water transmission main to the site. Initial site preparation including removal of the existing landfill liner, tire chips and ash. Construction of new offsite duct bank for underground electric and fiber optic to the site. Construction of a new 0.94MGD Advanced Water Reclamation Facility. The new WWTP includes the following: A cast-in-place Operations Building (7,500 SF), which houses the administrative and personnel areas, SCADA process control room, electrical room, laboratory, offices, bathrooms, storage garage, and chemical feed & storage; Influent Screening Facility; Solids Processing Facility (7,000 SF), two flow equalization basins; two 5-stage biological nutrient removal treatment trains each including anaerobic, 1st anoxic, aeration, 2nd anoxic and reaeration basins; two secondary clarifiers; two cloth disk tertiary filters; chlorine contact basin including two serpentine channels and plant effluent reuse pumping facilities; RAS and WAS pumping stations; methanol storage facility; four shallow injection wells; standby generator power; blowers; centrifuge; air piping; and sitework including paving.

St. Lucie West WWTP Expansion

Project Description: Installation of new headworks including mechanical screen with washer/compactor and a grit removal system along with the relocation and modification of the existing odor control unit; installation of two common-wall oxidation ditches with surface aeration & submersible mixers in an anoxic zone; Modification of two existing clarifiers to replace peripheral fed units; new tertiary filter system utilizing cloth media disks in existing concrete tank; modification to existing digesters; screw press based sludge dewatering system; synthetic pond liner; electrical; I&C, misc. piping.

Altamonte Springs RWRP Headworks Improvements

Project Description: Construction of a new headworks consisting of two (2) new mechanical bar screens, and six (6) new submersible pumps; new plant influent junction box to direct flow to the headworks, new grit process building adjacent to new headworks; new headworks electrical building with six (6) VFD's for wetwell pumps; new grit processing headcell structure and grit pump; new Return Activated Sludge pump station with (4) RAS pumps; modifications to existing electrical building for RAS pump VFDs; site drainage improvements; demolition of existing infrastructure; and a complete wall restoration and new coating system to the Mixed Liquor Return trough. To construct the new junction box, and tie-in various piping components, the project required a 4-month 13.5MGD bypass of the plant's main influent line, and concurrently, a 1.5MGD bypass of the secondary influent line. Site area was 7 acres. Demolition of the existing site included removal of the existing influent screw pumps, removal of the existing effluent screw pumps, removal of the existing headworks and grit removal structure, removal of the existing primary settling tank, and various site piping. In order to demolish the headworks and grit chamber, 100CYD of grit was removed from the existing structures. Tie-ing the 48" RCP main influent line and 30" SDR35 secondary influent line to the new influent junction box required a major tie-in. Overall lift station size: 39'-10" x 18'-4" x 31'-0", in order to avoid the utilization of shoring methods, the wetwell was constructed in three lifts and each lift sunk in place. In total, approximately 300 yards were poured in the walls and tour slab, and 70 yards were poured in the tremie slab. Wellpoints were primarily used to dewater the site. Concrete total yards were 2000 with 170 tons of rebar. The special coating systems used was Tnemec 217/218, and Tnemec 434/435. There were six (6) 45HP pumps and four (4) RAS Pumps 15HP pumps installed. Equipment installed from bar screens (2) Mechanical Bar screens (13MGD each), (6) submersible pumps (45 HP each), (4) Dry-mount pumps (15HP each), (1) Grit cyclone and snail conveyor (rated for 3MGD), (1) Grit Headcell. One (1) 2-ton monorail crane for headworks pump removal was used. The I&C description is SCADA and new PLC. Electrical consisted of duct banks / MCC & gear data/ service size: (10) new VFD's, (2) new MCC's with modifications to existing electrical buildings, (5) new transformers. There was a New SCADA operated entry gate for security. Startup details and staging consisted of two phase construction; the new headworks was brought online while the second phase was under construction.

750 Monroe Road, Sanford, FL 32771 | Phone: (407) 321-8410 | Fax: (407) 330-1092

Mailing Address: P.O. Box 471028, Lake Monroe, FL 32747-1028



Startup was split between the headworks equipment in phase one, and then all other equipment in phase 2. Plant Capacity was 25.0 MGD at completion and the Plant Added Capacity was 12.5 MGD.

Northeast Regional Wastewater Treatment Facility Expansion

Project Description: Wharton Smith provided Construction Management at Risk services for a 3 MGD expansion to the existing Northeast Regional Wastewater Treatment Facility in Polk County. The project included (2) each parallel 1,750 KW, medium voltage generators (diesel); the expansion of WWTF to include a new Biological Nutrient Removal reactor; a new sludge digester tank; new blower structure; new force main piping; and on-site Lift Station. Key upgrades include replacing the headworks/screen structure, deep bed filter structure, RAS/WAS, and return pump stations. Along with these new and upgraded structures, state-of-the-art smart gear, instrumentation and remote control, provide for a very advanced and energy conscious installation for long term, efficient use. The Wharton-Smith team's initial involvement was in efforts to reduce total nitrogen (TN) and ammonia in the effluent stream. The NE facility was permitted for 6 mg/L of TN and the levels were at 12 mg/L. We installed VFD's on the oxidation ditch surface aerators and a ChemScan nutrient level monitor and control system to control the aerator VFD's. We also cut in a slide gate to provide limited recirculation in the ditch. These measures saw a reduction in TN to below 6 mg/L, averaging around 3 mg/L. The ammonia levels were reduced as well.

Cocoa Beach Water Reclamation Facility Upgrades and Process Conversion

Project Description: Wharton-Smith was the General Contractor for the Cocoa Beach WRF Upgrades & Process Conversion. The scope of work included: Mix of rehab and new. Rehabilitated two existing aeration tanks from activated sludge process to I Kruger Hybas process. Hybas tanks contained six total mixers, six recirculation pumps and twelve aeration zones. Rehabilitated two headworks to add new grit separation systems. Added a building for each aeration tank containing grit equipment and new chemical feeds (Micro-C and alum). Rehabilitated two digesters to add access platform to hold existing rotary drum thickeners and new aerator mixers. Also added new PD blower to feed air to digesters. Rehabilitated two clarifiers, by painting existing mechanisms, adding a walkway around the exterior, launderer covers and replacing one drive unit. Rehabilitated transfer pump station to increase size of the flume from CCT and five new pumps. Two submersible to the golf course and three vertical turbine to the ground storage tanks. Added parapet walls to the four ground storage tanks to catch and reuse rainwater. Added new roof and stucco to existing generator/power distribution building. Demolished existing windrow building and constructed new metal building over press equipment on one end. Added a greenhouse on the other end of the windrow building slab. Rehabilitated existing off-site lift station with new roof, stucco, pumps, piping, wet well liner, power service and distribution, control panel and paint. Rehabilitated existing on site pump station with new roof, stucco, piping, wet well liner, power service and distribution, control panel and paint. Replaced three new high service pumps and four high service pump check valves. Replaced three existing sodium hypochlorite feed skids. Added new blower/electrical distribution building. Building contained three new turbo blowers and fed new SS air piping to the hybas tanks and anoxic tank. Added new anoxic tank containing four anoxic zones with mixers and a reaeration zone with diffusers. Tank also contained two rotoshears with a compactor and five transfer pumps. Added new aluminum walkways throughout the site between tanks and control room. Replaced existing control system and panels with new SCADA system.

750 Monroe Road, Sanford, FL 32771 | Phone: (407) 321-8410 | Fax: (407) 330-1092
Mailing Address: P.O. Box 471028, Lake Monroe, FL 32747-1028

CERTIFICATION PURSUANT TO FLORIDA STATUTE § 215.4725

I, Ronald F. Davoli, President/CEO, on behalf of Wharton-Smith, Inc., certifies
Print Name Company Name

that Wharton-Smith, Inc. does not:
Company Name

1. Participate in a boycott of Israel; and
2. Is not on the Scrutinized Companies that Boycott Israel list; and
3. Is not on the Scrutinized Companies with Activities in Sudan List; and
4. Is not on the Scrutinized Companies with Activities in the Iran Petroleum Energy Sector List; and
5. Has not engaged in business operations in Cuba or Syria.


Signature

Ronald F. Davoli, President/CEO
Title

February 6, 2019
Date

Wharton-Smith, Inc.
CONSTRUCTION GROUP

CORPORATE RESOLUTION


I, the undersigned Secretary of Wharton Smith, Inc., a corporation organized and existing under the laws of the State of Florida, do hereby certify that a meeting of the Board of Directors of said corporation, duly held on November 30th, 2018 a quorum being present, the following resolution was adopted and entered upon the regular minute book of said corporation, is in accordance with the by-laws and is now in full force and effect to-wit:

The current list of qualifiers to act for the business organization in all matters connected with its contracting business has now been amended to read:

Ronald F. Davoli
George E. Smith
David V. Hayes
Timothy S. Smith
Devon A. Lewis
Patrick J. Hewitt
Kenneth E. Marcell III
Cecil D. Harris
Darin A. Crafton
Todd H. O'Donnell
Gregory L. Williams
Thomas D. Iarossi

I HEREBY certify that the foregoing is a true and exact copy of the resolution adopted by the Board of Directors of this Corporation, and that such resolution has not been amended, modified, or revoked and is still in force and effect.

Signed and sealed this 19th day of December, 2018.
(Seal of Corporation)


Devon A. Lewis, Secretary


George E. Smith, Director


Ronald F. Davoli, Director


Timothy S. Smith, Director

REFERENCES AND PRIOR EXPERIENCE
(Form to be used by Prime Contractor, Electrical and Instrumentation Subcontractors)

Bidder Company Name: C.C. Control Corp.

PROJECT NAME: City of Lake Worth RO Improvements

Owner/Reference Name: City of Lake Worth

Owner/Reference Contact: Tim Sloan WTP Superintendant
Name Title

(561) 586-1636

Phone

TSloan@LakeWorth.org

Email

Project Location: City of Lake Worth WTP

Project Description: SCADA integration of all control panels and instrumentation with newly developed SCADA screens including system loop-checks and system start-up utilizing Trihedral VTScada.

Was the Bidder Prime Contractor or Subcontractor? Subcontractor

List project scope similarities: ControlLogix PLC programming, VTScada programming

Project Cost:	Initial Contract Value	\$ <u>1,350,000.00</u>
	Change Orders	\$ <u>0.00</u>
	Final Contract Price	\$ <u>1,350,000.00</u>

Explain Reason(s) for Change Orders: N/A

Project Timeline:	Start Date	<u>12/2009</u>
	Contract Time Extension	<u>N/A</u>
	Completion Date	<u>09/2011</u>

Explain Reason(s) for Time Extension: N/A

NOTE: Include additional pages with the same format to list other projects as proof of prior experience. List a minimum of five (5) similar projects for prime contractor.

FAILURE TO COMPLETE THIS FORM MAY RESULT IN THE BID BEING DECLARED NON-RESPONSIVE

REFERENCES AND PRIOR EXPERIENCE
(Form to be used by Prime Contractor, Electrical and Instrumentation Subcontractors)

Bidder Company Name: C.C. Control Corp.

PROJECT NAME: City of North Lauderdale WTP Improvements

Owner/Reference Name: City of North Lauderdale

Owner/Reference Contact:	<u>George Krawczyk</u>	<u>Assistant Utilities Director</u>
	Name	Title
	<u>(954) 724-7070</u>	<u>GKrawczyk@nlauderdale.org</u>
	Phone	Email

Project Location: City of North Lauderdale WTP

Project Description: SCADA integration of all control panels and instrumentation with newly developed SCADA screens including system loop-checks and system start-up utilizing Trihedral VTScada.

Was the Bidder Prime Contractor or Subcontractor? Subcontractor

List project scope similarities: ControlLogix PLC programming, VTScada programming

Project Cost:	Initial Contract Value	\$ <u>690,000.00</u>
	Change Orders	\$ <u>0.00</u>
	Final Contract Price	\$ <u>690,000.00</u>

Explain Reason(s) for Change Orders: N/A

Project Timeline:	Start Date	<u>06/2010</u>
	Contract Time Extension	<u>N/A</u>
	Completion Date	<u>04/2012</u>

Explain Reason(s) for Time Extension: N/A

NOTE: Include additional pages with the same format to list other projects as proof of prior experience. List a minimum of five (5) similar projects for prime contractor.

FAILURE TO COMPLETE THIS FORM MAY RESULT IN THE BID BEING DECLARED NON-RESPONSIVE

REFERENCES AND PRIOR EXPERIENCE
(Form to be used by Prime Contractor, Electrical and Instrumentation Subcontractors)

Bidder Company Name: C.C. Control Corp.

PROJECT NAME: Seacoast Utility Authority Repump Facility Modifications

Owner/Reference Name: Seacoast Utility Authority

Owner/Reference Contact:	<u>Rim Bishop</u>	<u>Utility Director</u>
	Name	Title
	<u>(561) 627-2900</u>	<u>rbishop@sua.com</u>
	Phone	Email

Project Location: Seacoast Utility Authority

Project Description: Fiber optic Ethernet network, ContoLogix PLC programming, instrumentation and start-up

Was the Bidder Prime Contractor or Subcontractor? Subcontractor

List project scope similarities: ControlLogix PLC programming, Fiber optic terminations, testing
and network start-up.

Project Cost:	Initial Contract Value	\$ <u>650,000.00</u>
	Change Orders	\$ <u>0.00</u>
	Final Contract Price	\$ <u>650,000.00</u>

Explain Reason(s) for Change Orders: N/A

Project Timeline:	Start Date	<u>09/2010</u>
	Contract Time Extension	<u>N/A</u>
	Completion Date	<u>06/2014</u>

Explain Reason(s) for Time Extension: N/A

NOTE: Include additional pages with the same format to list other projects as proof of prior experience. List a minimum of five (5) similar projects for prime contractor.

FAILURE TO COMPLETE THIS FORM MAY RESULT IN THE BID BEING DECLARED NON-RESPONSIVE

REFERENCES AND PRIOR EXPERIENCE
(Form to be used by Prime Contractor, Electrical and Instrumentation Subcontractors)

Bidder Company Name: C.C. Control Corp.

PROJECT NAME: Seacoast Utility Authority Hood Road WTP RO Improvements

Owner/Reference Name: Seacoast Utility Authority

Owner/Reference Contact: Rim Bishop Utility Director
Name Title

(561) 627-2900

Phone

rbishop@sua.com

Email

Project Location: Hood Road WTP / Seacoast Utility Authority

Project Description: ContollLogix PLC programming, Ethernet remote i/o networking and
various process instrumentation

Was the Bidder Prime Contractor or Subcontractor? Subcontractor

List project scope similarities: ControlLogix PLC programming, Fiber optic terminations, testing
and network start-up.

Project Cost:	Initial Contract Value	<u>\$ 2,060,000.00</u>
	Change Orders	<u>\$ 0.00</u>
	Final Contract Price	<u>\$ 2,060,000.00</u>

Explain Reason(s) for Change Orders: N/A

Project Timeline:	Start Date	<u>09/2010</u>
	Contract Time Extension	<u>N/A</u>
	Completion Date	<u>06/2014</u>

Explain Reason(s) for Time Extension: N/A

NOTE: Include additional pages with the same format to list other projects as proof of prior experience. List a minimum of five (5) similar projects for prime contractor.

FAILURE TO COMPLETE THIS FORM MAY RESULT IN THE BID BEING DECLARED NON-RESPONSIVE

REFERENCES AND PRIOR EXPERIENCE
(Form to be used by Prime Contractor, Electrical and Instrumentation Subcontractors)

Bidder Company Name: C.C. Control Corp.

PROJECT NAME: City of Sunrise WWTP Biosolids Management

Owner/Reference Name: City of Sunrise

Owner/Reference Contact:	Roal Small	Chief Operator (Springtree WWTP)
	Name	Title
	(954) 572-2428	rsmall@sunrisefl.gov
	Phone	Email

Project Location: Sawgrass WWTP and Springtree WWTP

Project Description: GE PACSystems Rx3i PLC platform with local I/O expansion.

PLC integration to communicate to new centrifuge PLCs over Ethernet messaging for handshaking and controls.

Was the Bidder Prime Contractor or Subcontractor? Subcontractor

List project scope similarities: Fiber optic terminations, testing and network start-up.

Various instrumentation including magnetic flowmeters, ultrasonic level transmitters, pressure gauges,
pressure switches and pressure diaphragm seals.

Project Cost:	Initial Contract Value	\$ <u>420,000.00</u>
	Change Orders	\$ <u>0.00</u>
	Final Contract Price	\$ <u>420,000.00</u>

Explain Reason(s) for Change Orders: N/A

Project Timeline:	Start Date	<u>10/2013</u>
	Contract Time Extension	<u>N/A</u>
	Completion Date	<u>06/2016</u>

Explain Reason(s) for Time Extension: N/A

NOTE: Include additional pages with the same format to list other projects as proof of prior experience. List a minimum of five (5) similar projects for prime contractor.

FAILURE TO COMPLETE THIS FORM MAY RESULT IN THE BID BEING DECLARED NON-RESPONSIVE

1

REFERENCES AND PRIOR EXPERIENCE
(Form to be used by Prime Contractor, Electrical and Instrumentation Subcontractors)

Bidder Company Name: Edwards Electric Corp.

PROJECT NAME: West Water Treatment Plant Reverse Osmosis Expansion

Owner/Reference Name: City of Miramar

Owner/Reference Contact: Sam Akrouk - Project Manager

Name

Title

954-739-8100

sakrouk@jjkllc.com,

Phone

Email

Project Location: 4100 Flamingo Road, Miramar, FL. 33027

Project Description: See attached Scope of Work.

Was the Bidder Prime Contractor or Subcontractor? Subcontractor

List project scope similarities: Add Switchgear, Panelboards, Disconnects, Transformers, Lighting, Conduit, Wire, Terminations, Grounding, Manholes.

Project Cost:	Initial Contract Value	\$ <u>1,872,768</u>
	Change Orders	\$ <u>0.00</u>
	Final Contract Price	\$ <u>1,872,768</u>

Explain Reason(s) for Change Orders: _____

Project Timeline:	Start Date	<u>January / 2009</u>
	Contract Time Extension	<u>None</u>
	Completion Date	<u>October / 2010</u>

Explain Reason(s) for Time Extension: _____

NOTE: Include additional pages with the same format to list other projects as proof of prior experience. List a minimum of five (5) similar projects for prime contractor.

FAILURE TO COMPLETE THIS FORM MAY RESULT IN THE BID BEING DECLARED NON-RESPONSIVE

Edwards Electric Corp.
INDUSTRIAL ELECTRICAL CONTRACTORS

November 7, 2008

REVISION NO.1

SCOPE OF ELECTRICAL WORK

WEST WATER TREATMENT PLANT

REVERSE OSMOSIS EXPANSION

IFB # 08-012

MPI PROJECT NO.: 4475-009

FOR

CITY OF MIRAMAR, FLORIDA

We propose to provide the following scope of electrical work for the above described project found on the Electrical Drawings and described in Division 16000, pursuant to Plans and Specifications and Addendum No.1 thru 3 prepared by Malcolm Pirnie, Inc. dated September / 2008.

INCLUDED

Furnish and install labor, materials, tools and equipment for the electrical work generally described on the Electrical Drawings and defined in Division 16, as particularly described herein.

Section 16050 General Provisions for Electrical Work - Furnish and install as specified.

Section 16061 Grounding Systems - Furnish and install as specified including Independent Testing.

Section 16062 Lightning Protection System - Furnish and install as specified.

Section 16070 Supporting Systems - Furnish and install as specified.

Section 16075 Electrical Identification - Furnish and install as specified.

Section 16121 Instrumentation Cable - Furnish and install as specified.

Section 16122 600 Volt Cable - Furnish and install as specified.

Section 16131 Rigid Conduit - Furnish and install as specified.

Section 16132 Flexible Conduits - Furnish and install as specified.

Section 16133 Sealed Fittings - Furnish and install as specified.

Section 16134 Expansion/Deflection Fittings - Furnish and install as specified.

Section 16135 Pull, Junction and Terminal Boxes - Furnish and install as specified.

Section 16136 Outlet Boxes - Furnish and install as specified.

Section 16137 Underground Ductbanks - Furnish and install as specified.

Section 16141 Receptacles - Furnish and install as specified.

Section 16142 Snap Switches - Furnish and install as specified.

Section 16143 Disconnect Switches - Furnish and install as specified.

Section 16144 Control Stations - Furnish and install as specified.

Section 16210 Utility Services - Furnish and install as specified. All FP&L Fees are specifically excluded.

Section 16215 Power Distribution System Study - Furnish and install as specified.

Section 16231 Engine Generator Systems - Conduit, wire and terminations to Engine Generator Systems including Generator Switchboard No.1 and No.2 furnished and set by others.

Section 16271 Dry Type Transformers - Furnish and install as specified.

Section 16282 Transient Voltage Surge Suppression - Furnish and install as specified.

Section 16342 Metal Clad Switchgear – There is no Metal Clad Switchgear shown in the Contract Documents and is therefore excluded.

Section 16346 Metal Enclosed Busway - Furnish and install as specified.

Section 16412 Auto Transfer Switches - Conduit, wire and terminations to Auto Transfer Switches furnished and set by others.

Section 16423 Motor Control Centers - Furnish and install as specified including Independent Testing.

Section 16425 Variable Frequency Drives - Furnish and install as specified.

Section 16440 Switchboards - Furnish and install as specified.

Section 16442 Lighting and Distribution Panelboards - Furnish and install as specified.

Trash delivered to an on site receptacle furnished and maintained by others.

Temporary power for One (1) office trailer within 75 feet of a service location, and construction plug boards for small hand tools located within 150 feet of service locations on the site.

EXCLUDED

1. Cutting and patching of roads, sidewalks, concrete and/or asphalt, except as noted in the above inclusions.
2. Dewatering, compaction, density testing, resodding or restoration of disturbed or excavated areas.
3. Hauling away of any contaminated or unwanted material found on site.

4. Items not listed or specifically referenced in the **Included** section.
5. Bonds. They are available for an additional amount.
6. Insurance with limits in excess of \$3 million in forms or descriptions other than those which are standard in the marketplace. Waivers of subrogation.
7. Permits or temporary power unless specifically included above.
8. Housekeeping pads, transformer pads and or other equipment pads.
9. Installation of in-line devices or mechanically activated instruments or devices, or any piping, impulse piping, tubing, and or pneumatic tubing, or any other mechanical or plumbing services.
10. Power company usage fees or in and out fees.
11. Special mounting hardware and or stanchions and supports for equipment furnished by others. All equipment to be furnished by others and terminated by Edwards Electric Corp. is to have all necessary lugging, interconnect wiring, terminal blocks, etc. and junction boxes or connection areas of suitable size for the required terminations, included with the equipment.
12. Painting or coating of any kind.
13. Off loading, lifting and placement of all heavy equipment and materials.
14. Construction Photographs, Video Taping, Reference Points or Professional Land Surveying of any kind.
15. Generator fuel, fuel piping, leak detection system, fuel monitoring system, fuel control panels, fuel inventory alarm switches, exhaust piping, exhaust system connections, penetrations, insulation, louvers, louver modifications if required or main fuel tank.
16. Pump Control Panel, Control Panels, Local Control Panels, Modifications to Existing Control Panels or Local Control Panels, Motors, Instrumentation including Field Devices, TVSS or Stanchions, Pressure Switches, PLC, PLC Programming, Security System, Intercom System, Telephone System, Floats, Solenoids, Pipe Taps, Pipe Saddles, Valves, Sump Pumps, Thermostats, Exhaust Fans, Motor Space Heaters, High Temperature Switches, Vibration Switches, Bollards, Barrier Posts, Air Conditioners, Air Compressors, Blowers, Gauges, Power Factor Correction Capacitors, RTU System including Antennas, Antenna Erection or Anchor Base, Ethernet Cable, Data Highway Cable or Fiber Optic Cable including Panels, Switches or Terminations of any kind.
17. Directional boring of any kind.
18. By-Pass Pumping Electric. If required, please transmit your scope of work and we will offer a price adder.
19. Allowances per Bid Form.

This proposal is subject to a firm commitment within 7 days of bid, subject only to owner award, and a contract in a form acceptable to Edwards Electric Corp., within 60 days of this date, which includes a mutually acceptable schedule that provides reasonable periods of performance for each activity consistent with the contract documents, and monthly payment requests for work in place including materials stored on site.

Please feel free to call if you have any questions or if I can be of any further assistance.

Sincerely Yours,

Tyrone A. Fox
Vice President
Phone 561-683-7066 Ext 208
Fax 561-683-8115
Cell 561-722-9648
Email: tfoxvpeec@aol.com

08063sow

EDWARDS ELECTRIC CORP.

WEB: www.edwardselectric.com

7231 SOUTHERN BLVD., SUITE C-2, WEST PALM BEACH, FL. 33413
561-683-7066 (Phone) 561-683-8115 (Fax) tfoxvpeec@aol.com (E-mail) EC-0001100

REFERENCES AND PRIOR EXPERIENCE
(Form to be used by Prime Contractor, Electrical and Instrumentation Subcontractors)

Bidder Company Name: Edwards Electric Corp.

PROJECT NAME: Anion Exchange Treatment Facility Water Treatment Plant 1A

Owner/Reference Name: Broward County

Owner/Reference Contact: Casey Sullivan - Project Manager

	Name	Title
954-975-0388	csullivan@rjsullivancorp.com,	
Phone	Email	

Project Location: 3701 North State Road 7, Lauderdale Lakes, FL. 33319

Project Description: See attached Scope of Work.

Was the Bidder Prime Contractor or Subcontractor? Subcontractor

List project scope similarities: Add Switchgear, Panelboards, Disconnects, Transformers, Lighting, Conduit, Wire, Terminations, Grounding, Manholes.

Project Cost:	Initial Contract Value	\$ <u>899,893.00</u>
	Change Orders	\$ <u>0.00</u>
	Final Contract Price	\$ <u>899,893.00</u>

Explain Reason(s) for Change Orders: _____

Project Timeline:	Start Date	<u>May / 2009</u>
	Contract Time Extension	<u>None</u>
	Completion Date	<u>October / 2011</u>

Explain Reason(s) for Time Extension: _____

NOTE: Include additional pages with the same format to list other projects as proof of prior experience. List a minimum of five (5) similar projects for prime contractor.

FAILURE TO COMPLETE THIS FORM MAY RESULT IN THE BID BEING DECLARED NON-RESPONSIVE

Edwards Electric Corp.

INDUSTRIAL ELECTRICAL CONTRACTORS

August 5, 2008

SCOPE OF ELECTRICAL WORK

ANION EXCHANGE TREATMENT FACILITY

WATER TREATMENT PLANT 1A

BCWWS PROJECT NO. 9073

BID NO. Y508161CAF

CDM PROJECT NO. 6005-51538

FOR

BROWARD COUNTY, FLORIDA

We propose to provide the following scope of electrical work for the above described project found on the Electrical Drawings and described in Division 16000, pursuant to Plans and Specifications and Addendum No.1 thru 3 prepared by Camp Dresser & McKee, Inc. dated May / 2008.

INCLUDED

Furnish and install labor, materials, tools and equipment for the electrical work generally described on the Electrical Drawings and defined in Division 16, as particularly described herein.

Section 16000 Electrical General Provisions - Furnish and install as specified including Independent Testing and Protective Devices Coordination Study.

Section 16110 Raceways, Boxes, Fittings, and Supports - Furnish and install as specified.

Section 16120 Wires and Cables - Furnish and install as specified.

Section 16121 Medium Voltage Cables - Furnish and install as specified.

Section 16150 Motors - Conduit, wire and terminations to Motors furnished and set by others.

Section 16191 Miscellaneous Equipment - Furnish and install as specified including the Weatherproof Enclosures for the VFD's. See exclusions.

Section 16370 Variable Frequency Drives - Conduit, wire and terminations to Variable Frequency Drives furnished and set by others.

Section 16400 Medium Voltage Transformers - Furnish and install as specified.

Section 16470 Panelboards - Furnish and install as specified.

Section 16480 480 Volt Motor Control Centers - Furnish and install as specified.

Section 16485 Solid State, Reduced Voltage Starters - Furnish and install as specified.

Section 16500 Lighting System - Furnish and install as specified including Spare Hand Lamp.

Section 16600 Underground System - Furnish and install as specified.

Section 16660 Grounding System - Furnish and install as specified.

Section 16670 Static Dissipator Lightning Protection System - Furnish and install as specified.

Section 16900 Concrete Electrical Duct Encasement - Furnish and install as specified.

Trash delivered to an on site receptacle furnished and maintained by others.

Temporary power for One (1) office trailer within 75 feet of a service location, and construction plug boards for small hand tools located within 150 feet of service locations on the site.

EXCLUDED

1. Cutting and patching of roads, sidewalks, concrete and/or asphalt, except as noted in the above inclusions.
2. Dewatering, compaction, density testing, resodding or restoration of disturbed or excavated areas.
3. Hauling away of any contaminated or unwanted material found on site.
4. Items not listed or specifically referenced in the **Included** section.
5. Bonds. They are available for an additional amount.
6. Insurance with limits in excess of \$3 million in forms or descriptions other than those which are standard in the marketplace. Waivers of subrogation.
7. Permits or temporary power unless specifically included above.
8. Housekeeping pads, transformer pads and or other equipment pads.
9. Installation of in-line devices or mechanically activated instruments or devices, or any piping, impulse piping, tubing, and or pneumatic tubing, or any other mechanical or plumbing services.
10. Power company usage fees or in and out fees.
11. Special mounting hardware and or stanchions and supports for equipment furnished by others. All equipment to be furnished by others and terminated by Edwards Electric Corp. is to have all necessary lugging, interconnect wiring, terminal blocks, etc. and junction boxes or connection areas of suitable size for the required terminations, included with the equipment.
12. Painting or coating of any kind.
13. Off loading, lifting and placement of all heavy equipment and materials.
14. Construction Photographs, Video Taping, Reference Points or Professional Land Surveying of any kind.

15. Control Panels, Local Control Panels, Modifications to Existing Control Panels or Local Control Panels, Instrumentation including Field Devices, TVSS or Stanchions, UPS Systems, Emergency Shower Alarm Horn/Light, PLC, PLC Programming, Security System, Intercom System, Telephone System, Floats, Solenoids, Pipe Taps, Pipe Saddles, Valves, Sump Pumps, Thermostats, Exhaust Fans, Motor Space Heaters, High Temperature Switches, Vibration Switches, Bollards, Barrier Posts, Air Conditioners, Air Compressors, Blowers, Gauges, Power Factor Correction Capacitors, RTU System including Antennas, Antenna Erection or Anchor Base, Ethernet Cable, Data Highway Cable or Fiber Optic Cable including Panels, Switches or Terminations of any kind.

16. Directional boring of any kind.

17. The requirements of 16191-2.02 in its entirety.

18. Allowances per Bid Form.

This proposal is subject to a firm commitment within 7 days of bid, subject only to owner award, and a contract in a form acceptable to Edwards Electric Corp., within 60 days of this date, which includes a mutually acceptable schedule that provides reasonable periods of performance for each activity consistent with the contract documents, and monthly payment requests for work in place including materials stored on site.

Please feel free to call if you have any questions or if I can be of any further assistance.

Sincerely Yours,

Tyrone A. Fox
Vice President
Phone 561-683-7066 Ext 208
Fax 561-683-8115
Cell 561-722-9648
Email: tfoxvpeec@aol.com

08043sow

EDWARDS ELECTRIC CORP.

WEB: www.edwardselectric.com

7231 SOUTHERN BLVD., SUITE C-2, WEST PALM BEACH, FL. 33413
561-683-7066 (Phone) 561-683-8115 (Fax) tfoxvpeec@aol.com (E-mail) EC-0001100

3

REFERENCES AND PRIOR EXPERIENCE
(Form to be used by Prime Contractor, Electrical and Instrumentation Subcontractors)

Bidder Company Name: Edwards Electric Corp.

PROJECT NAME: Sawgrass Water Treatment Plant Improvements

Owner/Reference Name: City of Sunrise

Owner/Reference Contact: Michael Brandao - Project Manager

Name

Title

954-587-0520

mbrandao@prim.com,

Phone

Email

Project Location: 14150 NW 8th St., Sunrise, FL. 33325

Project Description: See attached Scope of Work.

Was the Bidder Prime Contractor or Subcontractor? Subcontractor

List project scope similarities: Add Switchgear, Panelboards, Disconnects, Transformers, Lighting, Conduit, Wire, Terminations, Grounding, Manholes.

Project Cost:	Initial Contract Value	<u>\$ 1,187,000</u>
	Change Orders	<u>\$ 0.00</u>
	Final Contract Price	<u>\$ 1,187,000</u>

Explain Reason(s) for Change Orders: _____

Project Timeline:	Start Date	<u>February / 2013</u>
	Contract Time Extension	<u>None</u>
	Completion Date	<u>June / 2014</u>

Explain Reason(s) for Time Extension: _____

NOTE: Include additional pages with the same format to list other projects as proof of prior experience. List a minimum of five (5) similar projects for prime contractor.

FAILURE TO COMPLETE THIS FORM MAY RESULT IN THE BID BEING DECLARED NON-RESPONSIVE

Edwards Electric Corp.

INDUSTRIAL ELECTRICAL CONTRACTORS

September 27, 2012

SCOPE OF ELECTRICAL WORK

SAWGRASS WATER TREATMENT IMPROVEMENTS

PROJECT AGREEMENT PA NO. 11-002-CH

CITY PROJECT NO. 501SG & 5011SG

BID NO. 12(39) 12-19-09-27-R

CH2M HILL PROJECT NO. 398232

CITY OF SUNRISE, FLORIDA

We propose to provide the following scope of electrical work for the above described project found on the Electrical Drawings and described in Division 16000, pursuant to Plans and Specifications and Addendum No.1 prepared by CH2M Hill dated August / 2012.

INCLUDED

Furnish and install labor, materials, tools and equipment for the electrical work generally described on the Electrical Drawings and defined in Division 16, as particularly described herein.

Section 26 05 02 Basic Electrical Requirements - Furnish and install as specified.

Section 26 05 04 Basic Electrical Materials and Methods - Furnish and install as specified including Spare Parts and Switchboard Matting.

Section 26 05 05 Conductors - Furnish and install as specified.

Section 26 05 26 Grounding and Bonding for Electrical Systems - Furnish and install as specified.

Section 26 05 33 Raceway and Boxes - Furnish and install as specified including Conduit Layout Drawings and Precast Manholes.

Section 26 05 70 Electrical Systems Analysis - Furnish and install as specified including ARC Flash Study and Warning Labels.

Section 26 08 00 Commissioning of Electrical Systems - Furnish and install as specified including Independent Electrical Testing.

Section 26 20 00 Low-Voltage AC Induction Motors - We will furnish conduit, wire and terminations only as specified. The Motors are furnished and set by others.

Section 26 22 00 Low-Voltage Transformers - Furnish and install as specified.

Section 26 24 16 Panelboards - Furnish and install as specified.

Section 26 24 19 Low-Voltage Motor Control - Furnish and install as specified.

Section 26 27 26 Wiring Devices - Furnish and install as specified.

Section 26 43 00 Transient Voltage Suppression - Furnish and install as specified.

Site Lighting Drawings 10-E-206, 10-E-207 and 10-E-208 - Furnish and install Site Lighting Complete including Certified Wind Load Calculations and Light Pole Anchor Bases as specified.

Russelectric Low Voltage Main Switchgear Modifications Drawing 80-E-601 - Furnish and install as specified pursuant to Russelectric Inc. Quotation No.Q37219 Dated 9/26/12 Scope Attached.

Electrical Permit.

Trash delivered to an on site receptacle furnished and maintained by others.

Temporary power for construction plug boards for small hand tools located within 150 feet of service locations on the site. Please advise if your Temporary Scope needs exceed this and we can give you an Adder.

EXCLUDED

1. Cutting and patching of roads, sidewalks, concrete and/or asphalt, except as noted in the above inclusions.
2. Dewatering, compaction, density testing, resodding or restoration of disturbed or excavated areas.
3. Hauling away of any contaminated or unwanted material found on site.
4. Items not listed or specifically referenced in the **Included** section.
5. Bonds. They are available for an additional amount.
6. Insurance with limits in excess of \$3 million in forms or descriptions other than those which are standard in the marketplace. Waivers of subrogation.
7. Permits or temporary power unless specifically included above.
8. Housekeeping pads, transformer pads and or other equipment pads.
9. Installation of in-line devices or mechanically activated instruments or devices, or any piping, impulse piping, tubing, and or pneumatic tubing, or any other mechanical or plumbing services.
10. Power company usage fees or in and out fees.
11. Special mounting hardware and or stanchions and supports for equipment furnished by others. All equipment to be furnished by others and terminated by Edwards Electric Corp. is to have all necessary lugging, interconnect wiring, terminal blocks, etc. and junction boxes or connection areas of suitable size for the required terminations, included with the equipment.
12. Painting or coating of any kind.
13. Off loading, lifting and placement of all heavy equipment and materials.

14. Construction Photographs, Video Taping, Reference Points or Professional Land Surveying of any kind.
15. Fiber Optic Communication System, Gai-Tronics Intercom System, Repair or Rehabilitation of any existing Intercom Components, Access Gate System, Gate Security System or Card Reader System including Pedestals or Tyco Security System.
16. Control Panels, Local Control Panels, Modifications to Existing Control Panels or Local Control Panels, Instrumentation including (Field Devices, TVSS or Stanchions), Computer Console Protective Panels, PLC, PLC Programming, Electric Actuators, Cathodic Protection System, Gate Operators, Gate Position Sensors, Level Sensors, Door Switches, Intercom System, Communication System, Telephone System, Fence work of any kind, Floats, Solenoids, Pipe Taps, Pipe Saddles, Valves, Pumps, Sump Pump System, Thermostats, Exhaust Fans, Motor Space Heaters, High Temperature Switches, Vibration Switches, Vibration Testing of any kind, Limit Switches, Level Switches, Heat Trace System, Hatches, Bollards, Barrier Posts, Air Conditioners, Air Compressors, Blowers, Gauges, Power Factor Correction Capacitors, RTU System including (Battery, Polyphasers, Antennas, Antenna Erection or Anchor Base), Ethernet Cable, Data Highway Cable or Fiber Optic Cable including Panels, Switches or Terminations of any kind.
17. Directional boring, if required, of any kind.
18. Allowances or Contingencies per Bid Form, Contract Drawings or Specifications.
19. Provisions for consequential damages of any kind.

This proposal is subject to a contract in a form acceptable to Edwards Electric Corp. that includes a mutually acceptable schedule that provides reasonable periods of performance for each activity utilizing a forty hour work week without overtime, or work at night, on weekends, or on holidays, a standard 1 year warranty, and monthly payment requests for work in place including materials stored on site.

Please feel free to call if you have any questions or if I can be of any further assistance.

Sincerely Yours,

Tyrone A. Fox
Vice President
Phone 561-683-7066 Ext 208
Fax 561-683-8115
Cell 561-722-9648
Email: tfoxvpeec@aol.com
FEID NO. 65-0130700

9391sow

4

REFERENCES AND PRIOR EXPERIENCE
(Form to be used by Prime Contractor, Electrical and Instrumentation Subcontractors)

Bidder Company Name: Edwards Electric Corp.

PROJECT NAME: Solid Waste Authoprity Power Block

Owner/Reference Name: West Palm Beach

Owner/Reference Contact: Bill Rahrig - Project Manager

Name

Title

561-262-6148

rahrigwj@cdmsmith.com,

Phone

Email

Project Location: 6801 North Jog Road, West Palm Beach, FL. 33412

Project Description: See attached Scope of Work.

Was the Bidder Prime Contractor or Subcontractor? Subcontractor

List project scope similarities: Add Switchgear, Panelboards, Disconnects, Transformers, Lighting, Conduit, Wire, Terminations, Grounding, Manholes.

Project Cost:	Initial Contract Value	<u>\$ 6,421,000</u>
	Change Orders	<u>\$ 0.00</u>
	Final Contract Price	<u>\$ 6,421,000</u>

Explain Reason(s) for Change Orders: _____

Project Timeline:	Start Date	<u>October / 2013</u>
	Contract Time Extension	<u>None</u>
	Completion Date	<u>November / 2015</u>

Explain Reason(s) for Time Extension: _____

NOTE: Include additional pages with the same format to list other projects as proof of prior experience. List a minimum of five (5) similar projects for prime contractor.

FAILURE TO COMPLETE THIS FORM MAY RESULT IN THE BID BEING DECLARED NON-RESPONSIVE

KBR	ELECTRICAL CONSTRUCTION INSTALLATION	TECHNICAL SPECIFICATION
		E02-1E-D408
REV: 1	SOLID WASTE AUTHORITY OF PALM BEACH COUNTY – PBREF NO. 2 PROJECT WEST PALM BEACH, FL PREPARED BY BE&K ENGINEERING COMPANY, LLC A KBR Company 2000 International Park Dr, Birmingham, AL 35243	PAGE 5 OF 41

2.5 Electrical equipment, apparatus, and materials furnished under this specification shall be new and suitable for the intended application whether installed indoors or outdoors and whether installed in dry, wet, or corrosive atmosphere. Environments typical of industrial complexes shall be expected. Where particular types or brand names are solely specified, it is understood that there will be no substitutions except with the written approval of the Owner's representative.

2.6 Materials or equipment required by the NEC to be listed, labeled, identified, or approved shall be UL labeled or have written Owner approval.

3. DETAILED REQUIREMENTS OF INSTALLATION

3.1 General Provisions

3.1.1 The electrical power system for the facility will consist of an incoming utility tie at 138 kV that will be transformed to the primary plant utilization voltage of 13.8 kV for plant distribution and connection of a 100 MW Generator. The primary plant distribution voltage of 13.8 kV will be transformed to 4160 Volts and 480 Volts. The 480 Volt system will be transformed to 480/277 Volts and/or 208/120 Volts with transformers and panel boards for lighting and power, and other systems (communications, control, etc.) as specified and indicated on applicable drawings. There will also be a 480 Volt to a 208/120-volt UPS system (or systems as required) with panel boards to serve critical loads as specified and indicated on applicable drawings. There will also be a 480 Volt Emergency Generator to supply critical 480 Volt loads and a 125 Volt DC system associated with the station battery for specific 125 Volt DC loads.

3.1.2 The work shall include complete testing (as described herein) of equipment and wiring at the completion of the work and making connection changes or adjustments necessary for the proper functioning of the system and equipment. Power distribution, lighting, control, and miscellaneous systems shall be properly adjusted and in working order at the time of final acceptance.

3.1.3 The Contractor shall be responsible for reclaiming motors from storage, transportation to final location, and placement on base. For direct-coupled applications, the alignment, bolting down, and doweling shall be by others. For belted service motors, the Contractor shall install the slide rail base, belts, and belt sheaves. The proper tensioning of the belts will be the responsibility of the Contractor. Installation of belt or coupling guards will be by others.

3.1.4 Manufacturer's instructions for installation of electrical equipment shall be fully complied with. In the event that conflicts arise between the manufacturer's instructions and this specification or the applicable design drawings, the Engineer shall be contacted in writing for resolution prior to the actual installation.

3.1.5 Equipment and control devices shall be supported independently of conduit connections. Panels or cabinets shall not be mounted directly in contact with the structure. Except where mounted on machine or pedestal, control devices and metal enclosures shall be bolted to steel channel (unistrut) or steel plate supports attached to walls with expansion bolts. In general, lighting panels and service and distribution panels shall have cabinets mounted so that the distance from the floor to the center of top breaker or fuse will not exceed 6-ft 6-in. Electrical equipment and devices not covered by the above, such as miscellaneous switches, thermostats, duct switches, temperature switches, floats, photoelectric devices and similar electrical devices, shall be located and set as required for proper operation of the equipment.

3.1.6 Taping, splicing, and termination materials shall be furnished by the Contractor. All materials and their applications shall be in accordance with the cable manufacturer's instructions.

5

REFERENCES AND PRIOR EXPERIENCE
(Form to be used by Prime Contractor, Electrical and Instrumentation Subcontractors)

Bidder Company Name: Edwards Electric Corp.

PROJECT NAME: Sawgrass Wastewater Treatment Plant

Owner/Reference Name: City of Sunrise

Owner/Reference Contact: Michael Brandao - Project Manager

Name

Title

954-587-0520

mbrandao@prim.com,

Phone

Email

Project Location: 14150 NW 8th St., Sunrise, FL. 33325

Project Description: See attached Scope of Work.

Was the Bidder Prime Contractor or Subcontractor? Subcontractor

List project scope similarities: Add Switchgear, Panelboards, Disconnects, Transformers, Lighting, Conduit,
Wire, Terminations, Grounding, Manholes.

Project Cost:	Initial Contract Value	<u>\$ 2,383,000</u>
	Change Orders	<u>\$ 0.00</u>
	Final Contract Price	<u>\$ 2,383,000</u>

Explain Reason(s) for Change Orders: _____

Project Timeline: Start Date December / 2015

Contract Time Extension None

Completion Date November / 2018

Explain Reason(s) for Time Extension: _____

NOTE: Include additional pages with the same format to list other projects as proof of prior experience. List a minimum of five (5) similar projects for prime contractor.

FAILURE TO COMPLETE THIS FORM MAY RESULT IN THE BID BEING DECLARED NON-RESPONSIVE

Edwards Electric Corp.

INDUSTRIAL ELECTRICAL CONTRACTORS

June 17, 2015

REVISION NO.1

SCOPE OF ELECTRICAL WORK

SAWGRASS WWTP

REUSE FACILITY – PHASE I

CITY PROJECT NO. 025017SG

PROJECT AGREEMENT NO. 12-016-BC

BID NO. 15-05-11-HR

CITY OF SUNRISE, FLORIDA

We propose to provide the following scope of electrical work for the above described project found on the Electrical Drawings and described in Division 16000, pursuant to Plans and Specifications prepared by Brown and Caldwell as follows:

Plans 000-E-01 thru 780-E-61 dated March / 2015

Specifications dated April / 2015

Addendum No.1 dated 5/13/15

Addendum No.2 dated 5/20/15

Addendum No.3 dated 5/27/15

Addendum No.4 dated 6/2/15

Addendum No.5 dated 6/11/15

INCLUDED

Furnish and install labor, materials, tools and equipment for the electrical work generally described on the Electrical Drawings and defined in Division 16, as particularly described herein.

Section 16000 General Requirements for Electrical Work – Furnish and install as specified including:

Temporary Lighting and Power per 01500

Temporary Lamps and Ballasts per 01560

Temporary power for Two (2) office trailers within 75 feet of a service location, and construction plug boards for small hand tools located within 150 feet of service locations on the site per 01590.

Special Monitoring for Electrical Switchgear that we furnish per 01605-3.0.G

Equipment and System Performance and Operational Testing for Electrical per 01660

Training per 01664

Operation and Maintenance Information per 01730

Protective Matting per 16000-2.07

Spare Fuses per 16000-3.01.E

Testing per 16000-3.02

Temporary Power for the Buildings.

Temporary Power for the Trailer Complex.

We will furnish a 75HP Dewatering Pump Feeder. This does not include Controls or Starting Equipment of any kind.

Section 16030 Electrical Acceptance Testing – Furnish and install as specified.

Section 16110 Raceways, Boxes and Supports – Furnish and install as specified including:

Manholes per 2.02.C

Handholes per 2.02.D

Manhole and Handhole Cable Supports per 2.02.E

Concrete Encased Duct Banks (Electrical) per 2.04

Cable Tray per 3.04

Section 16120 600 Volt Conductors, Wire and Cable – Furnish and install as specified.

Section 16140 Wiring Devices – Furnish and install as specified.

Section 16155 Individual Motor Starters – Furnish and install as specified.

Section 16175 Miscellaneous Electrical Devices – Furnish and install as specified.

Section 16176 Local Control Panels – We will set in place and install conduit, wire and terminations only to Local Control Panels. All Local Control Panels are furnished by others.

Section 16260 Automatic Transfer Switches – Furnish and install as specified.

Section 16310 Low Voltage Switchgear – Furnish and install as specified.

Section 16311 Low Voltage Switchboards – Furnish and install as specified.

Section 16431 Arc Flash Analysis, Short Circuit Study, and Protective Device Coordination Report – Furnish and install as specified.

Section 16440 Instrument Transformers, Meters, Switches and Accessories – Furnish and install as specified.

Section 16445 Surge Protective Devices – Furnish and install as specified including:

Training per 3.03

Section 16446 Lightning Protection System – Furnish and install as specified.

Section 16450 Grounding System – Furnish and install as specified.

Section 16460 Dry-Type Transformers – Furnish and install as specified.

Section 16470 Lighting and Power Distribution Panelboards – Furnish and install as specified.

Section 16500 Luminaires – Furnish and install as specified including:

Spare Parts per 1.04

Light Pole Bases per Drawing 000-E-06 / Detail R

Section 16850 Fire Alarm System – Furnish and install as specified.

Section 16920 600 Volt Motor Control Centers – Furnish and install as specified including:

Adjustable Frequency Drives (Mounted in MCC) per 2.14

Spare Parts per 2.16

Electrical Permit Coordination. Permit paid for by others.

Trash delivered to an onsite receptacle furnished and maintained by others.

EXCLUDED

1. Cutting and patching of roads, sidewalks, concrete and/or asphalt, except as noted in the above inclusions.
2. Dewatering, compaction, density testing, resodding or restoration of disturbed or excavated areas including furnishing New or Replacement of any Sub-Base, Base Rock or Road Rock.
3. Hauling away of any contaminated or unwanted material found on site.
4. Items not listed or specifically referenced in the **Included** section.
5. Bonds. They are available for an additional amount.
6. Insurance with limits in excess of \$3 million in forms or descriptions other than those which are standard in the marketplace. Waivers of subrogation.
7. Permits or temporary power unless specifically listed as Included above.
8. Housekeeping pads, transformer pads and or other equipment pads.
9. Installation of in-line devices or mechanically activated instruments or devices, or any piping, impulse piping, tubing, and or pneumatic tubing, or any other mechanical or plumbing services.
10. Power company usage fees or in and out fees, FPL fees of any kind.
11. Special mounting hardware and or stanchions and supports for equipment furnished by others. All equipment to be furnished by others and terminated by Edwards Electric Corp. is to have all necessary lugging, interconnect wiring, terminal blocks, etc. and junction boxes or connection areas of suitable size for the required terminations, included with the equipment.
12. Painting or coating of any kind.
13. Off loading, lifting and placement of all heavy equipment and materials.
14. Construction Photographs, Video Taping, Reference Points or Professional Land Surveying of any kind.
15. Fence work of any kind.
16. Control Panels, Local Control Panels, Modifications to Existing Control Panels or Local Control Panels.
17. Instrumentation including Field Devices, TVSS, Stanchions or Sunshields, PLC, PLC Local Control Panels, PLC Programming.
18. Electric Motors, Electric Actuators, Level Sensors, Door Switches, Floats, Solenoids, Pipe Taps, Pipe Saddles, Valves, Pumps, Sump Pumps, Thermostats, Exhaust Fans, Motor Space Heaters, High Temperature Switches, Vibration Switches, Vibration Sensors, Vibration Testing of any kind, Emergency Eyewash / Shower Alarm Stations, Limit Switches, Level Switches, Leak Detection System, Heat Trace System, Hatches, Bollards, Barrier Posts, Air Conditioners, Air Compressors, Blowers, Gauges or Power Factor Correction Capacitors.
19. RTU System including Antenna, Antenna Erection or Anchor Base.
20. Data Highway Cable, Data-Link Cable or Fiber Optic Cable System of any kind including Fiber Optic Cable, Panels, Splice Boxes, Switches, Terminations or Testing.
21. Intercom System, Communication System, Telephone System, Security System, Camera System, Access Gate System, Gate Operators, Gate Position Sensors or Card Reader System including Pedestals.
22. Directional boring, if required, of any kind.
23. Allowances or Contingencies per Bid Form, Specifications or Plans unless specifically listed as Included above.
24. Provisions for consequential damages of any kind.
25. Restoration of Improvements per 01700.
26. Variable Frequency Drives per 11069.
27. All Standard Support Details as shown on Drawing 000-1-51.
28. All HVAC control wiring not shown on the Electrical Drawings.
29. Fire/Smoke Dampers not shown on the Electrical Drawings.
30. Concrete encasement of individual conduits under all slabs including the Chemical Storage Area Slab.
31. The FPL Primary Conduit and Wire are furnished by others.

This proposal is subject to a contract in a form acceptable to Edwards Electric Corp. that includes a mutually acceptable schedule that provides reasonable periods of performance for each activity utilizing a forty hour work week without overtime, or work at night, on weekends, or on holidays, **a standard 1 year warranty after date of Final Owner Acceptance**, and monthly payment requests for work in place including materials stored on site.

Please feel free to call if you have any questions or if I can be of any further assistance.

Sincerely Yours,

Tyrone A. Fox
Vice President
Phone 561-683-7066 Ext 208
Fax 561-683-8115
Cell 561-722-9648
Email: tfoxvpeec@aol.com
FEID NO. 65-0130700
License No. EC-0001100

11319sow

EDWARDS ELECTRIC CORP.

WEB: www.edwardselectric.com

7231 SOUTHERN BLVD., SUITE C-2, WEST PALM BEACH, FL. 33413
561-683-7066 (Phone) 561-683-8115 (Fax) tfoxvpeec@aol.com (E-mail) EC-0001100