



Change Order

No. 8

PROJECT: 2017 WTP Renewal and Replacement

DATE OF ISSUANCE:

OWNER: Village of Wellington

OWNER'S PROJECT NO.: CUT17012

CONTRACTOR: Weiss Construction Company of Florida, LLC

You are directed to make the following changes in the Contract Documents.

Description: Increase Contract Price for the Procurement of Additional Equipment that will be purchased Owner Direct and installed by Owner

Purpose:

- | | | |
|--|----|------------|
| 1. Micron Filter 8- HC Warner Quotation 5845 | \$ | 37,535.84 |
| 2. High Pressure Pump 8 - Afton Quote RS-20-1035 RT Rev 2 | \$ | 220,507.74 |
| 3. High Pressure Variable Speed Drive 8-Schneider Quote Q2C41843 | \$ | 84,944.34 |

CHANGE IN CONTRACT PRICE

CHANGE IN CONTRACT TIME

Original Contract Price

\$17,005,300.00

Original Contract Time

1-Aug-20
days or date

Previous Change Order No. 1 to No. 7

(\$3,763,365.48)

Net change from previous Change Orders

0
days

Contract Price prior to this Change Order

\$13,241,934.52

Contract Time prior to this Change Order

15-Sep-20
days or date

Net Increase of this Change Order

\$342,987.92

Net increase of this Change Order

0
days

Contract Price with all approved Change Orders

\$13,584,922.44

Contract Time with all approved Change Orders

15-Sep-20
days or date

APPROVED:

by _____

Assistant Village Manager

APPROVED:

by _____

Utility Director

APPROVED:

by _____

Contractor



H. C. WARNER, INC.
2970 MERCURY ROAD
JACKSONVILLE, FL 32207(home office)

800-874-8608 Toll Free
904-737-9411 Phone
904-731-5004 Fax

www.hcwarner-filter.com

QUOTATION

Date	Estimate #
3/30/2020	5845

To:	Account #	1115101	Ship To
VILLAGE OF WELLINGTON 12300 WEST FOREST HILL BLVD. WELLINGTON, FL 33414 kberroteran@wellingtonfl.gov			VILLAGE OF WELLINGTON 1100 WELLINGTON TRACE WELLINGTON, FL 33414 USA FL-PAL

Quote Expires	Terms	Ship Via	FOB	Quoted by:
5/29/2020	Net 30	MOTOR FREIGHT	SP, FNA, PPA	CECIL BATY

Item (PC)	Description - Lead time ARO	Quantity	U/M	Unit Price	Total
6LMP176H312FK1-WEL...	Model No. 6RO176H-3-12FK1 manufactured by Wessels Company identical to Parker Model No. 6LMP176H-3-12FK1. ASME Code design, U Stamp, 316L Stainless Steel construction, Horizontal mounting, 12" ANSI 150# RFSO Flanged Inlet & Outlet connections, (2) 3/4" FNPT 3000# Vent connections, (2) 1/2" FNPT 3000# Gauge connections, (2) FNPT 3000# Drain connections (clean & dirty) Swingbolt style closure with Buna-N o-ring seal, Mechanical coverlift davit assembly. Cartridge alignment plate, vessel saddle supports, Glass bead blast finish, pickled & passivated. •Material sourcing worldwide unrestricted •Wessels standard electronic vessel documentation •Drawing for approval to be provided upon receipt of PO •Vessel to be a mirror image of Wessels 118-1079 as previously provided •For use with a qty. (176) Parker HFT1M30A filter cartridges, 2.5 in. O.D. x 30 in. L, DOE or 222/SOE (cartridges not included) Shipment: (10) weeks after receipt of approval to proceed	1	ea	35,264.00	35,264.00T

Unless otherwise noted, the quantity above and price are per individual piece.
F.O.B.: Shipping point - Freight charges Collect to invoice(prepay & add upon request).
Lead time: quoted manufacture time-subject to availability.
Transit time: Additional standard shipping time beyond lead time.

Sales Tax..

Total

(Freight not included unless otherwise specified)
THANK YOU FOR THE OPPORTUNITY TO PROVIDE THIS QUOTATION!



H. C. WARNER, INC.
2970 MERCURY ROAD
JACKSONVILLE, FL 32207(home office)

800-874-8608 Toll Free
904-737-9411 Phone
904-731-5004 Fax

www.hcwarner-filter.com

QUOTATION

Date	Estimate #
3/30/2020	5845

To:	Account #	1115101
VILLAGE OF WELLINGTON 12300 WEST FOREST HILL BLVD. WELLINGTON, FL 33414 kberroteran@wellingtonfl.gov		

Ship To
VILLAGE OF WELLINGTON 1100 WELLINGTON TRACE WELLINGTON, FL 33414 USA FL-PAL

Quote Expires	Terms	Ship Via	FOB	Quoted by:
5/29/2020	Net 30	MOTOR FREIGHT	SP, FNA, PPA	CECIL BATY

Item (PC)	Description - Lead time ARO	Quantity	U/M	Unit Price	Total
See Description for part nu...	Documentation: \$100.00 (Net Each) for electronic vessel document book Includes: •Final assembly drawings •ASME code calculations •U-1A form •IOM (installation/operating manual) •Mill test reports •Name plate facsimile •Hydro test report •Spare parts list	1	ea	100.00	100.00T
	Sales Tax Discretionary			50.00	50.00
	Eric Delisle Project Manager PWC, LLC. 5256 Summerlin Commons Way Suite 203 Bldg #2				
					\$2,171.84

Unless otherwise noted, the quantity above and price are per individual piece.
F.O.B.: Shipping point - Freight charges Collect to invoice(prepay & add upon request).
Lead time: quoted manufacture time-subject to availability.
Transit time: Additional standard shipping time beyond lead time.

Sales Tax.. ~~\$2,121.84~~

Total \$37,535.84

(Freight not included unless otherwise specified)
THANK YOU FOR THE OPPORTUNITY TO PROVIDE THIS QUOTATION!

April 9, 2020

Village of Wellington

Afton RS-20-1035-RT Rev 2

R/O Feed Pumps –Modification TO SN 53206

Afton 10x12x14 - 3 stage Model MPV complete with 250 HP, 1800 RPM, VFD Duty, WPI motor. Materials will be 316L SS head, barrel, bowls, impellers and impeller wear rings, and 316SS shafting. Bowl wear rings and bearings will be babbitted carbon. Mechanical seal will be Crane 8B1 seal with 316L SS gland, sleeve and drive collar. We have included structural analysis, lateral and torsional analysis, hydrostatic test of head and barrel, performance and vibration testing, freight to site and service technician for start-up assistance in our offering.

Afton Model MPV 10x12x14 – 3 Pump: \$207,979.00

Florida State Sales Tax (6%): \$12,478.74

Palm Beach County Sales Tax (1% of first \$5,000): \$50.00

Total Price with Sales Tax Included: \$220,507.74 each

This proposal is valid for sixty (60) days from today. Delivery is as stated above after receipt of award or letter of intent. Submittal drawings will be available 10 weeks ARO.

Warranty is F.O.B. Afton factory Houston, TX. Expenses involved in a warranty situation for pump/motor removal, transportation and re-installation are by the contractor/owner.

Taxes are not included in the price and are to be paid directly by the buyer.

General

Items not included: VFD, testing with VFD, anchor bolts.

	Vertical Turbine Pumps Village of Wellington		AFTON QUOTE NUMBER RS-20-1035-RT	
			Revision 1	Date 30 March 20
			Page 1 of 1	

PENINSULAR ELECTRIC DISTRIBUTORS, INC.

MEMBER
IMARK GROUP

1301 Old Okeechobee Road
West Palm Beach, FL 33401
Phone: (561) 832-1626 / (800) 842-6816
FAX: (561) 832-2108

MEMBER
NAED

CUSTOMER: Gilmore Electric
JOB NAME: Wellington WTP
ADDRESS: Att: Steve

DATE: 4/9/2020
PO #: _____

ITEM	QUANTITY	MANUFACTURER	CATALOG NUMBER	UNIT	PER	TOTAL
1	1	SQD	Model 6 MCC VFD Back Pan w/ Cable		E	-
	-		Connection rated to 300HP @ 480v			
	-		Per the attached Bill of Material			
2	1	SQD	MAPG0403D MTE Matrix AP Adaptive		E	-
	-		Passive Harmomic Filter N1-2, 480V			
	-		403Amps			
3	1	SQD	HOA Switch		E	-
4	1	SQD	Day of Startup		E	-
5	1	Misc	Lot Price Items 1 Thru 4	80,089.00	E	80,089.00
	-					
	-					
	-					
	-					
	-					
	-					
	-					
	-					
	-					
	-					
	-					
	-					
	-					
	-					
	-					
	-					
	-					
	-			Subtotal		\$80,089.00

	Tax	\$ 4,855.34
By: <i>Edward Reed</i>	TOTAL:	\$84,944.34



Wellington WTP
MCC1002 VFD Retrofill
Q2C 41843957

1 - Schneider Electric Replacement

Model 6 Series low voltage MCC
Variable Torque VFD Back Pan w/Cable Connection
Rated To 300HP @ 480V Heavy Duty
With:
New Door w/Rotary Type Breaker Operator
Vent Fan
Powerpact 3 Pole L-Frame Circuit Breaker, 5.3A LSI
Rated 65kA @ 480V
ATV630 Type C25N4 VFD (Variable Torque)
Controls: Door Mounted Key Pad, HOA, POT, ETM
CPT: Type TF 480-120V w/Fuse Protection
Pilots: 1-Red, 1-Yellow
(3) Control Relay
Aux Contacts: Standard
Reset Button: Door Mounted
Wiring: 1B
Control Wire: 16 AWG
Terminal Blocks: Standard
Approx. Section Dimensions: 72"H x 40"W
Type: NEMA 1
Cable & Lugs Included

1 - MAPG0403D MTE Matrix AP Adaptive Passive Harmonic Filter, NEMA 1 - 2, 480V 60 Hertz, 403 Amps

1 – HOA Switch

1 – Day of startup