







The Village of Wellington

Monopole Site Upgrade Proposal

Customer: The Village of Wellington

12300 Forest Hill Blvd Wellington, FL 33414 Attn: Accounts payable Phone: 954-357-6082

Email: AccountsPayable@broward.org

Ship to: Village of Wellington MUNICIPAL COMPLEX 12300 Forest Hill Blvd

Village of Wellington, Florida 33414

Attn: William Silliman Office: 561-753-5265

Email: wsilliman@wellingtonfl.gov

Rep #: 641 Date: 5/19/2021

Acct.Rep: Brennan Wartmann

Good Thru: 6/19/2021 Delivery: 45 Days

Pricing Per Broward County Contract:

TEC2112490A1

			L			
Quantity	Model #	Description	MSRP	R1DSC	Unit/DSC	Total
3	AAR10QCGANQ1AN	Motorola SLR 5700 Base Radio	\$3,694.00	20%DSC	\$2,955.20	\$8,865.60
3	XUFIP0001	UHF Duplexer - Untuned 440-480 MHz	\$410.00	20%DSC	\$328.00	\$984.00
3	0112004B04	N - Type Male to N - Type Male 24"	\$124.63	20%DSC	\$99.70	\$299.11
3	0112004U04	N - Type Male to BNC Male 24"	\$79.20	20%DSC	\$63.36	\$190.08
3	HKLN4427*	Capacity Plus Repeater License	\$1,925.00	20%DSC	\$1,540.00	\$4,620.00
1	DSJ9782	HP Procurve 2530-24 Ethernet Switch	\$356.00	20%DSC	\$284.80	\$284.80
3	HKVN4205*	Data Network Application Interface (IP Wireline Data Gateway) GPS	\$866.00	20%DSC	\$692.80	\$2,078.40
3	HKVN4206*	Voice Network Application Interface (IP Wireline Voice Gateway) TRBOnet	\$289.00	20%DSC	\$231.20	\$693.60
3	T65143	Antenna - 450-470 MHz 6.6/7.8dB Exposed Dipole Omni - N Male	\$1,075.00	20%DSC	\$860.00	\$2,580.00
3	PMLE4548	Rack Mount Duplexer/Filter Enclosure Kit (includes mounting screws)	\$320.00	20%DSC	\$256.00	\$768.00
1	T579662	SmartRack 10U Wall-Mount Rack Enclosure Cabinet - equipment up to 20.5 in. deep	\$559.80	20%DSC	\$447.84	\$447.84
1	KIRMS General SOW and Equipment	Installation of Tri Chain Mount on Tower. Installation of (3) DB408 antennas, (3) runs of 1/2" cabling with associated hardware. (3) Polyphasers. Installation of Wellington provided boxes onto Wall. Install ground bar on to existing ground ring. Installation of conduit from monopole, up wall to box by others. Polyphaser mounted inside box, Imr400 jumpers ran inside from polyphaser to equipment from box. <i>Exclusions: Any electrical work to power box, conduit installation, wall penetration, Permits and Engineering</i> .			\$15,700.00	\$15,700.00
20	R1 ENGINEER	Motorola Certified Service Center - RF Engineer Hourly Bill			\$237.00	\$4,740.00
16	R1 TECH	Motorola Certified Service Center - RF Technician 2 Techs 1 Day			\$186.00	\$2,976.00
	I	Cancelled orders subject to a 20% restocking fee.		EQUIPMENT TOTAL		\$45,227.43
				TRANS	PORTATION	N/a

Terms:	20% At order, 60% at delivery, 20% Final Acceptance.
PO:	
Approved By:	
Date	



Sales Tax

TOTAL

EXEMPT

\$45,227.43